




Graduation Project





# Project Construction Management

## Supervisors

Assoc. Dr. Dina Tobbala

Eng. Sameh Makram





**Nile Higher Institute for  
Engineering & Technology**



**Department of Civil  
Engineering**

## **“Construction Project Management”**

**”مشروع ادارة مشروعات التشييد”**

### **Supervisors**

**Assoc. Prof. Dina Tobbala**

“Associate Professor at Civil Department, Nile Higher  
Institute for Engineering and Technology, Mansoura”

**Eng. Sameh Makram**

“Teaching Assistant at Civil Department, Nile Higher  
Institute for Engineering and Technology, Mansoura”

Dean

**Prof. Ahmed Refat**

“Professor at Communication and Electronic Department, Nile  
Higher Institute for Engineering and Technology, Mansoura”

**Spring 2024**



**Nile Higher Institute for  
Engineering & Technology**



**Department of Civil  
Engineering**

## **“Construction Project Management”**

**“مشروع ادارة مشروعات التشييد”**

| <b>Name</b>                               | <b>Code</b>   |
|-------------------------------------------|---------------|
| <b>Ahmed Galal Ahmed Sherif</b>           | <b>190186</b> |
| <b>Fatema Alzahraa Haroun Abdullah</b>    | <b>190193</b> |
| <b>Mohamed Esam Basiony khedr</b>         | <b>190095</b> |
| <b>Alaa Amer Abdulazim Nasr</b>           | <b>190023</b> |
| <b>Ahmed Al Refaee Abdulkaream soltan</b> | <b>190203</b> |
| <b>Omar Amin El said Naga</b>             | <b>190197</b> |
| <b>Abdelhameed Galal Zayed</b>            | <b>190188</b> |
| <b>Mohamed mostafa Helmy Dawood</b>       | <b>190120</b> |
| <b>Abdulrahman Ayman AlAsfoury</b>        | <b>190102</b> |
| <b>Mohamed Emad Abd Elmonem Salman</b>    | <b>190013</b> |
| <b>Mohamed Ali Nafea</b>                  | <b>180224</b> |
| <b>Atef Mohamed AlShater</b>              | <b>190147</b> |

### **Supervisors**

**Assoc. Prof. Dina Tobbala**

“Associate Professor at Civil Department, Nile Higher  
Institute for Engineering and Technology, Mansoura

**Eng. Sameh Makram**

“Teaching Assistant at Civil Department, Nile Higher  
Institute for Engineering and Technology, Mansoura”

**Spring 2024**

# Table of Contents

## Table of Contents

|                                                                       |             |
|-----------------------------------------------------------------------|-------------|
| <b>Supervisors .....</b>                                              | <b>I</b>    |
| <b>Table of Contents .....</b>                                        | <b>II</b>   |
| <b>List Of Figures.....</b>                                           | <b>VI</b>   |
| <b>List Of tables.....</b>                                            | <b>VII</b>  |
| <b>Acknowledgments .....</b>                                          | <b>VIII</b> |
| ABSTRACT.....                                                         | 1           |
| Problem statement.....                                                | 3           |
| <b>Chapter (1) .....</b>                                              | <b>5</b>    |
| Introduction.....                                                     | 6           |
| 1.1 project motivation: -.....                                        | 6           |
| 1.2 Project aims.....                                                 | 7           |
| 1.3 Project contributions .....                                       | 7           |
| <b>Chapter (2) .....</b>                                              | <b>9</b>    |
| Economic Feasibility and Engineering Standards .....                  | 10          |
| <b>2.1 Relation with the Environment and Economic Benefits: .....</b> | <b>10</b>   |
| 2.1.1 Environmental Relationship: .....                               | 10          |
| 2.1.2Economic Benefits:.....                                          | 10          |
| <b>2.2 Balancing Environmental and Economic Benefits: .....</b>       | <b>11</b>   |
| 2.2.1 Recommendations: .....                                          | 11          |
| 2.3 Economically feasibility study.....                               | 11          |
| 2.4 Engineering Standard: - .....                                     | 13          |
| <b>Chapter (3) .....</b>                                              | <b>14</b>   |
| System Design and Analysis.....                                       | 15          |
| 3-1 Design Constraints.....                                           | 15          |
| 3.2 Types of Constraints in construction .....                        | 15          |
| <b>3-2 Code of Ethics (COE) .....</b>                                 | <b>19</b>   |
| The Code of Professional Conduct Civil engineers shall: .....         | 19          |
| <b>Chapter (4) .....</b>                                              | <b>21</b>   |
| PROJECT DESCRIPTION .....                                             | 22          |



|                                                   |            |
|---------------------------------------------------|------------|
| 4.1 Project Description: - .....                  | 22         |
| 4.2 Project Description .....                     | 22         |
| 4.3 General information about the project: -..... | 23         |
| 4.4 Site Visit: -.....                            | 24         |
| 4.5 project location: - .....                     | 25         |
| 4.6 Drawings: - .....                             | 26         |
| <b>Chapter (5) .....</b>                          | <b>28</b>  |
| Contract Analysis.....                            | 29         |
| 5.1 Important Notes .....                         | 29         |
| <b>Chapter (6) .....</b>                          | <b>33</b>  |
| Method statement.....                             | 34         |
| 6.1 Excavation .....                              | 34         |
| 6.2 QA/QC Engineer: .....                         | 36         |
| 6.3 Safety precautions on the site: .....         | 36         |
| 6.3.1 Protective Equipment: .....                 | 36         |
| 6.3.2 Pre-Construction Safety Meetings .....      | 36         |
| Column work .....                                 | 37         |
| 6.4 Equipment and Tools: .....                    | 38         |
| 6.5 Safety & Health Requirements: .....           | 39         |
| 6.6 roof work with drop panel.....                | 41         |
| 6.7 Equipment and Tools: .....                    | 42         |
| 6.8 QA/QC Engineer: .....                         | 43         |
| <b>Chapter (7) .....</b>                          | <b>45</b>  |
| Work Breakdown Structure (WBS) .....              | 46         |
| 7.1 work breakdown structure (WBS) .....          | 46         |
| <b>Chapter (8) .....</b>                          | <b>50</b>  |
| BIM Modeling & Quantity Take off.....             | 51         |
| 8.1 What is BIM?.....                             | 51         |
| 8.2 The BIM growth forecast.....                  | 51         |
| 8.3 BIM Model (3D Modeling) .....                 | 51         |
| 8.4 (ASD) Auto cad Structure Details .....        | 59         |
| <b>Chapter (9) .....</b>                          | <b>108</b> |
| Detailed Quantity Take of (AutoCAD & Excel) ..... | 109        |

|                                                   |            |
|---------------------------------------------------|------------|
| <b>9.1- Quantities Take of AutoCAD:</b> .....     | <b>109</b> |
| 9.1.1- Quantities Of Building: .....              | 109        |
| 9.1.2- Quantities Of Plastering: .....            | 109        |
| 9.1.3- Quantities Of Ceramic:.....                | 109        |
| <b>9.2- Quantity Take Of Excel:</b> .....         | <b>111</b> |
| 9.2.1-Quantity Of Plastering.....                 | 111        |
| 9.2.2- Quantity Of Building:.....                 | 140        |
| <b>Chapter (10)</b> .....                         | <b>155</b> |
| Project Resources & Crew Formation .....          | 156        |
| <b>10.1 Project resources:</b> .....              | <b>156</b> |
| 10.1.1 Labor resource identification:.....        | 156        |
| 10.2 Equipment resource identification: .....     | 156        |
| 10.3 Project resources .....                      | 157        |
| 10.4 Crew formation: .....                        | 158        |
| 10.5 Resources Histogram: .....                   | 160        |
| <b>Chapter (11)</b> .....                         | <b>162</b> |
| Project Planning & Project Schedule .....         | 163        |
| 11.1What is Project Planning:.....                | 163        |
| 11.2Components of a project plan .....            | 163        |
| 11.3 What Is a Project Schedule? .....            | 164        |
| 11.4 What's Included in a Project Schedule? ..... | 164        |
| 11.5 Construction Sequence: .....                 | 165        |
| <b>Chapter (12)</b> .....                         | <b>174</b> |
| Cost management.....                              | 175        |
| 12.1 Defining The Cost estimating .....           | 175        |
| 12.2 Types of Cost Estimates: .....               | 175        |
| 12.3 List of Activities: .....                    | 190        |
| <b>Chapter (13)</b> .....                         | <b>200</b> |
| Cash flow .....                                   | 201        |
| 13.1 Cash flow .....                              | 201        |
| <b>Chapter (14)</b> .....                         | <b>209</b> |
| Project & Contract Pricing .....                  | 210        |
| <b>References :</b> .....                         | <b>219</b> |

## List Of Figures

|                                               |     |
|-----------------------------------------------|-----|
| Figure 1: Site Visit.....                     | 24  |
| Figure 2 Site Visit.....                      | 25  |
| Figure 3: Site Visit.....                     | 25  |
| Figure 4: Project Location.....               | 26  |
| Figure 5 Ground Floor Plan.....               | 26  |
| Figure 6: First Floor Plan.....               | 27  |
| Figure 7: Second Floor Plan.....              | 27  |
| Figure 8: Third Floor Plan.....               | 28  |
| Figure9: Digger.....                          | 34  |
| Figure10: Digger.....                         | 34  |
| Figure11: loaders.....                        | 34  |
| Figure12 : dump trucks.....                   | 35  |
| Figure13 : total station.....                 | 35  |
| Figure14 :Safety boots.....                   | 36  |
| Figure15 : Hard hats.....                     | 36  |
| Figure16 : Protective jackets.....            | 36  |
| Figure 17.....                                | 37  |
| Figure 18.....                                | 37  |
| Figure19 : Concrete mixer.....                | 38  |
| Figure 20.....                                | 39  |
| Figure 21.....                                | 41  |
| Figure 22.....                                | 41  |
| Figure 23.....                                | 42  |
| Figure24 : Concrete mixer.....                | 42  |
| Figurer25 : Concrete Pump.....                | 43  |
| Figure 26.....                                | 43  |
| Figure 27 project 3D modelling.....           | 51  |
| Figure 28 Project 3D footing.....             | 52  |
| Figure29:-3D column necks.....                | 52  |
| Figure29:-3D ground floor.....                | 53  |
| Figure 30 Project 3D columns and beams.....   | 53  |
| Figure 31:-3D stair model.....                | 54  |
| Figure 32 Auto cad Structure Details.....     | 59  |
| Fig.33 Number of walls for the Plastring..... | 110 |
| Fig.34 Number of walls for the building.....  | 110 |
| Figure 35 Carpenter Assistant Crews.....      | 160 |
| Figure 36 Steel Fixer Crews.....              | 160 |
| Figure 37 Carpenter crews .....               | 161 |
| Figure 38 Vibrator for concrete Crews .....   | 161 |
| Figure 39 Pump crews .....                    | 161 |
| Figure 40 Gant Chart.....                     | 166 |
| Figure 41 S- Curve.....                       | 176 |

## List Of tables

|                                                                        |     |
|------------------------------------------------------------------------|-----|
| Table 1: Project Description.....                                      | 22  |
| Table 2 Project Description.....                                       | 22  |
| Table 3 comperation for contract to Fedics.....                        | 30  |
| Table 4 WBS.....                                                       | 46  |
| Table 5 Quantity take off from Revit for concrete for the project..... | 55  |
| Table 6 Quantity of steel.....                                         | 59  |
| Table 7 Details of steel.....                                          | 60  |
| Tabel 8 Total Quantities Of Building.....                              | 109 |
| Tabel 9 Total Quantities Of Oyster.....                                | 109 |
| Tabel 10 Total Quantities Of Ceramic.....                              | 109 |
| Table 11 Quantity of plastering for second floor.....                  | 111 |
| Table 12 Quantity of building for third floor.....                     | 140 |
| Tabel 13Labour Recourses.....                                          | 156 |
| Tabel 14 Equipment Resources.....                                      | 156 |
| Tabel 15 Project Resources.....                                        | 157 |
| Tabel 16 Crew Formation.....                                           | 158 |
| Tabel 17 Material.....                                                 | 159 |
| Table 18 list Of Activity In Excel With Budget Total Cost .....        | 177 |
| Table 19 List Of Subs.....                                             | 199 |
| Table 20 list Of Activity in Primavera With Budget Total Cost.....     | 200 |
| Table 21 Cash Flow In Excel.....                                       | 212 |
| Table 22 Pricing.....                                                  | 221 |

## **Acknowledgments**

**Praise be to Allah who has granted us the knowledge, ability, and strength to perform this work.**

Furthermore, we realize that the Success of our project depends to a large extent on the encouragement of many others. Therefore, we take this opportunity to express our gratitude to the people who played an effective role in the successful completion of this project.

**We would like to show our greatest appreciation to**  
***Assoc. Prof. Dina Toballa***

***Eng. Sameh Makram***

**For continuous support, understanding, and capability to continued guidance. Those who did not hesitate for a moment to help us and answer all our questions.**

Sincere gratitude goes to all friends, colleagues, for their help in collecting the information needed. Finally, we owe our deepest gratitude to our parents and the whole family, as we would have never made it without their endless love and support



## ABSTRACT

The aim of this research is to analyze and study the construction project management for the construction of Tanta General Hospital. Key factors that impact the success of this project will be reviewed, and appropriate strategies will be identified for its effective management. A project management model will be presented, and an economic feasibility analysis of the project will be conducted to ensure the achievement of the defined objectives and reduction of potential risks. The performance of existing operations will also be evaluated, identifying strengths and weaknesses in order to improve project performance and ensure successful implementation.

### ❖ Problems: -

The Tanta General Hospital construction project may face several challenges and problems, including:

- Budget Overruns
- Schedule Delays
- Quality Control Issues
- Safety Concerns.
- Stakeholder Management
- Environmental Impact
- Resource Management
- Technical Challenges
- Coordination with Healthcare Professionals.

### ❖ Technology (Engineering Standard): -

1. The project follows engineering standards **Egyptian Code for Construction Project Management** (Code NO. 311-2015).
2. the project follows the **Egyptian contract Law 182 of 2018**
3. the project follows **FIDIC Contracts**.

### ❖ Results: -

1. Quality Assurance: - Meeting the required quality standards in all project aspects, including materials, designs, and workmanship.
2. Safety Records: - Maintaining a good safety record with minimal accidents and injuries on the construction site.
3. Stakeholder Satisfaction: - Ensuring satisfaction among all stakeholders, including owners, end-users (such as doctors and

patients), and the local community.

4. Regulatory Compliance: - Adhering to all relevant local and international construction and building regulations.
5. Social and Economic Impact: - Providing economic and social benefits to the local community, such as creating new jobs, improving healthcare infrastructure and Enhanced Healthcare Services.

## Problem statement

### ❖ Background: -

Tanta city is in urgent need of developing its healthcare infrastructure to meet the increasing demand for medical services. Tanta General Hospital is one of the key healthcare facilities that require comprehensive improvements in its infrastructure to provide high-quality healthcare to the residents.

### ❖ Problem: -

The Hospital Construction Project Management Project in Tanta faces several challenges that hinder the efficient and effective implementation of operations. These challenges include:

1. **Budget Overruns:** - Unforeseen costs can lead to exceeding the allocated budget. Factors contributing to this include rising material prices, labor costs, or unexpected site conditions.
2. **Schedule Delays:** - Delays in the construction schedule can occur due to various reasons such as poor weather conditions, supply chain disruptions, or delays in obtaining necessary permits and approvals.
3. **Quality Control Issues:** - Ensuring that construction meets the required standards can be challenging, especially if there are inconsistencies in material quality or workmanship.
4. **Safety Concerns:** - Maintaining a safe work environment is crucial. Construction sites are prone to accidents and injuries, which can halt progress and lead to legal and financial repercussions.
5. **Regulatory Compliance:** - Navigating the complexities of local, regional, and international construction regulations can be difficult, and non-compliance can result in fines, project delays, or shutdowns.
6. **Stakeholder Management:** - Balancing the expectations and requirements of different stakeholders, including investors, government bodies, healthcare providers, and the local community, can be challenging.
7. **Environmental Impact:** - Managing the environmental impact of the construction process, including waste disposal, emissions, and disturbance to the local ecosystem, is essential and can be a complex task.
8. **Resource Management:** - Efficiently managing resources such as labor, materials, and equipment is critical. Shortages or mismanagement can lead to delays and increased costs.
9. **Technical Challenges:** - Complex technical issues can arise during construction, especially in a healthcare facility that requires specialized infrastructure for medical equipment, HVAC systems, and sanitary conditions.


**10. Coordination with Healthcare Professionals:** Ensuring that the facility meets the operational needs of healthcare professionals requires constant coordination and may involve changes to the initial design, which can cause delays and additional costs.

❖ **Objective:**

The project aims to develop an efficient system for managing construction projects for Tanta General Hospital to ensure the project is executed efficiently, within the set budget, and on time with maintaining quality and safety

❖ **Proposed Solution:**

1. **Develop a detailed plan** that includes all project phases and clearly defines tasks and responsibilities.
2. **Project time management** by using modern tools and techniques to track work progress and ensure adherence to timelines.
3. **Effective resource management** through meticulous planning to allocate material and human resources.
4. **Precise budget management** through cost analysis and regular expense monitoring.
5. **Quality assurance** by applying quality control standards at all project stages.
6. **Enhance communication** among all stakeholders by utilizing advanced project management systems.



# Chapter (1)

## Introduction

Construction project management handles the planning, coordination, and execution of a construction project, whether in the agricultural, residential, commercial, institutional, industrial, civil, or environmental industries.

Construction projects typically include hundreds of tasks and multiple phases that require a deep knowledge of the building process and ability to problem-solve to keep the project on track. Due to the complex, often shifting nature of construction projects, the role of a construction project manager is to keep the project moving according to plan.

The goal is to manage the project so that it finishes on time and on budget, while still delivering a final product that meets codes, plans, and specifications. Some of the construction project manager's responsibilities include project management planning and cost, quality, and safety management. The management of construction projects requires knowledge of modern management as well as an understanding of the design and construction process. Construction projects have a specific set of objectives and constraints such as a required time frame for completion. While the relevant technology, institutional arrangements or processes will differ, the management of such projects has much in common with the management of similar types of projects in other specialty or technology domains such as aerospace, pharmaceutical and energy developments.

Project management is the art of directing and coordinating human and material resources throughout the life of a project by using modern management techniques to achieve predetermined objectives of scope, cost, time, quality and participation satisfaction.

### 1.1 project motivation: -

1. **Improving healthcare services:** Expanding and developing Tanta General Hospital with its facilities and equipment can improve the quality of healthcare received by patients in the area.
2. **Meeting growing medical needs:** Developing the hospital can help meet the community's increasing need for healthcare services and treatment.
3. **Achieving financial sustainability:** Developing the hospital can increase revenue streams and achieve financial sustainability for the hospital.
4. **Promoting the local economy:** Implementing the construction project of the hospital can drive the local economic development by creating local job opportunities and supporting local businesses.
5. **Enhancing the hospital's reputation:** Improving and expanding Tanta

General Hospital can enhance

## 1.2 Project aims

The project aims to successfully manage the construction project for Tanta General Hospital, ensuring that it is completed on time, within budget, and according to quality standards. This includes coordinating with contractors, suppliers, and stakeholders, managing resources effectively, and addressing any issues or risks that may arise during the construction process. Additionally, the project aims to deliver a safe and functional hospital facility that meets the needs of the community and provides quality healthcare services according to **(Engineering Standard): -**

1. The project follows engineering standards **Egyptian Code for Construction Project Management** (Code NO. 311-2015).
2. the project follows the **Egyptian contract Law 182 of 2018**
3. the project follows **FIDIC Contracts**.

## 1.3 Project contributions


Some potential project contributions for a construction management project for the construction of Tanta General Hospital could include:

1. Developing a comprehensive project plan outlining the scope, schedule, budget, and resources required for the construction of the hospital.
2. Conducting site surveys and feasibility studies to assess the suitability of the location for the hospital and identify any potential challenges or obstacles.
3. Managing the procurement process to source qualified contractors, vendors, and suppliers for the construction project.
4. Implementing quality control measures to ensure that all construction work meets the required standards and specifications.
5. Coordinating with relevant stakeholders, including government officials, healthcare professionals, and local communities, to ensure alignment and support for the project.
6. Monitoring the progress of construction activities, identifying and addressing any issues or delays that may arise during the project.
7. Conducting regular risk assessments to identify potential risks to the project and develop mitigation strategies to minimize their impact.
8. Ensuring compliance with all relevant regulations, codes, and standards throughout the construction process.
9. Collaborating with architects, engineers, and other professionals to ensure that the design and construction of the hospital meet the needs and

requirements of its future occupants.

- 10.** Providing regular updates and reports to stakeholders on the progress and performance of the construction project.





## Chapter (2)

## **Economic Feasibility and Engineering Standards**

The Economic Feasibility Study for the project of managing construction projects for Tanta General Hospital aims to

1. Evaluate the financial and economic aspects of the project,
2. Analyze the possibility of achieving the expected financial return from it.

This study usually includes economic factors that affect the project such as the costs required for construction and operation, expected revenues from hospital services, fixed and variable costs, and analysis of the financial profitability of the project.

The study aims to provide an accurate estimate of the project cost and the possibility of achieving profits from it, and to provide recommendations on the feasibility of continuing the project and improving its economic performance in the future.

The economic feasibility study is considered one of the important steps in preparing any project before starting its implementation.

### **2.1 Relation with the Environment and Economic Benefits:**

The construction project of Tanta General Hospital provides significant economic benefits to the region and the local community as a whole, as it contributes to creating job opportunities for local residents during the construction and operational phases. Additionally, the project works to enhance investments in the area and attract capital.

#### 2.1.1 Environmental Relationship:

the construction project of Tanta General Hospital can help improve the quality of the surrounding environment by monitoring and reducing harmful emissions and using environmentally friendly building materials. The project can also support the sustainability of local resources by employing green construction techniques and promoting principles of recycling and the use of renewable resources.

#### 2.1.2 Economic Benefits:

##### 1. Short-term Benefits: -

- Job Opportunities: - Creating job opportunities for local residents during the construction phase, boosting the local economy.
- Local Investment: - Attracting local and foreign investments to participate in the project, enhancing the local economy.

## **2. Long-term Benefits: -**

- Improved Healthcare Services: - Providing advanced healthcare services can improve community health and reduce long-term healthcare costs.
- Economic Growth: - Improved healthcare infrastructure can attract more residents and investments to the area, boosting local economic growth.
- Reduced Healthcare costs: - better healthcare can lower the costs of treatment and travel for medical care.

## **2.2 Balancing Environmental and Economic Benefits:**

- Sustainable Design: - Investing in sustainable construction technologies can be costly initially but it provides long-term savings through reduced energy consumption and lower maintenance costs.
- Environmental Policies: - Adhering to strict environmental policies can ensure a balance between economic development and environmental preservation.

### **2.2.1 Recommendations:**

- Environmental Impact Assessment: - Conducting studies to assess the environmental impact of the project before starting and taking necessary measures to mitigate any negative effects.
- Community Engagement: - Involving the local community in the planning and implementation phases to ensure the project meets their needs and addresses their concerns.
- Training and Development: - Providing training programs for workers on using sustainable technologies and eco-friendly work practices.

## **2.3 Economically feasibility study**

### **Introduction**

This study aims to evaluate the economic feasibility of constructing Tanta General Hospital. The analysis will include cost estimation, revenue projection, benefit analysis, and financial metrics to determine the viability of the project.

### **1. Project Overview**

- Project Name: Tanta General Hospital
- Location: - Tanta, Gharbia, Egypt
- Capacity: - 300 beds
- Project Area: 13100 m<sup>2</sup>
- Services: General medicine, surgery, emergency services, pediatrics, maternity, and specialty clinics

## **2. Cost Estimation**

### **➤ Initial Capital Investment**

- Land Acquisition: \$2,000,000
- Construction Costs: \$20,000,000
- Medical Equipment and Technology: \$10,000,000
- Furniture and Fixtures: \$2,000,000
- Pre-Operating Expenses (permits, licenses, etc.): \$1,000,000
- Contingency (10% of total costs): \$3,500,000
- Total Initial Investment

### **➤ Operating Costs (Annual)**

- Salaries and Wages: \$5,000,000
- Utilities and Maintenance: \$1,500,000
- Supplies and Pharmaceuticals: \$2,000,000
- Administrative and Overhead: \$1,000,000
- Total Annual Operating Costs: \$9,500,000

## **3. Revenue Projection**

### **➤ Service Revenue (Annual)**

- Inpatient Services: \$12,000,000
- Outpatient Services: \$5,000,000
- Specialty Services and Surgeries: \$8,000,000
- Diagnostic and Laboratory Services: \$2,000,000
- Total Annual Revenue: \$27,000,000

### **➤ Other Revenue**

- Government Grants and Subsidies: \$1,500,000
- Donations and Fundraising: \$500,000
- Total Additional Revenue: \$2,000,000
- Total Annual Revenue: \$29,000,000

## **4. Benefit Analysis**

### **➤ Cost-Benefit Analysis**

- Annual Net Revenue:  $\$29,000,000 - \$9,500,000 = \$19,500,000$
- Payback Period:  $\$38,500,000 / \$19,500,000 = \sim 2 \text{ years}$


## **5. Risk Analysis**

- Construction Delays: Mitigation through strict project management and contingency planning.

- Cost Overruns: Addressed by including a contingency fund and thorough planning.
- Revenue Shortfalls: Conservative revenue estimates and diversifying service offerings.
- Regulatory Changes: Regular compliance checks and engagement with regulatory bodies.

#### **2.4 Engineering Standard: -**

1. The project follows engineering standards **Egyptian Code for Construction Project Management** (Code NO. 311-2015).
2. the project follows the **Egyptian contract Law 182 of 2018**.
3. the project follows **FIDIC Contracts**.



## Chapter (3)

# System Design and Analysis

## 3-1 Design Constraints

There are many constraints in every industry. But there are instances where we become unaware of the existence of the constraints. Or we tend to put more emphasis on the goals of the project.

The construction industry includes a multitude of parties that would bring complications in the management of the project. This could lead to conflicts and disputes which have cost consequences directly or indirectly to the clients and or contractors. It is therefore critical to identify the potential constraints to help decrease the loss of money and time due to inadequate planning. Controlling the possible constraints is a pre-requisite for the high performance of the project.

However, constraints in the construction sector limit their ability to perform at a high-level. If we can understand constraints better at the onset, then the performance level of your business will improve.

## 3.2 Types of Constraints in construction

- Design

Design constraints are factors that limit the range of possible design outputs. Although, there is an argument that design constraints can be helpful in the creation and development of the design

The design constraints could include the budget, performance requirements, site boundaries, conditions from neighboring properties, site access, local structures, building regulations, completion dates, and local weather conditions.

It is also possible that design constraints may be known at the early stages of a project while others become apparent at the latter design process.

- Technical

These types of constraints usually refer to the process involving the completion of construction activities. And they are often based on the practicality of building

standards and methods. Other technical constraints are related to the tolerances of construction, the space required for builders to work, available handling or storage areas, site access, and the coordination of services.

These constraints are all linked to health and safety, building regulations,

control and client needs, and any architectural aspects. Some of these constraints will be small and may seem meaningless but it can have a large impact.

An example of a technical constraint is the construction of the foundation. The site must be properly excavated. After this, the framework and the reinforcement can be placed before the concrete is poured. Each step or task must be completed before the next one can begin. Making the previous task a constraint to the next task.

There are also a few technical restraints that can come from a restrictive site area and congested environments or surroundings. This can pose constraints in storage space, design, and transportation. These are usually recognized at the stage of design, but this doesn't necessarily mean that all constraints can be readily overcome.

- **Environmental**

Are limiting factors that concern the following; Air, water, or ground pollution.

Usage of hazardous or sustainable materials. Carbon emissions or energy consumption. Waste and water management, Dust, vibration, and noise.

Preservation of ecology, traffic, and transportation, climate change resilience.

Design for deconstruction and disposal.

These factors often can overlap with legal constraints but additional requirements can be provided by the client for environmental policies.

- **Economic**

These relate to the budget of the project and the allocation of resources. If the budget is not enough or it is not allocated properly then it can have a negative impact on the quality, functionality, performance, safety, and success of the project.

Generally, construction projects are balanced between quality and cost. Any change in one will directly impact the other two.

However, these relate to not just the overall budget but also the flow of cash through the supply chain. Clients should have available funds to pay for works as they progress. Payments must be made on time through the contractual chain.

Cash flow is one of the primary causes of bankruptcy in the construction



business. and having to find new suppliers, contractors and subcontractors can cause a project to be delayed which would lead to additional costs.

Due to budget constraints, the adopted system for the construction may not necessarily be the best option for achieving quality and project goals. If the budget is also not efficiently allocated it can hamper the progress of the project. In summary, if the economic constraints are not managed properly it can affect the product, performance, function, and quality of the project.

- **Technological**

These kinds of constraints are directly related to the limitation of projects due to technology. It is defined as the logical relationship between activities that cannot be changed unless the technology is changed. This is the most obvious constraint, as the application of a machine or a piece of automated equipment can directly change the progression of activities that changes the nature of the work.

- **Legal**

This refers to regulations that the practices and activities in a construction project have to comply with. This usually involves safety requirements, employment law, building regulations, planning, and environmental requirements.

The process of complying with all these requirements and regulations can be time consuming and it usually requires a complete understanding of complicated bureaucratic procedures. However, failure in complying with these regulations can have a negative impact on your project and business. It can affect the project by causing delays, remedial works, financial penalties and it can even cause criminal proceedings.

Any building will have to first get a planning permit and it has to meet certain criteria for approval. Planners can apply restrictions and or ask for improvements for your business to get permission. Building regulations have a set of detailed performance requirements or standards that the completed project must comply with. When your project or business can comply with all the requirements a certificate is normally provided or issued for insurance purposes.

- **Social**

Public concern and pressure from the media can impose a limitation and greater scrutiny on a project. It can even sometimes result in the alteration of the original plans and completion dates. Social constraints include components that arise from the result of wider interest or opposition to specific projects.

Projects that are funded by the public are normally subject to social constraints because of the greater Interest it entails.

These types of constraints are often labeled as "not in my backyard" or nimbyism.

- **Time**

These include vital dates on a scheduled project or milestone. Conforming to these dates is usually important in terms of the overall project completion date. Penalties are normally given if a business is unable to meet the agreed dates.

But some delays are not necessarily the fault of a contractor. Of which they are usually granted an extension. Pushing the dates back.

Other time constraints can come from third parties. These third-party components can be anything from planning permission expiry dates to changes in legislation.

Contracts normally specify the earliest completion date, the date on which the task should be completed, and the exact date on which a task must be completed. Projects that have phases may include multiple starts and end dates.

- **Managerial**

Lastly, are managerial constraints. These are related to resources such as materials, equipment, and workers. This happens when it is required to adjust the schedule of active resources for certain projects or operations which can't be available as soon as they are needed. Management needs to take into consideration many constraints that are related to the nature of the equipment and its corresponding management principles.

Several factors can affect the planning and scheduling of activities for construction. Which can lead to impacting the productivity, operating time, and rates of production.

Timing for maintenance of equipment, security programs, inventory of parts, workers' schedules, are all elements of a managerial constraint that should be considered heavily

### **3-2 Code of Ethics (COE)**

#### **Ethical Principles**

Ever cognizant of the profound interrelationship of their profession with both human society and Nature, civil engineers shall work for the development of technology, deepen and consolidate their knowledge, contribute by means of their wisdom, skills, and virtues to both the peace and prosperity of the people and the nation and to the welfare and sustainable development of the humanity.

#### **The Code of Professional Conduct Civil engineers shall:**

##### **1. Contribute to society.**

Utilize their expertise and experience to develop and implement comprehensive solutions to issues of public interest, keeping in mind the peace and prosperity of the people and the development of society as their constant concern.

##### **2. Respect both Nature and the fabric of civilization and culture.**

Respect Nature indispensable to the survival and development of humanity while holding in esteem diverse civilizations and cultures.

##### **3. Ensure the security of society and mitigate disasters.**

Be committed to aiding in protecting the life and property of the people, working with colleagues across a broad range of disciplines, while looking beyond their professional expertise to the concerns of the people, realizing both the capabilities and the limitations of technology with the people.

##### **4. Fulfill their professional responsibilities.**

Recognize the essentially social significance of their work and thus endeavor to fulfill their duty to society.

##### **5. Guard their integrity and avoid any conflicts of interest.**

Be fair and unbiased in all their interactions with the people, their clients, the organizations for which they work, as well as themselves, faithfully and honestly discharging their duties and avoiding any conflicts of interest.

##### **6. Openly provide information and engage in public dialog.**

For the sake of the general welfare, be pro-active in sharing their expertise and knowledge in their endeavors and communicate in an open exchange of views with the people.

## **7. Make known the results of their research endeavors.**


Publish their findings and policy recommendations with research papers and reports in conformity with both their scientific convictions and their own consciences, sharing these with both their professional colleagues and the people, always mindful of objective facts and the intellectual achievements of others.

## **8. Strive for self-improvement and human-resource development.**

Cultivate and nurture their virtues, general knowledge and professional competence, pursue scientific endeavors in the realms of both scientific and practical theories for the sake of technological advances, and put to use their individual abilities, experience, and merits for the education and training of engineers.

## **9. Comply with established norms.**

Carry out their work in full understanding of all laws, rules, and regulations as well as of well-founded principles, actively and willingly taking the lead in the observance of societal standards and seeking to improve them in response to both social and technological change.



## Chapter (4)

## PROJECT DESCRIPTION

### 4.1 Project Description: -

Table 1: Project Description

|                     |                                                                |
|---------------------|----------------------------------------------------------------|
| <b>Project Name</b> | <b>A project of the Construction of Tanta General Hospital</b> |
| <b>Owner</b>        | <b>Ministry of Health and population</b>                       |
| <b>Consultant</b>   | <b>Ain Shams University, Faculty of Engineering</b>            |
| <b>Contractor</b>   | <b>Wadi EL Nile Company</b>                                    |


### 4.2 Project Description

Table 2 Project Description

| <b>Floor</b>            | <b>Components</b>                                                                                                                                                                                                                                                           |
|-------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Ground</b>           | Main Entrance - Inquiries - Waiting Area – Financial and administrative management offices – Emergency department – X-ray place – Renal dialysis – Natural therapy – Service rooms – Outpatient clinics -Mortuary.                                                          |
| <b>First Floor</b>      | Senior management of the hospital (Manager – Administrative offices – Meeting room – 4 intensive care units – 5 operating rooms – Heart catheterization department – Department of burns – Department of minimally invasive surgery – Laboratory department and blood bank) |
| <b>Second Floor</b>     | Waiting area – Patient residence area – Women and maternity department – 2 cesarean operating rooms - Nurseries                                                                                                                                                             |
| <b>Third Floor</b>      | Patient accommodation                                                                                                                                                                                                                                                       |
| <b>Fourth Floor</b>     | Patient accommodation – Doctor’s accommodation – Nursing accommodation                                                                                                                                                                                                      |
| <b>General Location</b> | Service rooms (Transformers – Main electrical panels – Generator – Security – Workshops – Warehouses – Fire tank– Parking for cars and ambulances – Oxygen tank)                                                                                                            |
| <b>Annex Buildings</b>  | Electric Room- Processing Station- Fire Tank                                                                                                                                                                                                                                |

#### 4.3 General information about the project: -

- **Project Area:** - 13100 m<sup>2</sup>
- **Location:** - Egypt-Gharbia-Tanta-Seberbay.
- **Total Price:** 1363863000 billion EGP
- **Project start date:** 01/10/2023
- **Duration:** 21 months
- **Actual implementation rate:** 90%



#### 4.4 Site Visit: -



Figure 9: Site Visit



Figure 10 Site Visit





Figure 11: Site Visit

#### 4.5 project location: -

- *Location: - Egypt-Gharbia-Tanta-Seberbay*




Figure 12: Project Location

#### 4.6 Drawings: -

- *Ground Floor Plan*




Figure 13 Ground Floor Plan:

- *First Floor Plan*




Figure 14: First Floor Plan



- **Second Floor Plan**




Figure 15: Second Floor Plan

- **Third Floor Plan**





Figure 16: Third Floor Plan



## Chapter (5)

## **Contract Analysis**

### **5.1 Important Notes**

- 1) Prices include making detailed operating drawings for each space showing all specialties (sanitary, electricity, gases, air conditioning, etc., furnishings, etc.), with the participation of supplying companies specialized in supplying supplies and equipment for hospitals, provided that they are approved by the consultants before the start of the project business.
- 2) All prices include the contractor's careful review of the actual dimensions and their review with the drawings Submitted by the consultant regarding signing the building on site and approving it with the consultant before starting implementation.
- 3) All prices include making operating drawings for any part and any specialty of the project, depending on For consultant instructions.
- 4) The contractor is obligated to provide all products supplied to the site in their original sealed packaging indicating the name of the producing company and its industry.
- 5) Prices include the contractor providing training to specialists from the Ministry's employees on the following:
- 6) Use of all equipment supplied to the building, methods of use and maintenance methods.
- 7) Methods of checking the validity of fire alarm devices. Dealing with central air conditioning devices.
- 8) Electricity distribution panels and other electrical devices.
- 9) When submitting the bid, the contractor is deemed to have visited the site and inspected it for due diligence.
- 10) The items include removing and demolishing any buildings from the public site after they have been approved by the consulting engineer, or completely clearing it of any trees, buildings, concrete bases, or any facilities, and removing any foundations or fences, transporting demolition products to public dumps, and supplying all demolition products, including gates, windows, etc., To hospital warehouses, in accordance with the instructions of the consulting engineer.


Table 3 compression for contract to Fedics

| FIDIC                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Terms of the contract                                                                                                                                                                                                                                                                                                                                    | Comparison           |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|
| <p>The first clause</p> <p>The previous introduction, tender documents, and project specifications are considered the subject of the contract, which was prepared by the Center for Research and Engineering Consultations at the Faculty of Engineering - Tanta University and approved by the competent authority of both parties to conclude this contract, as well as all previous correspondences and minutes prepared by the first party, which are an integral part of this contract and complement its provisions.</p> | <p>This part includes the general conditions for submitting a bid for the construction of works specified in detail in the documents attached hereto the conditions, which consist of:</p> <p>A. Working drawings.</p> <p>B. Technical specifications.</p> <p>C. Tables of quantities and prices.</p>                                                    | <p>in accordance</p> |
| <p>The second clause</p> <p>The second party shall carry out the construction of Tanta General Hospital building at the University Hospitals in accordance with the specifications attached to this contract, provided that the accounting is based on the actual implementation of the works according to the drawings, items, quantities, and specifications specified in the work schedule and in accordance with the list of weights received with the assignment order.</p>                                               | <p>These Contractor's documents shall be in accordance with the specification and drawings, shall be written in the language for communications defined in Sub-Clause 1.4 (Law and Language), and shall include additional information required by the Engineer to add to the drawings for coordination of each party's designs</p>                      | <p>in accordance</p> |
| <p>The Third clause</p> <p>This contract shall come into effect from the date of receiving the advance payment, linked to the receipt of the site free from obstacles and impediments, according to a receipt signed by the representative of the second party.</p>                                                                                                                                                                                                                                                            | <p>The Employer shall make an advance payment, as an interest-free loan for mobilization, when the Contractor submits a guarantee in accordance with the Subclause. The total advance payment, the number and timing of instalments (if more than one), and the applicable currencies and proportions, shall be as stated in the Appendix to Tender.</p> | <p>in accordance</p> |
| <p>Fourth Clause</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                          | <p>in accordance</p> |

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                      |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|
| <p>The execution period of the works is twenty-four months starting from the date of receiving the advance payment associated with the receipt of the site free of obstacles and hindrances, with the commitment of the second party to provide a schedule within two weeks for the duration of the execution to be approved by the first party...</p> <p>The first party undertakes to take measures to issue permits.</p>                                                                                                     | <p>The Contractor shall submit a detailed time programmed to the Engineer within 28 days after receiving the notice under Sub-Clause 8.1 [Commencement of Works]. The Contractor shall also submit a revised programmed whenever the previous programmed is inconsistent with actual progress or with the Contractor's obligations. Each programmed shall include: (a) The order in which the Contractor intends to carry out the Works, including the anticipated timing of each stage of design (if any), Contractor's Documents procurement, manufacture of Plant, delivery to Site, construction, erection and testing,</p> |                      |
| <p>The Fifth clause<br/>Police regulations - Health - Maintaining order - Roads:<br/>On the other hand, following police regulations, health, organization, labor laws, and other regulations, and it is incumbent upon his agents and workers to follow them and be responsible for maintaining order at the workplace. The second party must be removed from work within 24 hours of receiving the order from the engineer of the first party or his representative if he does not follow the instructions issued to him.</p> | <p>The Contractor shall at all times take all reasonable precautions to maintain the health and safety of the Contractor's Personnel. In Collaboration with local health authorities the Contractor shall ensure that medical staff, first aid facilities, sick bay and ambulance service are available at all times at the site and at any accommodation for Contractor's and Employer's Personnel, and that suitable arrangements are made for all necessary welfare and hygiene requirements and for the prevention of epidemics.</p>                                                                                        | <p>in accordance</p> |
| <p>The sixth Clause<br/>If he is late in completing the work and delivering the project on the specified dates, delay fines will be imposed on him in accordance with the Tenders and Auctions Law No. 89 issued in 1998 and its executive regulations issued by the Minister of Finance. This fine will be imposed as soon as the delay occurs without the need for an official or informal assignment or warning or taking any legal measures.</p>                                                                            | <p>If the Contractor fails to comply with Subclause 8.2 [Time for Completion], the Contractor shall subject to Sub-Clause 2.5 [Employer's Claims] pay delay damages to the Employer for this default. These delay damages shall be the sum stated in the Appendix to Tender, which shall be paid for every day, which shall elapse between the relevant Time for Completion and the Date stated in the Taking-Over Certificate. However, the total amount due under this Sub-Clause shall not exceed the maximum amount of delay damages (if any) stated in the</p>                                                             | <p>in accordance</p> |

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                      |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|
|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | <p>Appendix to Tender. These delay damages shall be the only damages due from the Contractor for such default, other than in the event of termination under Subclause 15.2 [Termination by Employer] prior to completion of the Works. These damages shall not relieve the Contractor from his obligation to complete the Works, or from any other duties, obligations or responsibilities, which he may have under the Contract.</p>                            |                      |
| <p>The Seventh Clause</p> <p>The owner has the right to send samples of materials supplied by the second party to government laboratories and private laboratories to ensure their suitability and compliance with the conditions and specifications. The second party must, at its expense, provide the necessary supplies, workmanship, and means of transportation necessary to conduct this test, as well as all testing costs to be borne by the second party or paid by the party. The first deducts it from the second party's receivables</p> | <p>The contractor shall submit the Following samples of materials, and relevant information, to the Engineer for consent prior to using the Materials in or for the Works:</p> <p>(a) manufacturer's standard samples of Materials and samples specified in the Contract, all at the Contractor's cost</p> <p>(b) additional samples instructed by the Engineer as Variation.</p> <p>Each sample shall be labeled as to origin and intended use in the Works</p> | <p>in accordance</p> |





## Chapter (6)

## Method statement

### 6.1 Excavation

#### Scope:

This method statement for excavation defines the sequence and control procedures to be followed for excavation work for the project and the practical guidance to manage health and safety risks associated with excavation activity.

#### The description of the procedure/ sequence:

- 1) Excavation work: depends on the foundations of fire tanks and building foundations.
- 2) Excavation work: in cubic metres 13104 m<sup>3</sup>.
- 3) Excavation will be carried out using an excavator with bucket.



Figure9: Digger

- 4) The excavators with bucket will be used to excavate the sandy soil and loaders will work at the same time to load the excavated materials in the dump truck.



Figure10: Digger



Figure11: loaders

- 5) The dump trucks will move the excavated materials to the land filling, considering the amount of the backfilling soil that is required.



Figure12 : dump trucks

6) Excavation work: in cubic meters, excavation of the foundations of the fire tank to any depth at all times Types of soil according to the consultant's instructions and the soil research report, and the category includes solid aspects Drilling also includes the removal of surface and groundwater, if any, and everything necessary for completion Work in accordance with conditions and specifications and according to industry principles and engineering measurement For design drawings, the measurement method was explained in the technical specifications for drilling and works Dirt. 1700 m<sup>3</sup> .

7) Excavation work: in cubic meters, digging foundations to any depth in all types of soil According to the consultant's instructions and the soil research report, the category includes surface water dewatering And the subterranean materials, if any, and everything necessary to complete the work in accordance with the conditions and specifications The principles of industry and engineering measurement are according to the design drawings, and the measurement method is explained Technical specifications for excavation and earthworks. 7500 m<sup>3</sup>

8) The surveyor will keep checking on the level of each stage of excavation to avoid any over excavation or any over depth that will result a landslide of the soil that is being excavated .

9) The building area will be leveled with the aid of the total station.



Figure13 : total station.

## 6.2 QA/QC Engineer:

- 1) Ensure the proper implementation of the Quality system and monitor the overall quality of the work is maintained.
- 2) Conduct inspection and monitor tests. Determine and report any non-conformance and recommended corrective actions.
- 3) Ensure that all personnel is aware of the quality requirement.
- 4) Training of relevant personnel

## 6.3 Safety precautions on the site:

### 6.3.1 Protective Equipment:

- Safety boots. • Hard hats. • Protective jackets.



Figure14: Safety boots



Figure15: Hard hats



Figure16: Protective jackets.

### 6.3.2 Pre-Construction Safety Meetings

- Method statement and Risk Assessment to be briefed to all construction team before the activity start.
- General contractual safety, health, and environmental requirements.
- Roles of the contractor, subcontractors, authorized representatives, and all project workers. Accident reporting requirements.

| Description           | Applications                   |
|-----------------------|--------------------------------|
| Loader                | Loading of Excavated Materials |
| Excavator with bucket | Excavation Works               |
| Dump Trucks           | Hauling of Excavated Materials |
| Water Trucks          | Dust Control                   |
| Generators            | Power Supply                   |
| Total Station         | Setting Out for Construction   |

## Column work

### The description of the procedure/ sequence:

**Planning and Design:** Engineering planning and design of columns is done based on project requirements and expected loads.




Figure 17

- 1) Site preparation : This includes cleaning the site, preparing it for construction operations, and determining the locations of columns on the project land according to engineering drawings.
- 2) Column mold casting : Column molds are formed and prepared for casting in reinforced concrete.
- 3) Reinforcing steel placement : Reinforcing steel is arranged and placed inside the column molds in coordination with the engineering design.



Figure 18

- 4) Concrete pouring : Concrete is poured into the column molds after securing the reinforcement steel.
- 5) Taking care of the curing process : After pouring, care must be taken of the

curing process to allow the concrete to harden properly.

- 6) Removal of formwork : After the concrete is strong enough, the formwork for the columns is carefully removed.
- 7) Quality Check : Columns are carefully inspected to ensure they are performed correctly according to specifications.
- 8) Moving to the next step : After ensuring the quality of the columns, we move to the next steps in the construction process.

#### 6.4 Equipment and Tools:

- 1) Column molds : used to form concrete and act as containers for poured concrete.
- 2) Reinforcing steel : Iron bars are used to reinforce concrete and give it additional strength and rigidity.
- 3) Cutting tools : such as an electric or iron saw to cut rebar bars according to the required size and shape.
- 4) Measuring tools : such as a ruler, scale, and angles to ensure accurate column measurements and determine iron locations.
- 5) : to mix concrete in sufficient quantities and in the required proportion.



Figure19 : Concrete mixer

- 1) Concrete pump (optional) : If columns are high or require difficult access, a concrete pump can be used to pump concrete to the specified location.
- 2) Cleaning brooms and brushes : to clean the site of dust and dirt before pouring concrete.
- 3) Personal safety equipment : such as safety helmet, goggles, work gloves, and safety shoes to ensure worker safety while working.
- 4) Cure and Care Equipment : Such as blankets and water for irrigation to help



the concrete cure properly.

- 5) Fastening tools : such as manual and automatic tools to hold column molds in place.

## 6.5 Safety & Health Requirements:

- 1) Worker Training : Workers must have good training on how to work safely according to proper standards and procedures.
- 2) Personal Protective Equipment : All workers must wear personal protective equipment such as safety helmets, goggles, work gloves, and safety shoes.
- 3) Safety at work at heights : If the work requires working at height, safe and well-secured platforms and ladders must be provided.
- 4) Movement direction and control : Good direction and control must be provided for the movement of heavy equipment and trucks within the site to avoid accidents.



Figure 20

- 5) Providing safe work spaces : Work spaces must provide the necessary safety means such as safe corridors and safety signs.
- 6) Good ventilation : Work must be done in well-ventilated areas to reduce workers' exposure to dust and harmful gases.
- 7) Emergency Procedures : Appropriate emergency procedures must be provided, such as fire extinguishers, rescue crews, and first aid.
- 8) Risk assessment and management : An assessment of potential risks must be carried out and procedures applied to manage and reduce them as much as possible.
- 9) Health and safety follow-up : Health and safety policies must be constantly updated and reviewed and implementation monitored to ensure compliance.
- 10) Communication and instructions : Clear directions and instructions must be

provided to workers about safety and health procedures and the need to comply with them.

- 11) Worker Training :** Ensure that all workers involved in the roof pouring process have the necessary safety training and the correct procedures to work safely.
- 12) Use personal protective equipment :** Ensure that all workers wear appropriate personal protective equipment such as safety helmets, goggles, work gloves, and safety boots.
- 13) Securing the site :** Make sure the site is well secured to prevent accidents, and use barriers and signs to identify risky areas and prevent unauthorized entry.
- 14) Control of materials and equipment :** Ensure that all materials and equipment used have the necessary quality and safety, and ensure that there are no damage or defects in them.
- 15) Good ventilation :** Make sure there is adequate ventilation in the workplace to reduce exposure to harmful gases and hazardous vapors.
- 16) Check the site periodically :** Check the site periodically to ensure that there are no new risks or unsafe activities.
- 17) Clean the site regularly :** Make sure to clean the site regularly from dust and debris to reduce the risk of slipping and falling.
- 18) Handle hazardous materials with caution :** If there are hazardous materials such as chemicals or heavy boards, be sure to handle them with caution according to security guidelines.
- 19) Implement emergency procedures :** Ensure that an emergency plan is in place, that the necessary rescue equipment is available, and that workers are trained to use it.
- 20) Communication and Collaboration :** Enhancing communication and cooperation among all team members to ensure that work is carried out safely and effectively
- 21) QA/QC Engineer:**
- 22) Develop and determine all standards to perform inspection and tests on all procedures and oversee all testing methods and maintain high standards of quality for all processes.**
- 23) Review the quality of all materials at the site and ensure compliance with all project specifications and quality and collaborate with the department for all material procurement and maintain a quality of materials.**
- 24) Supervise the effective implementation of all test and inspection schedules and ensure adherence to all procedures and coordinate with various teams to**



25) Assist with employees to ensure knowledge of all quality standards and ensure compliance to all quality manuals and procedures and collaborate with contractors and suppliers to maintain the quality of all systems.

The description of the procedure/ sequence:

Figure 1: Typical Reinforcement Detail for a Column. This technical drawing shows a cross-section of a reinforced concrete column. The column is rectangular with a width  $b$  and height  $h$ . It is surrounded by a concrete slab. The reinforcement includes longitudinal bars (top and bottom) and transverse bars (stirrups). Labels indicate 'Negative reinforcement', 'Stirrups', 'Development length', 'Positive reinforcement', 'Column', 'Slab', 'Reinforcing bar', and 'Concrete'. A note at the bottom states: 'Note: L = Spacing between columns'.

- 1) **Site Preparation:** Clean the site and prepare it for construction activities. Mark the locations for installing the drop panels according to the engineering design.
- 2) **Installation of Drop Panels:** Install the drop panels according to the engineered specifications. Ensure they are properly aligned and securely fixed in place.



**3) Installation of Horizontal and Vertical Supports:** Install horizontal supports (beams) and vertical supports (columns) that connect the drop panels and

support the overall roof structure.

- 4) **Reinforcement Placement:** If required, place reinforcement bars (rebar) according to the design specifications for added strength and durability.



Figure 23

- 5) **Curing Process:** Allow the concrete to cure properly to achieve the desired strength and stability. Implement curing techniques such as water curing or using curing compounds as per the engineering recommendations.
- 6) **Installation of Roofing Materials:** Once the concrete has cured, proceed with the installation of roofing materials such as insulation, waterproofing membranes, and final roofing elements.
- 7) **Finishing Touches:** Complete any finishing touches such as adding insulation, sealing joints, and applying protective coatings as necessary.
- 8) **Quality Inspection:** Conduct a thorough inspection of the completed work to ensure it meets quality standards and engineering specifications.

### 6.7 Equipment and Tools:

- 1) **Concrete mixer :** used to mix concrete in large quantities and ensure its homogeneity.



Figure24 : Concrete mixer

- 2) **Concrete Pump (Optional) :** Can be used to pump concrete to the site more effectively, especially if the ceiling is high or not easily accessible.



Figurer25 : Concrete Pump

- 3) Molds for pouring concrete : used to form concrete correctly according to the specified design.
- 4) Reinforcing tools : This includes the reinforcing steel and the cutting and shaping tools required for its installation.
- 5) Spraying and cleaning equipment : used to clean and prepare the roof surface before pouring concrete and spraying insulating materials when needed.
- 6) Measuring and auxiliary tools : such as a ruler, scale, and angles to measure and determine locations accurately.




Figure 26

- 7) Personal safety equipment : such as safety helmet, goggles, work gloves, and safety shoes to protect workers.
- 8) Finishing tools : such as smoothing tools, air compressors, and other finishing tools necessary to complete the work properly.
- 9) Lifting and guiding equipment (optional) : Used to lift heavy materials to elevated locations and guide them accurately.
- 10) Cure and maintenance equipment : used to care for concrete after it has been poured, such as blankets, sprayers, and maintenance equipment.

## 6.8 QA/QC Engineer:

- 1) Develop and determine all standards to perform inspection and tests on all procedures and oversee all testing methods and maintain high standards of quality for all processes.

- 2) Review the quality of all materials at the site and ensure compliance with all project specifications and quality and collaborate with the department for all material procurement and maintain a quality of materials.
- 3) Supervise the effective implementation of all test and inspection schedules and ensure adherence to all procedures and coordinate with various teams to perform quality audits on processes.
- 4) Assist with employees to ensure knowledge of all quality standards and ensure compliance to all quality manuals and procedures and collaborate with contractors and suppliers to maintain the quality of all systems.




# Chapter (7)


# Work Breakdown Structure (WBS)

## 7.1 work breakdown structure (WBS)

a visual, hierarchical and deliverable-oriented deconstruction of a project. It is a helpful diagram for project managers because it allows them to break down their project scope and visualize all the tasks required to complete their projects.

Table 4 WBS








| WBS Name                                                                                                            | WBS Code                                | TotalActivities |
|---------------------------------------------------------------------------------------------------------------------|-----------------------------------------|-----------------|
|  Tanta General Hospital-Final      | T.GH-8                                  | 259             |
|  Milestones                        | T.GH-8.MileStone                        | 12              |
|  Key dates                         | T.GH-8.MileStone.Key dates              | 2               |
|  Contractual                       | T.GH-8.MileStone.1                      | 3               |
|  Controls                          | T.GH-8.MileStone.2                      | 7               |
|  Mobilization works                | T.GH-8.mobilization works               | 5               |
|  Fence                             | T.GH-8.mobilization works.( fence )     | 2               |
|  Carvans                           | T.GH-8.mobilization works.( carvans )   | 1               |
|  Lighting                          | T.GH-8.mobilization works.( lighting )  | 1               |
|  Surveying                         | T.GH-8.mobilization works.( Surveying ) | 1               |
|  Engineering                       | T.GH-8.eng                              | 4               |
|  Procurement                       | T.GH-8.proc                             | 6               |
|  Arch Material                     | T.GH-8.proc.Arch                        | 2               |
|  Civil Material                   | T.GH-8.proc.Elec                        | 2               |
|  MEP Material                    | T.GH-8.proc.Mech                        | 2               |
|  Construction                    | T.GH-8.cons                             | 232             |
|  Sup Structure Works             | T.GH-8.cons.sup                         | 15              |
|  Soil Works                      | T.GH-8.cons.sup.soil                    | 4               |
|  Concrete Works                  | T.GH-8.cons.sup.conc                    | 8               |
|  Foundation Works                | T.GH-8.cons.sup.conc.Foundation         | 8               |
|  PC for Foundation Works         | T.GH-8.cons.sup.conc.Foundation.PC      | 3               |
|  RC for Foundation Works         | T.GH-8.cons.sup.conc.Foundation.RC      | 5               |
|  Arch Works                      | T.GH-8.cons.sup.Arch                    | 3               |
|  Super structure Works           | T.GH-8.cons.Super                       | 217             |
|  Ground Floor Works              | T.GH-8.cons.Super.GF                    | 39              |
|  Concrete Works for Ground floor | T.GH-8.cons.Super.GF.Conc               | 16              |
|  Columns for Ground floor        | T.GH-8.cons.Super.GF.Conc.Col           | 4               |

|                                                                                     |                                  |                                    |    |
|-------------------------------------------------------------------------------------|----------------------------------|------------------------------------|----|
|    | Slab for Ground floor            | T.G.H-8.cons.Super.GF.Conc.slab    | 4  |
|    | Marginal Beam for Ground floor   | T.G.H-8.cons.Super.GF.Conc.beam    | 4  |
|    | Stairs for Ground Floor          | T.G.H-8.cons.Super.GF.Conc.Stairs  | 4  |
|    | Finishing Works for Ground Floor | T.G.H-8.cons.Super.GF.Finish       | 23 |
|    | First Floor Works                | T.G.H-8.cons.Super.1st             | 39 |
|    | Concrete Works for First floor   | T.G.H-8.cons.Super.1st.Conc        | 16 |
|    | Columns for First floor          | T.G.H-8.cons.Super.1st.Conc.Col    | 4  |
|    | Slab for First floor             | T.G.H-8.cons.Super.1st.Conc.slab   | 4  |
|    | Marginal Beam for First floor    | T.G.H-8.cons.Super.1st.Conc.beam   | 4  |
|    | Stairs for First Floor           | T.G.H-8.cons.Super.1st.Conc.Stairs | 4  |
|    | Finishing Works for First Floor  | T.G.H-8.cons.Super.1st.Finish      | 23 |
|    | Second Floor Works               | T.G.H-8.cons.Super.2nd             | 39 |
|    | Concrete Works for Second floor  | T.G.H-8.cons.Super.2nd.Conc        | 16 |
|    | Columns for Second floor         | T.G.H-8.cons.Super.2nd.Conc.Col    | 4  |
|    | Slab for Second floor            | T.G.H-8.cons.Super.2nd.Conc.slab   | 4  |
|    | Marginal Beam for Second floor   | T.G.H-8.cons.Super.2nd.Conc.beam   | 4  |
|    | Stairs for Second Floor          | T.G.H-8.cons.Super.2nd.Conc.Stairs | 4  |
|    | Finishing Works for Second Floor | T.G.H-8.cons.Super.2nd.Finish      | 23 |
|    | Third Floor Works                | T.G.H-8.cons.Super.3rd             | 39 |
|    | Concrete Works for Third floor   | T.G.H-8.cons.Super.3rd.Conc        | 16 |
|    | Columns for Third floor          | T.G.H-8.cons.Super.3rd.Conc.Col    | 4  |
|    | Slab for Third floor             | T.G.H-8.cons.Super.3rd.Conc.slab   | 4  |
|    | Marginal Beam for Third floor    | T.G.H-8.cons.Super.3rd.Conc.beam   | 4  |
|    | Stairs for Third Floor           | T.G.H-8.cons.Super.3rd.Conc.Stairs | 4  |
|    | Finishing Works for Third Floor  | T.G.H-8.cons.Super.3rd.Finish      | 23 |
|    | Fourth Floor Works               | T.G.H-8.cons.Super.4th             | 39 |
|    | Concrete Works for Fourth floor  | T.G.H-8.cons.Super.4th.Conc        | 16 |
|   | Columns for Fourth floor         | T.G.H-8.cons.Super.4th.Conc.Col    | 4  |
|  | Slab for Fourth floor            | T.G.H-8.cons.Super.4th.Conc.slab   | 4  |
|  | Marginal Beam for Fourth floor   | T.G.H-8.cons.Super.4th.Conc.beam   | 4  |
|  | Stairs for Fourth Floor          | T.G.H-8.cons.Super.4th.Conc.Stairs | 4  |
|  | Finishing Works for Fourth Floor | T.G.H-8.cons.Super.4th.Finish      | 23 |
|  | Roof works                       | T.G.H-8.cons.Super.Roof            | 8  |
|  | Finishing Works for Roof         | T.G.H-8.cons.Super.Roof.Finish     | 8  |
|  | Elevators                        | T.G.H-8.cons.Super.Elevator        | 2  |
|  | Parapets                         | T.G.H-8.cons.Super.Parapets        | 4  |
|  | Cladding Works                   | T.G.H-8.cons.Super.Cladding        | 5  |
|  | General Site                     | T.G.H-8.cons.Super.GS              | 3  |



## Chapter (8)

# **BIM Modeling & Quantity Take off**

## **8.1 What is BIM?**

Building information modeling (BIM) is the holistic process of creating and managing information for a built asset. Based on an intelligent model and enabled by a cloud platform, BIM integrates structured, multi-disciplinary data to produce a digital representation of an asset across its lifecycle, from planning and design to construction and operations.

## **8.2 The BIM growth forecast**

Want to know the future for BIM? Or see how we stack up to our competitors? By analyzing global revenue and trends, Frost & Sullivan's report identifies strategic imperatives, growth opportunities, and has reviewed every major software provider out there. Perfect for BIM users and the BIM-curious alike. Dive in.

## **8.3 BIM Model (3D Modeling)**




Figure 27 project 3D modelling




Figure 28 Project 3D footing




Figure29:-3D column necks




Figure29:-3D ground floor




Figure 30 Project 3D columns and beams




Figure 31:-3D stair model



Table 5 Quantity take off from Revit for concrete for the project

| REVIT                                              |                         |              |
|----------------------------------------------------|-------------------------|--------------|
| Family and Type                                    | Material: Volume        | Level        |
| Floor: slab 0.15                                   | 11.357 m <sup>3</sup>   | slab I 28.75 |
| slab I 28.75: 1                                    | 11.357 m <sup>3</sup>   |              |
| Floor: slab 0.25m                                  | 18.550 m <sup>3</sup>   | slab I 26.75 |
| slab I 26.75: 1                                    | 18.550 m <sup>3</sup>   |              |
| Floor: slab 0.16                                   | 12.158 m <sup>3</sup>   | slab I 25.55 |
| slab I 25.55: 1                                    | 12.158 m <sup>3</sup>   |              |
| Concrete-Rectangular-Column: coulumn 0.3x0.6       | 1.238 m <sup>3</sup>    | fourth       |
| Concrete-Rectangular-Column: coulumn 0.3x0.65      | 1.338 m <sup>3</sup>    | fourth       |
| Concrete-Rectangular-Column: coulumn 0.25x0.40     | 17.695 m <sup>3</sup>   | fourth       |
| Concrete-Rectangular-Column: coulumn 0.300x1 2     | 1.028 m <sup>3</sup>    | fourth       |
| Concrete-Rectangular-Column: coulumn 0.300x1.300 2 | 1.334 m <sup>3</sup>    | fourth       |
| Concrete-Rectangular-Column: coulumn 0.400x1.500 2 | 2.035 m <sup>3</sup>    | fourth       |
| Concrete-Rectangular-Column: coulumn 0.400x2.00    | 2.710 m <sup>3</sup>    | fourth       |
| Floor: D.panle 0.45m                               | 200.073 m <sup>3</sup>  | fourth       |
| Floor: slab 0.30m                                  | 1466.179 m <sup>3</sup> | fourth       |
| fourth: 41                                         | 1693.630 m <sup>3</sup> |              |
| Concrete-Rectangular-Column: coulumn0.65x0.65      | 16.478 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.3x0.6       | 2.106 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.3x0.8       | 1.872 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.4x0.8       | 11.232 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.30x0.65 2   | 10.647 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.35x0.65     | 1.775 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.45x0.45     | 2.369 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.60x1.60     | 3.600 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.75x0.55     | 22.527 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.85x0.85     | 11.054 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.300 x0.800  | 1.872 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.300x1 2     | 12.870 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.300x1.300 2 | 28.782 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.300x1.600 2 | 1.800 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.350x1       | 1.365 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.350x1.300   | 1.775 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.400x1.500 2 | 9.360 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.400x2.00    | 15.000 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.400x2.400   | 18.144 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.400x2.600   | 3.900 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.500x1.450   | 13.594 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.600x1600    | 21.600 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 0.650x1600 2  | 3.900 m <sup>3</sup>    | third        |
| Concrete-Rectangular-Column: coulumn 0.800x1.300   | 31.200 m <sup>3</sup>   | third        |
| Concrete-Rectangular-Column: coulumn 1x1           | 18.900 m <sup>3</sup>   | third        |
| Floor: D.panle 0.45m                               | 200.073 m <sup>3</sup>  | third        |



|                                                   |                         |         |
|---------------------------------------------------|-------------------------|---------|
| Concrete-Rectangular-Column: coulmn 0.350x1.300   | 1.845 m <sup>3</sup>    | first   |
| Concrete-Rectangular-Column: coulmn 0.400x1.500 2 | 9.360 m <sup>3</sup>    | first   |
| Concrete-Rectangular-Column: coulmn 0.400x2.00    | 15.000 m <sup>3</sup>   | first   |
| Concrete-Rectangular-Column: coulmn 0.400x2.400   | 18.144 m <sup>3</sup>   | first   |
| Concrete-Rectangular-Column: coulmn 0.400x2.600   | 3.900 m <sup>3</sup>    | first   |
| Concrete-Rectangular-Column: coulmn 0.500x1.450   | 13.594 m <sup>3</sup>   | first   |
| Concrete-Rectangular-Column: coulmn 0.600x1600    | 21.600 m <sup>3</sup>   | first   |
| Concrete-Rectangular-Column: coulmn 0.650x1600 2  | 3.900 m <sup>3</sup>    | first   |
| Concrete-Rectangular-Column: coulmn 0.800x1.300   | 31.200 m <sup>3</sup>   | first   |
| Concrete-Rectangular-Column: coulmn 1x1           | 18.900 m <sup>3</sup>   | first   |
| Floor: D.panle 0.45m                              | 200.073 m <sup>3</sup>  | first   |
| Floor: slab 0.16                                  | 98.810 m <sup>3</sup>   | first   |
| Floor: slab 0.25m                                 | 83.623 m <sup>3</sup>   | first   |
| Floor: slab 0.30m                                 | 1373.403 m <sup>3</sup> | first   |
| first: 157                                        | 2023.925 m <sup>3</sup> |         |
|                                                   |                         |         |
| Concrete-Rectangular-Column: coulmn0.65x0.65      | 18.650 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.3x0.6       | 2.354 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.3x0.8       | 2.093 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.4x0.8       | 12.557 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.30x0.65 2   | 11.903 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.35x0.65     | 1.984 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.45x0.45     | 2.649 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.60x1.60     | 4.042 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.75x0.55     | 25.179 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.85x0.85     | 12.384 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.300 x0.800  | 2.093 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.300x1 2     | 14.388 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.300x1.300 2 | 32.191 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.300x1.600 2 | 2.021 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.350x1       | 1.526 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.350x1.300   | 2.054 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.400x1.500 2 | 10.464 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.400x2.00    | 16.840 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.400x2.400   | 20.352 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.400x2.600   | 4.378 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.500x1.450   | 15.261 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.600x1600    | 24.250 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 0.650x1600 2  | 4.378 m <sup>3</sup>    | ground  |
| Concrete-Rectangular-Column: coulmn 0.800x1.300   | 35.027 m <sup>3</sup>   | ground  |
| Concrete-Rectangular-Column: coulmn 1x1           | 21.200 m <sup>3</sup>   | ground  |
| Floor: D.panle 0.45m                              | 221.412 m <sup>3</sup>  | ground  |
| Floor: slab 0.25m                                 | 33.715 m <sup>3</sup>   | ground  |
| Floor: slab 0.30m                                 | 1557.884 m <sup>3</sup> | ground  |
| r sec: 0.65x130                                   | 39.516 m <sup>3</sup>   | ground  |
| ground: 159                                       | 2152.744 m <sup>3</sup> |         |
|                                                   |                         |         |
| Concrete-Rectangular-Column: column 1.25x1        | 6.125 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn0.65x0.65      | 51.058 m <sup>3</sup>   | Level 1 |

|                                                  |                          |         |
|--------------------------------------------------|--------------------------|---------|
| Concrete-Rectangular-Column: coulmn 0.4x0.8      | 14.688 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.35x0.65    | 36.957 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.35x1       | 5.355 m <sup>3</sup>     | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.45x0.45    | 6.480 m <sup>3</sup>     | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.60x1.60    | 4.560 m <sup>3</sup>     | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.75x0.55    | 29.453 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.85x0.85    | 14.269 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.350x1      | 14.280 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.350x1.300  | 50.073 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.350x1.600  | 13.972 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.400x2.00   | 19.640 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.400x2.400  | 23.184 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.400x2.600  | 4.940 m <sup>3</sup>     | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.500x1.450  | 17.654 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.600x1600   | 27.744 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.650x1600 2 | 4.940 m <sup>3</sup>     | Level 1 |
| Concrete-Rectangular-Column: coulmn 0.800x1.300  | 39.728 m <sup>3</sup>    | Level 1 |
| Concrete-Rectangular-Column: coulmn 1x1          | 19.750 m <sup>3</sup>    | Level 1 |
| Floor: slab clean 20cm                           | 1314.244 m <sup>3</sup>  | Level 1 |
| Floor: slab 0.25m                                | 79.318 m <sup>3</sup>    | Level 1 |
| Floor: Frist floor slab                          | 1642.806 m <sup>3</sup>  | Level 1 |
| Floor: foundation 130 cm                         | 8542.589 m <sup>3</sup>  | Level 1 |
| Footing-Rectangular: footing R 3m x 4m x 0.20m   | 72.000 m <sup>3</sup>    | Level 1 |
| Level 1: 364                                     | 12055.807 m <sup>3</sup> |         |
|                                                  |                          |         |
| Concrete-Rectangular Beam: Beam 0.12X0.80 2      | 0.743 m <sup>3</sup>     |         |
| Concrete-Rectangular Beam: Beam 0.25X0.70        | 28.992 m <sup>3</sup>    |         |
| Concrete-Rectangular Beam: Beam 0.25X0.80        | 268.918 m <sup>3</sup>   |         |
| Concrete-Rectangular Beam: Beam 0.25X0.90        | 35.783 m <sup>3</sup>    |         |
| Concrete-Rectangular Beam: Beam 0.40X0.80 2      | 4.066 m <sup>3</sup>     |         |
| Concrete-Rectangular Beam: Beam 0.65X130         | 71.623 m <sup>3</sup>    |         |
| Concrete-Rectangular Beam:                       | 1.709 m <sup>3</sup>     |         |
| : 457                                            | 411.834 m <sup>3</sup>   |         |
|                                                  |                          |         |
| Basic Wall: shear wall 0.25m                     | 482.328 m <sup>3</sup>   |         |
| Cast-In-Place Stair: Monolithic Stair 2 0.22     | 155.520 m <sup>3</sup>   |         |
| Cast-In-Place Stair: Monolithic Stair 2 0.28     | 15.220 m <sup>3</sup>    |         |
| Monolithic Landing: 7" Thickness                 | 43.052 m <sup>3</sup>    |         |
| Monolithic Run: 3/4" Nosing                      | 127.688 m <sup>3</sup>   |         |
| : 225                                            | 823.808 m <sup>3</sup>   |         |
| Grand total: 1718                                | 23053.482 m <sup>3</sup> |         |



|                                                   |                         |        |
|---------------------------------------------------|-------------------------|--------|
| Floor: slab 0.25m                                 | 83.563 m <sup>3</sup>   | third  |
| Floor: slab 0.30m                                 | 1373.330 m <sup>3</sup> | third  |
| third: 156                                        | 1924.687 m <sup>3</sup> |        |
| Concrete-Rectangular-Column: coulmn0.65x0.65      | 16.707 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.3x0.6       | 2.106 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.3x0.8       | 1.872 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.4x0.8       | 11.232 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.30x0.65 2   | 10.647 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.35x0.65     | 1.775 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.45x0.45     | 2.369 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.60x1.60     | 3.600 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.75x0.55     | 22.523 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.85x0.85     | 11.054 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.300 x0.800  | 1.872 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.300x1 2     | 12.870 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.300x1.300 2 | 28.782 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.300x1.600 2 | 1.800 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.350x1       | 1.365 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.350x1.300   | 1.845 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.400x1.500 2 | 9.360 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.400x2.00    | 15.000 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.400x2.400   | 18.144 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.400x2.600   | 3.900 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.500x1.450   | 13.594 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.600x1600    | 21.600 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 0.650x1600 2  | 3.900 m <sup>3</sup>    | second |
| Concrete-Rectangular-Column: coulmn 0.800x1.300   | 31.200 m <sup>3</sup>   | second |
| Concrete-Rectangular-Column: coulmn 1x1           | 18.900 m <sup>3</sup>   | second |
| Floor: D.panle 0.45m                              | 200.073 m <sup>3</sup>  | second |
| Floor: slab 0.25m                                 | 83.563 m <sup>3</sup>   | second |
| Floor: slab 0.30m                                 | 1373.330 m <sup>3</sup> | second |
| second: 156                                       | 1924.981 m <sup>3</sup> |        |
| Concrete-Rectangular-Column: coulmn0.65x0.65      | 16.707 m <sup>3</sup>   | first  |
| Concrete-Rectangular-Column: coulmn 0.3x0.6       | 2.106 m <sup>3</sup>    | first  |
| Concrete-Rectangular-Column: coulmn 0.3x0.8       | 1.872 m <sup>3</sup>    | first  |
| Concrete-Rectangular-Column: coulmn 0.4x0.8       | 11.232 m <sup>3</sup>   | first  |
| Concrete-Rectangular-Column: coulmn 0.30x0.65 2   | 10.647 m <sup>3</sup>   | first  |
| Concrete-Rectangular-Column: coulmn 0.35x0.65     | 1.775 m <sup>3</sup>    | first  |
| Concrete-Rectangular-Column: coulmn 0.45x0.45     | 2.369 m <sup>3</sup>    | first  |
| Concrete-Rectangular-Column: coulmn 0.60x1.60     | 3.600 m <sup>3</sup>    | first  |
| Concrete-Rectangular-Column: coulmn 0.75x0.55     | 22.523 m <sup>3</sup>   | first  |
| Concrete-Rectangular-Column: coulmn 0.85x0.85     | 11.054 m <sup>3</sup>   | first  |
| Concrete-Rectangular-Column: coulmn 0.300 x0.800  | 1.872 m <sup>3</sup>    | first  |
| Concrete-Rectangular-Column: coulmn 0.300x1 2     | 12.870 m <sup>3</sup>   | first  |
| Concrete-Rectangular-Column: coulmn 0.300x1.300 2 | 28.782 m <sup>3</sup>   | first  |
| Concrete-Rectangular-Column: coulmn 0.300x1.600 2 | 1.800 m <sup>3</sup>    | first  |
| Concrete-Rectangular-Column: coulmn 0.350x1       | 1.365 m <sup>3</sup>    | first  |

## 8.4 (ASD) Auto cad Structure Details







Figure 32 Auto cad Structure Details






Table 6 Quantity of steel

| T                  | # 18    | # 20    | # 22     |
|--------------------|---------|---------|----------|
| Unit weight (kg/m) | 2.0     | 2.5     | 3.0      |
| Total length (m)   | 91163.4 | 11826.0 | 136987.5 |
| Total weight (t)   | 182.3   | 29.2    | 411.0    |





Table 7 Details of steel



| Bar mark |   | Size | Length | Type | A    | B    | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|------|------|-----|---------------------------------------------------------------------------------------|----------------|
| 17       | 1 | 18   | 12.0   | 11   | 1.2  | 10.8 |     |    | 7.4            |
| 18       | 1 | 18   | 12.0   | 00   | 12.0 |      |     |  | 7.4            |
| 19       | 1 | 18   | 12.0   | 00   | 12.0 |      |     |  | 7.4            |
| 20       | 1 | 18   | 12.0   | 00   | 12.0 |      |     |  | 7.4            |
| 21       | 1 | 18   | 12.0   | 00   | 12.0 |      |     |  | 7.4            |


| Bar mark |   | Size | Length | Type | A    | B   | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|------|-----|-----|---------------------------------------------------------------------------------------|----------------|
| 22       | 1 | 18   | 12.0   | 00   | 12.0 |     |     |    | 7.4            |
| 23       | 1 | 18   | 12.0   | 00   | 12.0 |     |     |    | 7.4            |
| 24       | 1 | 18   | 12.0   | 00   | 12.0 |     |     |  | 7.4            |
| 25       | 1 | 18   | 12.0   | 00   | 12.0 |     |     |  | 7.4            |
| 26       | 1 | 18   | 10.0   | 11   | 8.8  | 1.2 |     |  | 6.1            |




| Bar mark |   | Size | Length | Type | A    | B    | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|------|------|-----|---------------------------------------------------------------------------------------|----------------|
| 27       | 1 | 18   | 12.0   | 11   | 1.2  | 10.8 |     |    | 12.7           |
| 28       | 1 | 18   | 12.0   | 00   | 12.0 |      |     |   | 12.7           |
| 29       | 1 | 18   | 12.0   | 00   | 12.0 |      |     |  | 12.7           |
| 30       | 1 | 18   | 12.0   | 00   | 12.0 |      |     |  | 12.7           |
| 31       | 1 | 18   | 12.0   | 00   | 12.0 |      |     |  | 12.7           |





| Bar mark |   | Size | Length | Type | A   | B   | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|-----|-----|---------------------------------------------------------------------------------------|----------------|
| 32       | 1 | 18   | 9.4    | 11   | 8.3 | 1.2 |     |    | 10.0           |
| 33       | 1 | 20   | 3.0    |      | 0.3 | 0.3 |     |   | 29.2           |
| 34       | 1 | 22   | 4.0    | 00   | 4.0 |     |     |  | 5.0            |
| 35       | 1 | 22   | 4.0    | 00   | 4.0 |     |     |  | 6.7            |
| 36       | 1 | 22   | 6.0    | 00   | 6.0 |     |     |  | 6.7            |




| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 37       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 1.0            |
| 38       | 1 | 18   | 4.0    | 00   | 4.0 |   |     |  | 3.5            |
| 39       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2            |
| 40       | 1 | 22   | 3.5    | 00   | 3.5 |   |     |  | 0.6            |
| 41       | 1 | 22   | 3.0    | 00   | 3.0 |   |     |  | 0.3            |

| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 42       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.5            |
| 43       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2            |
| 44       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.6            |
| 45       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.4            |
| 46       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.5            |





| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 47       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.6            |
| 48       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.8            |
| 49       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.3            |
| 50       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9            |
| 51       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.4            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 52       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.9            |
| 53       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2            |
| 54       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.5            |
| 55       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.5            |
| 56       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.4            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t)       |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------------|
| 57       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.9                  |
| 58       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9                  |
| 59       | 1 | 18   | 4.0    | 00   | 4.0 |   |     |  | 0.2                  |
| 60       | 1 | 18   | 4.0    | 00   | 4.0 |   |     |  | $7.2 \times 10^{-2}$ |
| 61       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.3                  |






| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 62       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.9            |
| 63       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9            |
| 64       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.5            |
| 65       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 66       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9            |





| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 67       | 1 | 18   | 3.0    | 00   | 3.0 |   |     |    | $3.6e-02$      |
| 68       | 1 | 18   | 3.0    | 00   | 3.0 |   |     |  | $5.4e-02$      |
| 69       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.1            |
| 70       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 71       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |




| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 72       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.5            |
| 73       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 74       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9            |
| 75       | 1 | 22   | 9.0    | 00   | 9.0 |   |     |  | 2.4            |
| 76       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.1            |

| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 77       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.2            |
| 78       | 1 | 18   | 5.0    | 00   | 5.0 |   |     |    | 1.2            |
| 79       | 1 | 18   | 7.0    | 00   | 7.0 |   |     |  | 6.9            |
| 80       | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 1.2            |
| 81       | 1 | 18   | 3.0    | 00   | 3.0 |   |     |  | 0.4            |




| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 82       | 1 | 18   | 6.0    | 00   | 6.0 |   |     |    | 4.9            |
| 83       | 1 | 18   | 7.0    | 00   | 7.0 |   |     |    | 5.2            |
| 84       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 3.6            |
| 85       | 1 | 18   | 5.0    | 00   | 5.0 |   |     |  | 0.8            |
| 86       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 87       | 1 | 22   | 7.0    | 00   | 7.0 |   |     |    | 11.7           |
| 88       | 1 | 18   | 4.0    | 00   | 4.0 |   |     |    | 0.6            |
| 89       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 90       | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.6            |
| 91       | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9            |

| Bar mark |   | Size | Length | Type | A    | B | E/R | Symbol (m)                                                                            | Total mass (t)       |
|----------|---|------|--------|------|------|---|-----|---------------------------------------------------------------------------------------|----------------------|
| 92       | 1 | 18   | 4.0    | 00   | 4.0  |   |     |    | 0.6                  |
| 93       | 1 | 22   | 5.0    | 00   | 5.0  |   |     |    | 0.9                  |
| 94       | 1 | 18   | 3.0    | 00   | 3.0  |   |     |  | $7.2 \times 10^{-2}$ |
| 95       | 1 | 22   | 10.0   | 00   | 10.0 |   |     |  | 5.8                  |
| 96       | 1 | 22   | 4.5    | 00   | 4.5  |   |     |  | 8.9                  |





| Bar mark |   | Size | Length | Type | A    | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|------|---|-----|---------------------------------------------------------------------------------------|----------------|
| 97       | 1 | 22   | 12.0   | 00   | 12.0 |   |     |    | 11.1           |
| 98       | 1 | 22   | 5.0    | 00   | 5.0  |   |     |    | 1.3            |
| 99       | 1 | 22   | 4.0    | 00   | 4.0  |   |     |  | 0.3            |
| 100      | 1 | 22   | 5.0    | 00   | 5.0  |   |     |  | 0.5            |
| 101      | 1 | 22   | 7.0    | 00   | 7.0  |   |     |  | 1.5            |







| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 102      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |    | 1.3            |
| 103      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |    | 1.3            |
| 104      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 2.5            |
| 105      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2            |
| 106      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.4            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 107      | 1 | 18   | 4.0    | 00   | 4.0 |   |     |    | 8.0e-03        |
| 108      | 1 | 18   | 6.0    | 00   | 6.0 |   |     |    | 0.5            |
| 109      | 1 | 18   | 6.0    | 00   | 6.0 |   |     |  | 0.5            |
| 110      | 1 | 22   | 8.0    | 00   | 8.0 |   |     |  | 4.9            |
| 111      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.4            |





| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 112      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.2            |
| 113      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |   | 2.5            |
| 114      | 1 | 22   | 7.0    | 00   | 7.0 |   |     |  | 3.7            |
| 115      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.1            |
| 116      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2            |

| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 117      | 1 | 22   | 3.5    | 00   | 3.5 |   |     |    | 0.2            |
| 118      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |    | 1.4            |
| 119      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 1.0            |
| 120      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9            |
| 121      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.6            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 122      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.1            |
| 123      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.1            |
| 124      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.3            |
| 125      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2            |
| 126      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.1            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t)       |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------------|
| 127      | 1 | 18   | 4.0    | 00   | 4.0 |   |     |    | $7.2 \times 10^{-2}$ |
| 128      | 1 | 22   | 3.5    | 00   | 3.5 |   |     |    | 0.2                  |
| 129      | 1 | 22   | 7.0    | 00   | 7.0 |   |     |  | 2.0                  |
| 130      | 1 | 22   | 8.0    | 00   | 8.0 |   |     |  | 2.3                  |
| 131      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7                  |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 132      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |    | 1.1            |
| 133      | 1 | 22   | 3.0    | 00   | 3.0 |   |     |   | 0.3            |
| 134      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.6            |
| 135      | 1 | 18   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 136      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.6            |


| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 137      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.5            |
| 138      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.9            |
| 139      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 140      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 141      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.5            |




| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 142      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.9            |
| 143      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.8            |
| 144      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 145      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.5            |
| 146      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |





| Bar mark |   | Size | Length | Type | A    | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|------|---|-----|---------------------------------------------------------------------------------------|----------------|
| 147      | 1 | 22   | 4.0    | 00   | 4.0  |   |     |    | 0.4            |
| 148      | 1 | 18   | 12.0   | 00   | 12.0 |   |     |    | 0.7            |
| 149      | 1 | 22   | 4.0    | 00   | 4.0  |   |     |  | 0.4            |
| 150      | 1 | 22   | 4.0    | 00   | 4.0  |   |     |  | 0.4            |
| 151      | 1 | 22   | 5.0    | 00   | 5.0  |   |     |  | 1.7            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t)       |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------------|
| 152      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.4                  |
| 153      | 1 | 18   | 6.0    | 00   | 6.0 |   |     |    | 0.3                  |
| 154      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 1.3                  |
| 155      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7                  |
| 156      | 1 | 18   | 3.0    | 00   | 3.0 |   |     |  | $3.6 \times 10^{-2}$ |

| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 157      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.2            |
| 158      | 1 | 22   | 3.5    | 00   | 3.5 |   |     |    | 0.2            |
| 159      | 1 | 18   | 6.0    | 00   | 6.0 |   |     |  | 1.9            |
| 160      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 1.1            |
| 161      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.8            |






| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 162      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.6            |
| 163      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.6            |
| 164      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.6            |
| 165      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.6            |
| 166      | 1 | 18   | 5.0    | 00   | 5.0 |   |     |  | 1.3            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 167      | 1 | 22   | 8.0    | 00   | 8.0 |   |     |    | 1.6            |
| 168      | 1 | 22   | 8.0    | 00   | 8.0 |   |     |    | 0.9            |
| 169      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.3            |
| 170      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.1            |
| 171      | 1 | 18   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |

| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 172      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 1.3            |
| 173      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.9            |
| 174      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 2.0            |
| 175      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 2.0            |
| 176      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 1.0            |

| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 177      | 1 | 22   | 7.0    | 00   | 7.0 |   |     |    | 2.4            |
| 178      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.9            |
| 179      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 2.0            |
| 180      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 1.3            |
| 181      | 1 | 22   | 7.0    | 00   | 7.0 |   |     |  | 3.4            |







| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 182      | 1 | 18   | 3.0    | 00   | 3.0 |   |     |    | 0.5            |
| 183      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 1.0            |
| 184      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 2.2            |
| 185      | 1 | 18   | 3.0    | 00   | 3.0 |   |     |  | 0.4            |
| 186      | 1 | 22   | 3.0    | 00   | 3.0 |   |     |  | 0.2            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 187      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.7            |
| 188      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.4            |
| 189      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 190      | 1 | 18   | 5.0    | 00   | 5.0 |   |     |  | 0.1            |
| 191      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2            |





| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 192      | 1 | 22   | 3.5    | 00   | 3.5 |   |     |    | 0.2            |
| 193      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.9            |
| 194      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 195      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.4            |
| 196      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.3            |

| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 197      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.5            |
| 198      | 1 | 18   | 4.0    | 00   | 4.0 |   |     |    | 2.6            |
| 199      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2            |
| 200      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.5            |
| 201      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.5            |





| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 202      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.1            |
| 203      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.5            |
| 204      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.7            |
| 205      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.4            |
| 206      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 1.1            |



| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 207      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.9            |
| 208      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.2            |
| 209      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 1.1            |
| 210      | 1 | 22   | 6.0    | 00   | 6.0 |   |     |  | 1.1            |
| 211      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.4            |


| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 212      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.2            |
| 213      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.9            |
| 214      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.6            |
| 215      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9            |
| 216      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.5            |

| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 217      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.1            |
| 218      | 1 | 22   | 3.5    | 00   | 3.5 |   |     |    | 0.2            |
| 219      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.5            |
| 220      | 1 | 22   | 3.5    | 00   | 3.5 |   |     |  | 0.2            |
| 221      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9            |




| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t)      |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|---------------------|
| 222      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.9                 |
| 223      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.2                 |
| 224      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.9                 |
| 225      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 1.5e-0 <sub>2</sub> |
| 226      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.4                 |


| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t)       |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------------|
| 227      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.7                  |
| 228      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |    | 0.6                  |
| 229      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2                  |
| 230      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.1                  |
| 231      | 1 | 18   | 3.0    | 00   | 3.0 |   |     |  | $5.4 \times 10^{-2}$ |


| Bar mark |   | Size | Length | Type | A   | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|-----|---|-----|---------------------------------------------------------------------------------------|----------------|
| 232      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 1.1            |
| 233      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |    | 0.8            |
| 234      | 1 | 22   | 5.0    | 00   | 5.0 |   |     |  | 0.4            |
| 235      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.1            |
| 236      | 1 | 22   | 4.0    | 00   | 4.0 |   |     |  | 0.2            |

| Bar mark |   | Size | Length | Type | A    | B    | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|------|------|-----|---------------------------------------------------------------------------------------|----------------|
| 237      | 1 | 18   | 5.0    | 00   | 5.0  |      |     |    | 0.8            |
| 238      | 1 | 22   | 12.0   | 11   | 1.2  | 10.9 |     |   | 19.1           |
| 239      | 1 | 22   | 12.0   | 00   | 12.0 |      |     |  | 19.1           |
| 240      | 1 | 22   | 12.0   | 00   | 12.0 |      |     |  | 19.1           |
| 241      | 1 | 22   | 12.0   | 00   | 12.0 |      |     |  | 19.1           |

| Bar mark |   | Size | Length | Type | A    | B    | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|------|------|-----|---------------------------------------------------------------------------------------|----------------|
| 242      | 1 | 22   | 12.0   | 00   | 12.0 |      |     |    | 19.1           |
| 243      | 1 | 22   | 10.6   | 11   | 9.5  | 1.2  |     |   | 16.9           |
| 244      | 1 | 22   | 12.0   | 11   | 1.2  | 10.9 |     |  | 11.1           |
| 245      | 1 | 22   | 12.0   | 00   | 12.0 |      |     |  | 11.1           |
| 246      | 1 | 22   | 12.0   | 00   | 12.0 |      |     |  | 11.1           |

| Bar mark |   | Size | Length | Type | A    | B | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|------|---|-----|---------------------------------------------------------------------------------------|----------------|
| 247      | 1 | 22   | 12.0   | 00   | 12.0 |   |     |    | 11.1           |
| 248      | 1 | 22   | 12.0   | 00   | 12.0 |   |     |    | 11.1           |
| 249      | 1 | 22   | 12.0   | 00   | 12.0 |   |     |  | 11.1           |
| 250      | 1 | 22   | 12.0   | 00   | 12.0 |   |     |  | 11.1           |
| 251      | 1 | 22   | 12.0   | 00   | 12.0 |   |     |  | 11.1           |

| Bar mark |   | Size | Length | Type | A    | B   | E/R | Symbol (m)                                                                            | Total mass (t) |
|----------|---|------|--------|------|------|-----|-----|---------------------------------------------------------------------------------------|----------------|
| 252      | 1 | 22   | 12.0   | 00   | 12.0 |     |     |    | 11.1           |
| 253      | 1 | 22   | 10.9   | 00   | 10.9 |     |     |  | 10.1           |
| 254      | 1 | 22   | 2.6    | 11   | 1.4  | 1.2 |     |  | 2.4            |



## Chapter (9)



## Detailed Quantity Take of (AutoCAD & Excel)

Detailed estimates: provides a deep dive into the details and costs of a project.

Quantity estimates: This estimate includes the amount of each material needed and the costs associated with that quantity

### 9.1- Quantities Take of AutoCAD:

#### 9.1.1- Quantities Of Building:

**Tabel 8 Total Quantities of Building.**

| Floor          | Area m <sup>2</sup> | BOQ          |
|----------------|---------------------|--------------|
| Ground         | 8652.098            |              |
| Frist          | 7949.829            |              |
| Second         | 6911.661            |              |
| Third          | 6578.487            |              |
| Fourth         | 7322                |              |
| above Roof     | 470                 |              |
| annex building | 1205.5              |              |
| backfill Short | 2662.844            |              |
| <b>Total</b>   | <b>41752.419</b>    | <b>42000</b> |

#### 9.1.2- Quantities Of Plastering:

**Tabel 9 Total Quantities of Oyster.**

| Floor        | Area m <sup>2</sup> | BOQ          |
|--------------|---------------------|--------------|
| Ground       | 14124.846           |              |
| Frist        | 14564.331           |              |
| Second       | 11727.111           |              |
| Third        | 12044.43            |              |
| Fourth       | 15846.618           |              |
| <b>Total</b> | <b>68307.336</b>    | <b>54400</b> |

#### 9.1.3- Quantities Of Ceramic:

**Tabel 10 Total Quantities of Ceramic.**

| Floor        | ceramic         | porcelain      | Vanille        |
|--------------|-----------------|----------------|----------------|
| Ground       | 9388            | 930            | 1004           |
| First        | 4471            | 1558           | 1306           |
| Second       | 5012            | 2319           | 489            |
| Third        | 5657            | 2267           | 0              |
| Fourth       | 6763            | 1813           | 0              |
| <b>Total</b> | <b>31291 m3</b> | <b>8887 m3</b> | <b>2799 m3</b> |




Fig.33 Number of walls for the Plastering




Fig.34 Number of walls for the building

## 9.2- Quantity Take Of Excel:

### 9.2.1-Quantity Of Plastering

Table 11 Quantity of plastering for second floor

| Wall number | Length (m) | Width (m) | Height (m) | Area (m <sup>2</sup> ) | Wall number | Length (m) | Width (m) | Height (m) | Area (m <sup>2</sup> ) |
|-------------|------------|-----------|------------|------------------------|-------------|------------|-----------|------------|------------------------|
| 1           | 1.802      | 0.02      | 3.9        | 7.028                  | 1306        | 0.33       | 0.02      | 3.9        | 1.287                  |
| 2           | 0.531      | 0.02      | 3.9        | 2.071                  | 1307        | 4.207      | 0.02      | 3.9        | 16.407                 |
| 3           | 0.18       | 0.02      | 3.9        | 0.702                  | 1308        | 4.214      | 0.02      | 3.9        | 16.435                 |
| 4           | 1.979      | 0.02      | 3.9        | 7.718                  | 1309        | 0.15       | 0.02      | 3.9        | 0.585                  |
| 5           | 1.801      | 0.02      | 3.9        | 7.024                  | 1310        | 0.51       | 0.02      | 3.9        | 1.989                  |
| 6           | 1.061      | 0.02      | 3.9        | 4.138                  | 1311        | 0.229      | 0.02      | 3.9        | 0.893                  |
| 7           | 0.16       | 0.02      | 3.9        | 0.624                  | 1312        | 0.14       | 0.02      | 3.9        | 0.546                  |
| 8           | 0.16       | 0.02      | 3.9        | 0.624                  | 1313        | 0.16       | 0.02      | 3.9        | 0.624                  |
| 9           | 1.531      | 0.02      | 3.9        | 5.971                  | 1314        | 0.53       | 0.02      | 3.9        | 2.067                  |
| 10          | 0.13       | 0.02      | 3.9        | 0.507                  | 1315        | 0.33       | 0.02      | 3.9        | 1.287                  |
| 11          | 0.16       | 0.02      | 3.9        | 0.624                  | 1316        | 0.16       | 0.02      | 3.9        | 0.624                  |
| 12          | 2.25       | 0.02      | 3.9        | 8.775                  | 1317        | 4.35       | 0.02      | 3.9        | 16.965                 |
| 13          | 3.686      | 0.02      | 3.9        | 14.375                 | 1318        | 0.14       | 0.02      | 3.9        | 0.546                  |
| 14          | 0.13       | 0.02      | 3.9        | 0.507                  | 1319        | 1.907      | 0.02      | 3.9        | 7.437                  |
| 15          | 0.16       | 0.02      | 3.9        | 0.624                  | 1320        | 5.858      | 0.02      | 3.9        | 22.846                 |
| 16          | 0.29       | 0.02      | 3.9        | 1.131                  | 1321        | 5.858      | 0.02      | 3.9        | 22.846                 |
| 17          | 0.14       | 0.02      | 3.9        | 0.546                  | 1322        | 2.263      | 0.02      | 3.9        | 8.826                  |
| 18          | 1.947      | 0.02      | 3.9        | 7.593                  | 1323        | 1.126      | 0.02      | 3.9        | 4.391                  |
| 19          | 0.16       | 0.02      | 3.9        | 0.624                  | 1324        | 0.092      | 0.02      | 3.9        | 0.359                  |
| 20          | 0.072      | 0.02      | 3.9        | 0.281                  | 1325        | 0.12       | 0.02      | 3.9        | 0.468                  |
| 21          | 0.38       | 0.02      | 3.9        | 1.482                  | 1326        | 1.126      | 0.02      | 3.9        | 4.391                  |
| 22          | 1.155      | 0.02      | 3.9        | 4.505                  | 1327        | 0.083      | 0.02      | 3.9        | 0.324                  |
| 23          | 3.178      | 0.02      | 3.9        | 12.394                 | 1328        | 0.16       | 0.02      | 3.9        | 0.624                  |
| 24          | 2.557      | 0.02      | 3.9        | 9.972                  | 1329        | 0.16       | 0.02      | 3.9        | 0.624                  |
| 25          | 3.558      | 0.02      | 3.9        | 13.876                 | 1330        | 0.079      | 0.02      | 3.9        | 0.308                  |
| 26          | 0.07       | 0.02      | 3.9        | 0.273                  | 1331        | 2.226      | 0.02      | 3.9        | 8.681                  |
| 27          | 0.16       | 0.02      | 3.9        | 0.624                  | 1332        | 0.16       | 0.02      | 3.9        | 0.624                  |
| 28          | 0.23       | 0.02      | 3.9        | 0.897                  | 1333        | 0.16       | 0.02      | 3.9        | 0.624                  |
| 29          | 2.796      | 0.02      | 3.9        | 10.904                 | 1334        | 2.226      | 0.02      | 3.9        | 8.681                  |
| 30          | 0.024      | 0.02      | 3.9        | 0.094                  | 1335        | 0.111      | 0.02      | 3.9        | 0.433                  |
| 31          | 0.16       | 0.02      | 3.9        | 0.624                  | 1336        | 0.14       | 0.02      | 3.9        | 0.546                  |
| 32          | 0.02       | 0.02      | 3.9        | 0.078                  | 1337        | 0.14       | 0.02      | 3.9        | 0.546                  |
| 33          | 0.922      | 0.02      | 3.9        | 3.596                  | 1338        | 0.399      | 0.02      | 3.9        | 1.556                  |
| 34          | 2.877      | 0.02      | 3.9        | 11.22                  | 1339        | 8.458      | 0.02      | 3.9        | 32.986                 |
| 35          | 0.54       | 0.02      | 3.9        | 2.106                  | 1340        | 0.523      | 0.02      | 3.9        | 2.04                   |
| 36          | 0.56       | 0.02      | 3.9        | 2.184                  | 1341        | 0.5        | 0.02      | 3.9        | 1.95                   |
| 37          | 2.5        | 0.02      | 3.9        | 9.75                   | 1342        | 0.13       | 0.02      | 3.9        | 0.507                  |
| 38          | 1.18       | 0.02      | 3.9        | 4.602                  | 1343        | 0.14       | 0.02      | 3.9        | 0.546                  |

|    |       |      |     |        |      |       |      |     |        |
|----|-------|------|-----|--------|------|-------|------|-----|--------|
| 39 | 0.18  | 0.02 | 3.9 | 0.702  | 1344 | 0.793 | 0.02 | 3.9 | 3.093  |
| 40 | 0.659 | 0.02 | 3.9 | 2.57   | 1345 | 3.333 | 0.02 | 3.9 | 12.999 |
| 41 | 0.16  | 0.02 | 3.9 | 0.624  | 1346 | 2.191 | 0.02 | 3.9 | 8.545  |
| 42 | 0.14  | 0.02 | 3.9 | 0.546  | 1347 | 0.87  | 0.02 | 3.9 | 3.393  |
| 43 | 1.118 | 0.02 | 3.9 | 4.36   | 1348 | 0.14  | 0.02 | 3.9 | 0.546  |
| 44 | 3.062 | 0.02 | 3.9 | 11.942 | 1349 | 0.71  | 0.02 | 3.9 | 2.769  |
| 45 | 0.046 | 0.02 | 3.9 | 0.179  | 1350 | 1.551 | 0.02 | 3.9 | 6.049  |
| 46 | 0.16  | 0.02 | 3.9 | 0.624  | 1351 | 1.72  | 0.02 | 3.9 | 6.708  |
| 47 | 0.276 | 0.02 | 3.9 | 1.076  | 1352 | 1.551 | 0.02 | 3.9 | 6.049  |
| 48 | 1.546 | 0.02 | 3.9 | 6.029  | 1353 | 0.13  | 0.02 | 3.9 | 0.507  |
| 49 | 0.16  | 0.02 | 3.9 | 0.624  | 1354 | 0.126 | 0.02 | 3.9 | 0.491  |
| 50 | 1.706 | 0.02 | 3.9 | 6.653  | 1355 | 0.397 | 0.02 | 3.9 | 1.548  |
| 51 | 0.23  | 0.02 | 3.9 | 0.897  | 1356 | 0.14  | 0.02 | 3.9 | 0.546  |
| 52 | 3.062 | 0.02 | 3.9 | 11.942 | 1357 | 0.127 | 0.02 | 3.9 | 0.495  |
| 53 | 0.161 | 0.02 | 3.9 | 0.628  | 1358 | 2.031 | 0.02 | 3.9 | 7.921  |
| 54 | 0.14  | 0.02 | 3.9 | 0.546  | 1359 | 1.31  | 0.02 | 3.9 | 5.109  |
| 55 | 0.16  | 0.02 | 3.9 | 0.624  | 1360 | 2.031 | 0.02 | 3.9 | 7.921  |
| 56 | 2.19  | 0.02 | 3.9 | 8.541  | 1361 | 0.323 | 0.02 | 3.9 | 1.26   |
| 57 | 0.29  | 0.02 | 3.9 | 1.131  | 1362 | 0.14  | 0.02 | 3.9 | 0.546  |
| 58 | 0.16  | 0.02 | 3.9 | 0.624  | 1363 | 0.523 | 0.02 | 3.9 | 2.04   |
| 59 | 0.16  | 0.02 | 3.9 | 0.624  | 1364 | 0.14  | 0.02 | 3.9 | 0.546  |
| 60 | 0.421 | 0.02 | 3.9 | 1.642  | 1365 | 0.04  | 0.02 | 3.9 | 0.156  |
| 61 | 3.637 | 0.02 | 3.9 | 14.184 | 1366 | 2.031 | 0.02 | 3.9 | 7.921  |
| 62 | 2.958 | 0.02 | 3.9 | 11.536 | 1367 | 1.994 | 0.02 | 3.9 | 7.777  |
| 63 | 0.13  | 0.02 | 3.9 | 0.507  | 1368 | 0.68  | 0.02 | 3.9 | 2.652  |
| 64 | 0.16  | 0.02 | 3.9 | 0.624  | 1369 | 0.26  | 0.02 | 3.9 | 1.014  |
| 65 | 0.27  | 0.02 | 3.9 | 1.053  | 1370 | 0.922 | 0.02 | 3.9 | 3.596  |
| 66 | 7.35  | 0.02 | 3.9 | 28.665 | 1371 | 1.334 | 0.02 | 3.9 | 5.203  |
| 67 | 0.29  | 0.02 | 3.9 | 1.131  | 1372 | 0.835 | 0.02 | 3.9 | 3.257  |
| 68 | 0.16  | 0.02 | 3.9 | 0.624  | 1373 | 0.14  | 0.02 | 3.9 | 0.546  |
| 69 | 0.13  | 0.02 | 3.9 | 0.507  | 1374 | 0.675 | 0.02 | 3.9 | 2.633  |
| 70 | 3.652 | 0.02 | 3.9 | 14.243 | 1375 | 1.174 | 0.02 | 3.9 | 4.579  |
| 71 | 1.88  | 0.02 | 3.9 | 7.332  | 1376 | 1.685 | 0.02 | 3.9 | 6.572  |
| 72 | 0.28  | 0.02 | 3.9 | 1.092  | 1377 | 1.174 | 0.02 | 3.9 | 4.579  |
| 73 | 1.757 | 0.02 | 3.9 | 6.852  | 1378 | 0.13  | 0.02 | 3.9 | 0.507  |
| 74 | 2.442 | 0.02 | 3.9 | 9.524  | 1379 | 0.176 | 0.02 | 3.9 | 0.686  |
| 75 | 0.28  | 0.02 | 3.9 | 1.092  | 1380 | 0.11  | 0.02 | 3.9 | 0.429  |
| 76 | 0.16  | 0.02 | 3.9 | 0.624  | 1381 | 0.525 | 0.02 | 3.9 | 2.047  |
| 77 | 0.16  | 0.02 | 3.9 | 0.624  | 1382 | 0.14  | 0.02 | 3.9 | 0.546  |
| 78 | 1.061 | 0.02 | 3.9 | 4.138  | 1383 | 0.108 | 0.02 | 3.9 | 0.421  |
| 79 | 0.045 | 0.02 | 3.9 | 0.175  | 1384 | 2.125 | 0.02 | 3.9 | 8.288  |
| 80 | 0.16  | 0.02 | 3.9 | 0.624  | 1385 | 0.722 | 0.02 | 3.9 | 2.816  |
| 81 | 0.16  | 0.02 | 3.9 | 0.624  | 1386 | 0.14  | 0.02 | 3.9 | 0.546  |
| 82 | 0.035 | 0.02 | 3.9 | 0.137  | 1387 | 0.16  | 0.02 | 3.9 | 0.624  |
| 83 | 4.768 | 0.02 | 3.9 | 18.595 | 1388 | 0.11  | 0.02 | 3.9 | 0.429  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 84  | 0.14  | 0.02 | 3.9 | 0.546  | 1389 | 0.299 | 0.02 | 3.9 | 1.166  |
| 85  | 3.359 | 0.02 | 3.9 | 13.1   | 1390 | 0.14  | 0.02 | 3.9 | 0.546  |
| 86  | 0.13  | 0.02 | 3.9 | 0.507  | 1391 | 7.863 | 0.02 | 3.9 | 30.666 |
| 87  | 0.14  | 0.02 | 3.9 | 0.546  | 1392 | 2.945 | 0.02 | 3.9 | 11.485 |
| 88  | 0.11  | 0.02 | 3.9 | 0.429  | 1393 | 0.14  | 0.02 | 3.9 | 0.546  |
| 89  | 1.23  | 0.02 | 3.9 | 4.797  | 1394 | 2.785 | 0.02 | 3.9 | 10.862 |
| 90  | 1.761 | 0.02 | 3.9 | 6.868  | 1395 | 4.232 | 0.02 | 3.9 | 16.505 |
| 91  | 1.23  | 0.02 | 3.9 | 4.797  | 1396 | 5.624 | 0.02 | 3.9 | 21.934 |
| 92  | 0.771 | 0.02 | 3.9 | 3.007  | 1397 | 0.399 | 0.02 | 3.9 | 1.556  |
| 93  | 0.12  | 0.02 | 3.9 | 0.468  | 1398 | 0.14  | 0.02 | 3.9 | 0.546  |
| 94  | 0.17  | 0.02 | 3.9 | 0.663  | 1399 | 0.169 | 0.02 | 3.9 | 0.659  |
| 95  | 0.04  | 0.02 | 3.9 | 0.156  | 1400 | 0.179 | 0.02 | 3.9 | 0.698  |
| 96  | 0.16  | 0.02 | 3.9 | 0.624  | 1401 | 0.875 | 0.02 | 3.9 | 3.413  |
| 97  | 0.04  | 0.02 | 3.9 | 0.156  | 1402 | 0.16  | 0.02 | 3.9 | 0.624  |
| 98  | 0.601 | 0.02 | 3.9 | 2.344  | 1403 | 2.464 | 0.02 | 3.9 | 9.61   |
| 99  | 1.37  | 0.02 | 3.9 | 5.343  | 1404 | 0.28  | 0.02 | 3.9 | 1.092  |
| 100 | 1.623 | 0.02 | 3.9 | 6.33   | 1405 | 1.74  | 0.02 | 3.9 | 6.786  |
| 101 | 0.31  | 0.02 | 3.9 | 1.209  | 1406 | 0.52  | 0.02 | 3.9 | 2.028  |
| 102 | 0.33  | 0.02 | 3.9 | 1.287  | 1407 | 0.5   | 0.02 | 3.9 | 1.95   |
| 103 | 2.09  | 0.02 | 3.9 | 8.151  | 1408 | 2.351 | 0.02 | 3.9 | 9.169  |
| 104 | 2.553 | 0.02 | 3.9 | 9.957  | 1409 | 0.13  | 0.02 | 3.9 | 0.507  |
| 105 | 0.13  | 0.02 | 3.9 | 0.507  | 1410 | 0.14  | 0.02 | 3.9 | 0.546  |
| 106 | 0.14  | 0.02 | 3.9 | 0.546  | 1411 | 0.25  | 0.02 | 3.9 | 0.975  |
| 107 | 0.63  | 0.02 | 3.9 | 2.457  | 1412 | 0.16  | 0.02 | 3.9 | 0.624  |
| 108 | 0.14  | 0.02 | 3.9 | 0.546  | 1413 | 2.783 | 0.02 | 3.9 | 10.854 |
| 109 | 0.36  | 0.02 | 3.9 | 1.404  | 1414 | 1.102 | 0.02 | 3.9 | 4.298  |
| 110 | 2.553 | 0.02 | 3.9 | 9.957  | 1415 | 0.722 | 0.02 | 3.9 | 2.816  |
| 111 | 1.357 | 0.02 | 3.9 | 5.292  | 1416 | 0.14  | 0.02 | 3.9 | 0.546  |
| 112 | 2.553 | 0.02 | 3.9 | 9.957  | 1417 | 0.16  | 0.02 | 3.9 | 0.624  |
| 113 | 0.137 | 0.02 | 3.9 | 0.534  | 1418 | 0.11  | 0.02 | 3.9 | 0.429  |
| 114 | 0.14  | 0.02 | 3.9 | 0.546  | 1419 | 0.26  | 0.02 | 3.9 | 1.014  |
| 115 | 0.407 | 0.02 | 3.9 | 1.587  | 1420 | 0.14  | 0.02 | 3.9 | 0.546  |
| 116 | 0.14  | 0.02 | 3.9 | 0.546  | 1421 | 0.73  | 0.02 | 3.9 | 2.847  |
| 117 | 0.11  | 0.02 | 3.9 | 0.429  | 1422 | 0.126 | 0.02 | 3.9 | 0.491  |
| 118 | 2.553 | 0.02 | 3.9 | 9.957  | 1423 | 0.14  | 0.02 | 3.9 | 0.546  |
| 119 | 0.582 | 0.02 | 3.9 | 2.27   | 1424 | 0.106 | 0.02 | 3.9 | 0.413  |
| 120 | 0.68  | 0.02 | 3.9 | 2.652  | 1425 | 1.893 | 0.02 | 3.9 | 7.383  |
| 121 | 1.16  | 0.02 | 3.9 | 4.524  | 1426 | 1.021 | 0.02 | 3.9 | 3.982  |
| 122 | 1.873 | 0.02 | 3.9 | 7.305  | 1427 | 1.712 | 0.02 | 3.9 | 6.677  |
| 123 | 0.772 | 0.02 | 3.9 | 3.011  | 1428 | 3.508 | 0.02 | 3.9 | 13.681 |
| 124 | 0.14  | 0.02 | 3.9 | 0.546  | 1429 | 1.18  | 0.02 | 3.9 | 4.602  |
| 125 | 0.912 | 0.02 | 3.9 | 3.557  | 1430 | 0.32  | 0.02 | 3.9 | 1.248  |
| 126 | 2.713 | 0.02 | 3.9 | 10.581 | 1431 | 1.16  | 0.02 | 3.9 | 4.524  |
| 127 | 3.177 | 0.02 | 3.9 | 12.39  | 1432 | 0.55  | 0.02 | 3.9 | 2.145  |
| 128 | 0.27  | 0.02 | 3.9 | 1.053  | 1433 | 2.598 | 0.02 | 3.9 | 10.132 |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 129 | 0.14  | 0.02 | 3.9 | 0.546  | 1434 | 4.259 | 0.02 | 3.9 | 16.61  |
| 130 | 0.11  | 0.02 | 3.9 | 0.429  | 1435 | 1.001 | 0.02 | 3.9 | 3.904  |
| 131 | 9.035 | 0.02 | 3.9 | 35.237 | 1436 | 0.174 | 0.02 | 3.9 | 0.679  |
| 132 | 0.399 | 0.02 | 3.9 | 1.556  | 1437 | 0.14  | 0.02 | 3.9 | 0.546  |
| 133 | 0.14  | 0.02 | 3.9 | 0.546  | 1438 | 0.154 | 0.02 | 3.9 | 0.601  |
| 134 | 0.14  | 0.02 | 3.9 | 0.546  | 1439 | 2     | 0.02 | 3.9 | 7.8    |
| 135 | 2.226 | 0.02 | 3.9 | 8.681  | 1440 | 0.27  | 0.02 | 3.9 | 1.053  |
| 136 | 0.111 | 0.02 | 3.9 | 0.433  | 1441 | 0.14  | 0.02 | 3.9 | 0.546  |
| 137 | 0.14  | 0.02 | 3.9 | 0.546  | 1442 | 0.11  | 0.02 | 3.9 | 0.429  |
| 138 | 0.14  | 0.02 | 3.9 | 0.546  | 1443 | 2.861 | 0.02 | 3.9 | 11.158 |
| 139 | 0.091 | 0.02 | 3.9 | 0.355  | 1444 | 4.099 | 0.02 | 3.9 | 15.986 |
| 140 | 0.866 | 0.02 | 3.9 | 3.377  | 1445 | 2.421 | 0.02 | 3.9 | 9.442  |
| 141 | 5.914 | 0.02 | 3.9 | 23.065 | 1446 | 1.081 | 0.02 | 3.9 | 4.216  |
| 142 | 2.19  | 0.02 | 3.9 | 8.541  | 1447 | 0.42  | 0.02 | 3.9 | 1.638  |
| 143 | 0.16  | 0.02 | 3.9 | 0.624  | 1448 | 1.629 | 0.02 | 3.9 | 6.353  |
| 144 | 5.04  | 0.02 | 3.9 | 19.656 | 1449 | 0.14  | 0.02 | 3.9 | 0.546  |
| 145 | 0.14  | 0.02 | 3.9 | 0.546  | 1450 | 1.609 | 0.02 | 3.9 | 6.275  |
| 146 | 2.17  | 0.02 | 3.9 | 8.463  | 1451 | 1.456 | 0.02 | 3.9 | 5.678  |
| 147 | 5.917 | 0.02 | 3.9 | 23.076 | 1452 | 0.14  | 0.02 | 3.9 | 0.546  |
| 148 | 0.858 | 0.02 | 3.9 | 3.346  | 1453 | 0.396 | 0.02 | 3.9 | 1.544  |
| 149 | 0.109 | 0.02 | 3.9 | 0.425  | 1454 | 0.48  | 0.02 | 3.9 | 1.872  |
| 150 | 0.14  | 0.02 | 3.9 | 0.546  | 1455 | 1.466 | 0.02 | 3.9 | 5.717  |
| 151 | 0.16  | 0.02 | 3.9 | 0.624  | 1456 | 0.6   | 0.02 | 3.9 | 2.34   |
| 152 | 0.079 | 0.02 | 3.9 | 0.308  | 1457 | 0.314 | 0.02 | 3.9 | 1.225  |
| 153 | 2.226 | 0.02 | 3.9 | 8.681  | 1458 | 0.13  | 0.02 | 3.9 | 0.507  |
| 154 | 0.03  | 0.02 | 3.9 | 0.117  | 1459 | 0.14  | 0.02 | 3.9 | 0.546  |
| 155 | 0.161 | 0.02 | 3.9 | 0.628  | 1460 | 2.411 | 0.02 | 3.9 | 9.403  |
| 156 | 0.16  | 0.02 | 3.9 | 0.624  | 1461 | 0.13  | 0.02 | 3.9 | 0.507  |
| 157 | 0.182 | 0.02 | 3.9 | 0.71   | 1462 | 0.14  | 0.02 | 3.9 | 0.546  |
| 158 | 0.53  | 0.02 | 3.9 | 2.067  | 1463 | 0.16  | 0.02 | 3.9 | 0.624  |
| 159 | 0.13  | 0.02 | 3.9 | 0.507  | 1464 | 1.506 | 0.02 | 3.9 | 5.873  |
| 160 | 5.238 | 0.02 | 3.9 | 20.428 | 1465 | 1.883 | 0.02 | 3.9 | 7.344  |
| 161 | 0.15  | 0.02 | 3.9 | 0.585  | 1466 | 4.233 | 0.02 | 3.9 | 16.509 |
| 162 | 1.02  | 0.02 | 3.9 | 3.978  | 1467 | 0.906 | 0.02 | 3.9 | 3.533  |
| 163 | 0.13  | 0.02 | 3.9 | 0.507  | 1468 | 0.14  | 0.02 | 3.9 | 0.546  |
| 164 | 2.227 | 0.02 | 3.9 | 8.685  | 1469 | 0.16  | 0.02 | 3.9 | 0.624  |
| 165 | 0.13  | 0.02 | 3.9 | 0.507  | 1470 | 1.578 | 0.02 | 3.9 | 6.154  |
| 166 | 0.14  | 0.02 | 3.9 | 0.546  | 1471 | 0.18  | 0.02 | 3.9 | 0.702  |
| 167 | 0.4   | 0.02 | 3.9 | 1.56   | 1472 | 0.38  | 0.02 | 3.9 | 1.482  |
| 168 | 0.14  | 0.02 | 3.9 | 0.546  | 1473 | 5.38  | 0.02 | 3.9 | 20.982 |
| 169 | 0.11  | 0.02 | 3.9 | 0.429  | 1474 | 0.14  | 0.02 | 3.9 | 0.546  |
| 170 | 2.227 | 0.02 | 3.9 | 8.685  | 1475 | 5.36  | 0.02 | 3.9 | 20.904 |
| 171 | 0.35  | 0.02 | 3.9 | 1.365  | 1476 | 0.78  | 0.02 | 3.9 | 3.042  |
| 172 | 1.02  | 0.02 | 3.9 | 3.978  | 1477 | 0.161 | 0.02 | 3.9 | 0.628  |
| 173 | 0.33  | 0.02 | 3.9 | 1.287  | 1478 | 1.336 | 0.02 | 3.9 | 5.21   |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 174 | 5.238 | 0.02 | 3.9 | 20.428 | 1479 | 0.14  | 0.02 | 3.9 | 0.546  |
| 175 | 0.35  | 0.02 | 3.9 | 1.365  | 1480 | 0.16  | 0.02 | 3.9 | 0.624  |
| 176 | 0.51  | 0.02 | 3.9 | 1.989  | 1481 | 8.031 | 0.02 | 3.9 | 31.321 |
| 177 | 0.049 | 0.02 | 3.9 | 0.191  | 1482 | 0.075 | 0.02 | 3.9 | 0.293  |
| 178 | 0.16  | 0.02 | 3.9 | 0.624  | 1483 | 0.14  | 0.02 | 3.9 | 0.546  |
| 179 | 0.16  | 0.02 | 3.9 | 0.624  | 1484 | 0.4   | 0.02 | 3.9 | 1.56   |
| 180 | 2.296 | 0.02 | 3.9 | 8.954  | 1485 | 0.14  | 0.02 | 3.9 | 0.546  |
| 181 | 0.067 | 0.02 | 3.9 | 0.261  | 1486 | 0.165 | 0.02 | 3.9 | 0.644  |
| 182 | 0.148 | 0.02 | 3.9 | 0.577  | 1487 | 8.191 | 0.02 | 3.9 | 31.945 |
| 183 | 0.16  | 0.02 | 3.9 | 0.624  | 1488 | 0.16  | 0.02 | 3.9 | 0.624  |
| 184 | 0.071 | 0.02 | 3.9 | 0.277  | 1489 | 1.953 | 0.02 | 3.9 | 7.617  |
| 185 | 0.864 | 0.02 | 3.9 | 3.37   | 1490 | 0.821 | 0.02 | 3.9 | 3.202  |
| 186 | 5.914 | 0.02 | 3.9 | 23.065 | 1491 | 0.156 | 0.02 | 3.9 | 0.608  |
| 187 | 2.188 | 0.02 | 3.9 | 8.533  | 1492 | 0.13  | 0.02 | 3.9 | 0.507  |
| 188 | 0.14  | 0.02 | 3.9 | 0.546  | 1493 | 0.14  | 0.02 | 3.9 | 0.546  |
| 189 | 5.04  | 0.02 | 3.9 | 19.656 | 1494 | 0.11  | 0.02 | 3.9 | 0.429  |
| 190 | 0.14  | 0.02 | 3.9 | 0.546  | 1495 | 0.344 | 0.02 | 3.9 | 1.342  |
| 191 | 2.172 | 0.02 | 3.9 | 8.471  | 1496 | 0.52  | 0.02 | 3.9 | 2.028  |
| 192 | 5.915 | 0.02 | 3.9 | 23.069 | 1497 | 0.98  | 0.02 | 3.9 | 3.822  |
| 193 | 0.868 | 0.02 | 3.9 | 3.385  | 1498 | 0.261 | 0.02 | 3.9 | 1.018  |
| 194 | 0.103 | 0.02 | 3.9 | 0.402  | 1499 | 0.659 | 0.02 | 3.9 | 2.57   |
| 195 | 0.14  | 0.02 | 3.9 | 0.546  | 1500 | 0.14  | 0.02 | 3.9 | 0.546  |
| 196 | 0.16  | 0.02 | 3.9 | 0.624  | 1501 | 0.16  | 0.02 | 3.9 | 0.624  |
| 197 | 0.079 | 0.02 | 3.9 | 0.308  | 1502 | 0.377 | 0.02 | 3.9 | 1.47   |
| 198 | 2.226 | 0.02 | 3.9 | 8.681  | 1503 | 4.873 | 0.02 | 3.9 | 19.005 |
| 199 | 0.03  | 0.02 | 3.9 | 0.117  | 1504 | 0.901 | 0.02 | 3.9 | 3.514  |
| 200 | 0.16  | 0.02 | 3.9 | 0.624  | 1505 | 0.14  | 0.02 | 3.9 | 0.546  |
| 201 | 0.12  | 0.02 | 3.9 | 0.468  | 1506 | 0.16  | 0.02 | 3.9 | 0.624  |
| 202 | 0.19  | 0.02 | 3.9 | 0.741  | 1507 | 1.81  | 0.02 | 3.9 | 7.059  |
| 203 | 0.53  | 0.02 | 3.9 | 2.067  | 1508 | 2.662 | 0.02 | 3.9 | 10.382 |
| 204 | 0.17  | 0.02 | 3.9 | 0.663  | 1509 | 0.14  | 0.02 | 3.9 | 0.546  |
| 205 | 5.329 | 0.02 | 3.9 | 20.783 | 1510 | 2.802 | 0.02 | 3.9 | 10.928 |
| 206 | 0.24  | 0.02 | 3.9 | 0.936  | 1511 | 0.704 | 0.02 | 3.9 | 2.746  |
| 207 | 1.62  | 0.02 | 3.9 | 6.318  | 1512 | 1.238 | 0.02 | 3.9 | 4.828  |
| 208 | 0.22  | 0.02 | 3.9 | 0.858  | 1513 | 0.724 | 0.02 | 3.9 | 2.824  |
| 209 | 1.537 | 0.02 | 3.9 | 5.994  | 1514 | 1.74  | 0.02 | 3.9 | 6.786  |
| 210 | 0.13  | 0.02 | 3.9 | 0.507  | 1515 | 2.118 | 0.02 | 3.9 | 8.26   |
| 211 | 0.14  | 0.02 | 3.9 | 0.546  | 1516 | 0.14  | 0.02 | 3.9 | 0.546  |
| 212 | 0.4   | 0.02 | 3.9 | 1.56   | 1517 | 2.098 | 0.02 | 3.9 | 8.182  |
| 213 | 0.14  | 0.02 | 3.9 | 0.546  | 1518 | 1.694 | 0.02 | 3.9 | 6.607  |
| 214 | 0.11  | 0.02 | 3.9 | 0.429  | 1519 | 0.64  | 0.02 | 3.9 | 2.496  |
| 215 | 1.537 | 0.02 | 3.9 | 5.994  | 1520 | 0.66  | 0.02 | 3.9 | 2.574  |
| 216 | 0.24  | 0.02 | 3.9 | 0.936  | 1521 | 0.62  | 0.02 | 3.9 | 2.418  |
| 217 | 1.62  | 0.02 | 3.9 | 6.318  | 1522 | 5.59  | 0.02 | 3.9 | 21.801 |
| 218 | 0.22  | 0.02 | 3.9 | 0.858  | 1523 | 1.754 | 0.02 | 3.9 | 6.841  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 219 | 5.329 | 0.02 | 3.9 | 20.783 | 1524 | 0.16  | 0.02 | 3.9 | 0.624  |
| 220 | 0.34  | 0.02 | 3.9 | 1.326  | 1525 | 2.812 | 0.02 | 3.9 | 10.967 |
| 221 | 0.51  | 0.02 | 3.9 | 1.989  | 1526 | 0.18  | 0.02 | 3.9 | 0.702  |
| 222 | 0.059 | 0.02 | 3.9 | 0.23   | 1527 | 1.32  | 0.02 | 3.9 | 5.148  |
| 223 | 0.14  | 0.02 | 3.9 | 0.546  | 1528 | 0.32  | 0.02 | 3.9 | 1.248  |
| 224 | 0.12  | 0.02 | 3.9 | 0.468  | 1529 | 4.132 | 0.02 | 3.9 | 16.115 |
| 225 | 2.238 | 0.02 | 3.9 | 8.728  | 1530 | 0.1   | 0.02 | 3.9 | 0.39   |
| 226 | 0.035 | 0.02 | 3.9 | 0.137  | 1531 | 1.594 | 0.02 | 3.9 | 6.217  |
| 227 | 0.092 | 0.02 | 3.9 | 0.359  | 1532 | 3.435 | 0.02 | 3.9 | 13.397 |
| 228 | 0.12  | 0.02 | 3.9 | 0.468  | 1533 | 5.766 | 0.02 | 3.9 | 22.487 |
| 229 | 0.043 | 0.02 | 3.9 | 0.168  | 1534 | 0.27  | 0.02 | 3.9 | 1.053  |
| 230 | 0.876 | 0.02 | 3.9 | 3.416  | 1535 | 2.335 | 0.02 | 3.9 | 9.107  |
| 231 | 5.954 | 0.02 | 3.9 | 23.221 | 1536 | 0.312 | 0.02 | 3.9 | 1.217  |
| 232 | 2.188 | 0.02 | 3.9 | 8.533  | 1537 | 0.27  | 0.02 | 3.9 | 1.053  |
| 233 | 0.1   | 0.02 | 3.9 | 0.39   | 1538 | 0.292 | 0.02 | 3.9 | 1.139  |
| 234 | 5     | 0.02 | 3.9 | 19.5   | 1539 | 2.991 | 0.02 | 3.9 | 11.665 |
| 235 | 0.1   | 0.02 | 3.9 | 0.39   | 1540 | 4.91  | 0.02 | 3.9 | 19.149 |
| 236 | 2.172 | 0.02 | 3.9 | 8.471  | 1541 | 2.991 | 0.02 | 3.9 | 11.665 |
| 237 | 5.955 | 0.02 | 3.9 | 23.225 | 1542 | 0.363 | 0.02 | 3.9 | 1.416  |
| 238 | 0.879 | 0.02 | 3.9 | 3.428  | 1543 | 0.27  | 0.02 | 3.9 | 1.053  |
| 239 | 0.075 | 0.02 | 3.9 | 0.293  | 1544 | 0.473 | 0.02 | 3.9 | 1.845  |
| 240 | 0.12  | 0.02 | 3.9 | 0.468  | 1545 | 3.971 | 0.02 | 3.9 | 15.487 |
| 241 | 0.12  | 0.02 | 3.9 | 0.468  | 1546 | 0.14  | 0.02 | 3.9 | 0.546  |
| 242 | 0.051 | 0.02 | 3.9 | 0.199  | 1547 | 2.125 | 0.02 | 3.9 | 8.288  |
| 243 | 2.238 | 0.02 | 3.9 | 8.728  | 1548 | 0.37  | 0.02 | 3.9 | 1.443  |
| 244 | 0.03  | 0.02 | 3.9 | 0.117  | 1549 | 0.144 | 0.02 | 3.9 | 0.562  |
| 245 | 0.1   | 0.02 | 3.9 | 0.39   | 1550 | 0.35  | 0.02 | 3.9 | 1.365  |
| 246 | 0.14  | 0.02 | 3.9 | 0.546  | 1551 | 1.122 | 0.02 | 3.9 | 4.376  |
| 247 | 0.1   | 0.02 | 3.9 | 0.39   | 1552 | 1.36  | 0.02 | 3.9 | 5.304  |
| 248 | 0.66  | 0.02 | 3.9 | 2.574  | 1553 | 1.122 | 0.02 | 3.9 | 4.376  |
| 249 | 0.28  | 0.02 | 3.9 | 1.092  | 1554 | 0.13  | 0.02 | 3.9 | 0.507  |
| 250 | 5.178 | 0.02 | 3.9 | 20.194 | 1555 | 0.144 | 0.02 | 3.9 | 0.562  |
| 251 | 0.38  | 0.02 | 3.9 | 1.482  | 1556 | 0.11  | 0.02 | 3.9 | 0.429  |
| 252 | 1.47  | 0.02 | 3.9 | 5.733  | 1557 | 0.053 | 0.02 | 3.9 | 0.207  |
| 253 | 0.36  | 0.02 | 3.9 | 1.404  | 1558 | 0.14  | 0.02 | 3.9 | 0.546  |
| 254 | 1.687 | 0.02 | 3.9 | 6.579  | 1559 | 1.332 | 0.02 | 3.9 | 5.195  |
| 255 | 0.13  | 0.02 | 3.9 | 0.507  | 1560 | 0.32  | 0.02 | 3.9 | 1.248  |
| 256 | 0.14  | 0.02 | 3.9 | 0.546  | 1561 | 1.32  | 0.02 | 3.9 | 5.148  |
| 257 | 0.4   | 0.02 | 3.9 | 1.56   | 1562 | 0.32  | 0.02 | 3.9 | 1.248  |
| 258 | 0.14  | 0.02 | 3.9 | 0.546  | 1563 | 1.46  | 0.02 | 3.9 | 5.694  |
| 259 | 0.11  | 0.02 | 3.9 | 0.429  | 1564 | 0.385 | 0.02 | 3.9 | 1.502  |
| 260 | 9.035 | 0.02 | 3.9 | 35.237 | 1565 | 1.46  | 0.02 | 3.9 | 5.694  |
| 261 | 0.399 | 0.02 | 3.9 | 1.556  | 1566 | 0.385 | 0.02 | 3.9 | 1.502  |
| 262 | 0.14  | 0.02 | 3.9 | 0.546  | 1567 | 0.79  | 0.02 | 3.9 | 3.081  |
| 263 | 2.386 | 0.02 | 3.9 | 9.305  | 1568 | 1.38  | 0.02 | 3.9 | 5.382  |



|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 264 | 0.111 | 0.02 | 3.9 | 0.433  | 1569 | 0.2   | 0.02 | 3.9 | 0.78   |
| 265 | 0.14  | 0.02 | 3.9 | 0.546  | 1570 | 0.76  | 0.02 | 3.9 | 2.964  |
| 266 | 0.16  | 0.02 | 3.9 | 0.624  | 1571 | 0.97  | 0.02 | 3.9 | 3.783  |
| 267 | 0.092 | 0.02 | 3.9 | 0.359  | 1572 | 2.14  | 0.02 | 3.9 | 8.346  |
| 268 | 1.126 | 0.02 | 3.9 | 4.391  | 1573 | 0.16  | 0.02 | 3.9 | 0.624  |
| 269 | 5.915 | 0.02 | 3.9 | 23.069 | 1574 | 0.4   | 0.02 | 3.9 | 1.56   |
| 270 | 2.45  | 0.02 | 3.9 | 9.555  | 1575 | 0.14  | 0.02 | 3.9 | 0.546  |
| 271 | 0.14  | 0.02 | 3.9 | 0.546  | 1576 | 0.16  | 0.02 | 3.9 | 0.624  |
| 272 | 5.04  | 0.02 | 3.9 | 19.656 | 1577 | 1.311 | 0.02 | 3.9 | 5.113  |
| 273 | 0.14  | 0.02 | 3.9 | 0.546  | 1578 | 1.36  | 0.02 | 3.9 | 5.304  |
| 274 | 2.43  | 0.02 | 3.9 | 9.477  | 1579 | 0.121 | 0.02 | 3.9 | 0.472  |
| 275 | 5.915 | 0.02 | 3.9 | 23.069 | 1580 | 0.14  | 0.02 | 3.9 | 0.546  |
| 276 | 1.126 | 0.02 | 3.9 | 4.391  | 1581 | 0.101 | 0.02 | 3.9 | 0.394  |
| 277 | 0.103 | 0.02 | 3.9 | 0.402  | 1582 | 1.05  | 0.02 | 3.9 | 4.095  |
| 278 | 0.14  | 0.02 | 3.9 | 0.546  | 1583 | 1.02  | 0.02 | 3.9 | 3.978  |
| 279 | 0.16  | 0.02 | 3.9 | 0.624  | 1584 | 1.02  | 0.02 | 3.9 | 3.978  |
| 280 | 0.079 | 0.02 | 3.9 | 0.308  | 1585 | 0.86  | 0.02 | 3.9 | 3.354  |
| 281 | 2.226 | 0.02 | 3.9 | 8.681  | 1586 | 6.78  | 0.02 | 3.9 | 26.442 |
| 282 | 0.16  | 0.02 | 3.9 | 0.624  | 1587 | 0.399 | 0.02 | 3.9 | 1.556  |
| 283 | 0.16  | 0.02 | 3.9 | 0.624  | 1588 | 0.161 | 0.02 | 3.9 | 0.628  |
| 284 | 0.195 | 0.02 | 3.9 | 0.76   | 1589 | 6.28  | 0.02 | 3.9 | 24.492 |
| 285 | 0.53  | 0.02 | 3.9 | 2.067  | 1590 | 0.52  | 0.02 | 3.9 | 2.028  |
| 286 | 0.17  | 0.02 | 3.9 | 0.663  | 1591 | 0.659 | 0.02 | 3.9 | 2.57   |
| 287 | 8.506 | 0.02 | 3.9 | 33.173 | 1592 | 0.32  | 0.02 | 3.9 | 1.248  |
| 288 | 0.13  | 0.02 | 3.9 | 0.507  | 1593 | 1.2   | 0.02 | 3.9 | 4.68   |
| 289 | 0.14  | 0.02 | 3.9 | 0.546  | 1594 | 0.161 | 0.02 | 3.9 | 0.628  |
| 290 | 0.4   | 0.02 | 3.9 | 1.56   | 1595 | 5.897 | 0.02 | 3.9 | 22.998 |
| 291 | 0.14  | 0.02 | 3.9 | 0.546  | 1596 | 0.281 | 0.02 | 3.9 | 1.096  |
| 292 | 2.777 | 0.02 | 3.9 | 10.83  | 1597 | 0.843 | 0.02 | 3.9 | 3.288  |
| 293 | 0.28  | 0.02 | 3.9 | 1.092  | 1598 | 0.724 | 0.02 | 3.9 | 2.824  |
| 294 | 2.62  | 0.02 | 3.9 | 10.218 | 1599 | 0.499 | 0.02 | 3.9 | 1.946  |
| 295 | 0.26  | 0.02 | 3.9 | 1.014  | 1600 | 4.912 | 0.02 | 3.9 | 19.157 |
| 296 | 3.089 | 0.02 | 3.9 | 12.047 | 1601 | 0.48  | 0.02 | 3.9 | 1.872  |
| 297 | 0.34  | 0.02 | 3.9 | 1.326  | 1602 | 2.353 | 0.02 | 3.9 | 9.177  |
| 298 | 0.51  | 0.02 | 3.9 | 1.989  | 1603 | 0.62  | 0.02 | 3.9 | 2.418  |
| 299 | 0.059 | 0.02 | 3.9 | 0.23   | 1604 | 1.32  | 0.02 | 3.9 | 5.148  |
| 300 | 0.16  | 0.02 | 3.9 | 0.624  | 1605 | 5.932 | 0.02 | 3.9 | 23.135 |
| 301 | 0.14  | 0.02 | 3.9 | 0.546  | 1606 | 0.195 | 0.02 | 3.9 | 0.76   |
| 302 | 0.273 | 0.02 | 3.9 | 1.065  | 1607 | 0.27  | 0.02 | 3.9 | 1.053  |
| 303 | 2.216 | 0.02 | 3.9 | 8.642  | 1608 | 0.343 | 0.02 | 3.9 | 1.338  |
| 304 | 0.122 | 0.02 | 3.9 | 0.476  | 1609 | 0.29  | 0.02 | 3.9 | 1.131  |
| 305 | 0.14  | 0.02 | 3.9 | 0.546  | 1610 | 0.27  | 0.02 | 3.9 | 1.053  |
| 306 | 0.16  | 0.02 | 3.9 | 0.624  | 1611 | 0.363 | 0.02 | 3.9 | 1.416  |
| 307 | 0.077 | 0.02 | 3.9 | 0.3    | 1612 | 2.355 | 0.02 | 3.9 | 9.185  |
| 308 | 0.594 | 0.02 | 3.9 | 2.317  | 1613 | 0.27  | 0.02 | 3.9 | 1.053  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 309 | 5.915 | 0.02 | 3.9 | 23.069 | 1614 | 5.746 | 0.02 | 3.9 | 22.409 |
| 310 | 2.192 | 0.02 | 3.9 | 8.549  | 1615 | 3.435 | 0.02 | 3.9 | 13.397 |
| 311 | 0.12  | 0.02 | 3.9 | 0.468  | 1616 | 1.88  | 0.02 | 3.9 | 7.332  |
| 312 | 5.47  | 0.02 | 3.9 | 21.333 | 1617 | 0.08  | 0.02 | 3.9 | 0.312  |
| 313 | 0.14  | 0.02 | 3.9 | 0.546  | 1618 | 4.263 | 0.02 | 3.9 | 16.626 |
| 314 | 2.598 | 0.02 | 3.9 | 10.132 | 1619 | 0.32  | 0.02 | 3.9 | 1.248  |
| 315 | 8.514 | 0.02 | 3.9 | 33.205 | 1620 | 0.616 | 0.02 | 3.9 | 2.402  |
| 316 | 0.13  | 0.02 | 3.9 | 0.507  | 1621 | 0.16  | 0.02 | 3.9 | 0.624  |
| 317 | 0.5   | 0.02 | 3.9 | 1.95   | 1622 | 3.623 | 0.02 | 3.9 | 14.13  |
| 318 | 3.298 | 0.02 | 3.9 | 12.862 | 1623 | 0.18  | 0.02 | 3.9 | 0.702  |
| 319 | 0.68  | 0.02 | 3.9 | 2.652  | 1624 | 2.02  | 0.02 | 3.9 | 7.878  |
| 320 | 0.16  | 0.02 | 3.9 | 0.624  | 1625 | 9.645 | 0.02 | 3.9 | 37.616 |
| 321 | 5.178 | 0.02 | 3.9 | 20.194 | 1626 | 2.363 | 0.02 | 3.9 | 9.216  |
| 322 | 0.18  | 0.02 | 3.9 | 0.702  | 1627 | 0.133 | 0.02 | 3.9 | 0.519  |
| 323 | 1.32  | 0.02 | 3.9 | 5.148  | 1628 | 0.14  | 0.02 | 3.9 | 0.546  |
| 324 | 0.16  | 0.02 | 3.9 | 0.624  | 1629 | 0.113 | 0.02 | 3.9 | 0.441  |
| 325 | 1.837 | 0.02 | 3.9 | 7.164  | 1630 | 1.028 | 0.02 | 3.9 | 4.009  |
| 326 | 0.13  | 0.02 | 3.9 | 0.507  | 1631 | 0.277 | 0.02 | 3.9 | 1.08   |
| 327 | 0.14  | 0.02 | 3.9 | 0.546  | 1632 | 2.812 | 0.02 | 3.9 | 10.967 |
| 328 | 0.25  | 0.02 | 3.9 | 0.975  | 1633 | 1.758 | 0.02 | 3.9 | 6.856  |
| 329 | 1.347 | 0.02 | 3.9 | 5.253  | 1634 | 0.4   | 0.02 | 3.9 | 1.56   |
| 330 | 0.354 | 0.02 | 3.9 | 1.381  | 1635 | 0.27  | 0.02 | 3.9 | 1.053  |
| 331 | 0.14  | 0.02 | 3.9 | 0.546  | 1636 | 0.14  | 0.02 | 3.9 | 0.546  |
| 332 | 0.334 | 0.02 | 3.9 | 1.303  | 1637 | 0.11  | 0.02 | 3.9 | 0.429  |
| 333 | 0.47  | 0.02 | 3.9 | 1.833  | 1638 | 1.35  | 0.02 | 3.9 | 5.265  |
| 334 | 0.317 | 0.02 | 3.9 | 1.236  | 1639 | 0.14  | 0.02 | 3.9 | 0.546  |
| 335 | 1.16  | 0.02 | 3.9 | 4.524  | 1640 | 0.16  | 0.02 | 3.9 | 0.624  |
| 336 | 2.502 | 0.02 | 3.9 | 9.758  | 1641 | 0.95  | 0.02 | 3.9 | 3.705  |
| 337 | 1.65  | 0.02 | 3.9 | 6.435  | 1642 | 4.873 | 0.02 | 3.9 | 19.005 |
| 338 | 1.612 | 0.02 | 3.9 | 6.287  | 1643 | 1.932 | 0.02 | 3.9 | 7.535  |
| 339 | 0.12  | 0.02 | 3.9 | 0.468  | 1644 | 0.14  | 0.02 | 3.9 | 0.546  |
| 340 | 1.612 | 0.02 | 3.9 | 6.287  | 1645 | 3.483 | 0.02 | 3.9 | 13.584 |
| 341 | 2.739 | 0.02 | 3.9 | 10.682 | 1646 | 0.14  | 0.02 | 3.9 | 0.546  |
| 342 | 0.14  | 0.02 | 3.9 | 0.546  | 1647 | 3.463 | 0.02 | 3.9 | 13.506 |
| 343 | 4.69  | 0.02 | 3.9 | 18.291 | 1648 | 0.16  | 0.02 | 3.9 | 0.624  |
| 344 | 2.966 | 0.02 | 3.9 | 11.567 | 1649 | 0.071 | 0.02 | 3.9 | 0.277  |
| 345 | 5.178 | 0.02 | 3.9 | 20.194 | 1650 | 0.16  | 0.02 | 3.9 | 0.624  |
| 346 | 0.318 | 0.02 | 3.9 | 1.24   | 1651 | 1.939 | 0.02 | 3.9 | 7.562  |
| 347 | 0.66  | 0.02 | 3.9 | 2.574  | 1652 | 5.101 | 0.02 | 3.9 | 19.894 |
| 348 | 0.051 | 0.02 | 3.9 | 0.199  | 1653 | 0.14  | 0.02 | 3.9 | 0.546  |
| 349 | 0.14  | 0.02 | 3.9 | 0.546  | 1654 | 5.69  | 0.02 | 3.9 | 22.191 |
| 350 | 0.16  | 0.02 | 3.9 | 0.624  | 1655 | 0.14  | 0.02 | 3.9 | 0.546  |
| 351 | 1.683 | 0.02 | 3.9 | 6.564  | 1656 | 2.04  | 0.02 | 3.9 | 7.956  |
| 352 | 3.613 | 0.02 | 3.9 | 14.091 | 1657 | 0.13  | 0.02 | 3.9 | 0.507  |
| 353 | 0.263 | 0.02 | 3.9 | 1.026  | 1658 | 0.14  | 0.02 | 3.9 | 0.546  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 354 | 0.14  | 0.02 | 3.9 | 0.546  | 1659 | 0.16  | 0.02 | 3.9 | 0.624  |
| 355 | 0.103 | 0.02 | 3.9 | 0.402  | 1660 | 0.79  | 0.02 | 3.9 | 3.081  |
| 356 | 2.938 | 0.02 | 3.9 | 11.458 | 1661 | 3.61  | 0.02 | 3.9 | 14.079 |
| 357 | 0.724 | 0.02 | 3.9 | 2.824  | 1662 | 2.69  | 0.02 | 3.9 | 10.491 |
| 358 | 0.5   | 0.02 | 3.9 | 1.95   | 1663 | 0.88  | 0.02 | 3.9 | 3.432  |
| 359 | 1.855 | 0.02 | 3.9 | 7.235  | 1664 | 0.161 | 0.02 | 3.9 | 0.628  |
| 360 | 3.458 | 0.02 | 3.9 | 13.486 | 1665 | 3.143 | 0.02 | 3.9 | 12.258 |
| 361 | 1.196 | 0.02 | 3.9 | 4.664  | 1666 | 0.14  | 0.02 | 3.9 | 0.546  |
| 362 | 0.14  | 0.02 | 3.9 | 0.546  | 1667 | 0.16  | 0.02 | 3.9 | 0.624  |
| 363 | 1.395 | 0.02 | 3.9 | 5.441  | 1668 | 4.871 | 0.02 | 3.9 | 18.997 |
| 364 | 0.14  | 0.02 | 3.9 | 0.546  | 1669 | 0.13  | 0.02 | 3.9 | 0.507  |
| 365 | 0.039 | 0.02 | 3.9 | 0.152  | 1670 | 0.14  | 0.02 | 3.9 | 0.546  |
| 366 | 3.458 | 0.02 | 3.9 | 13.486 | 1671 | 0.11  | 0.02 | 3.9 | 0.429  |
| 367 | 1.148 | 0.02 | 3.9 | 4.477  | 1672 | 1.42  | 0.02 | 3.9 | 5.538  |
| 368 | 0.68  | 0.02 | 3.9 | 2.652  | 1673 | 0.14  | 0.02 | 3.9 | 0.546  |
| 369 | 0.42  | 0.02 | 3.9 | 1.638  | 1674 | 6.431 | 0.02 | 3.9 | 25.081 |
| 370 | 0.68  | 0.02 | 3.9 | 2.652  | 1675 | 1.48  | 0.02 | 3.9 | 5.772  |
| 371 | 0.399 | 0.02 | 3.9 | 1.556  | 1676 | 0.18  | 0.02 | 3.9 | 0.702  |
| 372 | 0.14  | 0.02 | 3.9 | 0.546  | 1677 | 1.32  | 0.02 | 3.9 | 5.148  |
| 373 | 0.2   | 0.02 | 3.9 | 0.78   | 1678 | 0.161 | 0.02 | 3.9 | 0.628  |
| 374 | 3.418 | 0.02 | 3.9 | 13.33  | 1679 | 0.865 | 0.02 | 3.9 | 3.374  |
| 375 | 2.116 | 0.02 | 3.9 | 8.252  | 1680 | 4.33  | 0.02 | 3.9 | 16.887 |
| 376 | 0.18  | 0.02 | 3.9 | 0.702  | 1681 | 0.14  | 0.02 | 3.9 | 0.546  |
| 377 | 0.089 | 0.02 | 3.9 | 0.347  | 1682 | 4.31  | 0.02 | 3.9 | 16.809 |
| 378 | 2.4   | 0.02 | 3.9 | 9.36   | 1683 | 0.261 | 0.02 | 3.9 | 1.018  |
| 379 | 0.639 | 0.02 | 3.9 | 2.492  | 1684 | 0.14  | 0.02 | 3.9 | 0.546  |
| 380 | 0.18  | 0.02 | 3.9 | 0.702  | 1685 | 0.14  | 0.02 | 3.9 | 0.546  |
| 381 | 0.159 | 0.02 | 3.9 | 0.62   | 1686 | 0.68  | 0.02 | 3.9 | 2.652  |
| 382 | 2.2   | 0.02 | 3.9 | 8.58   | 1687 | 0.864 | 0.02 | 3.9 | 3.37   |
| 383 | 1.527 | 0.02 | 3.9 | 5.955  | 1688 | 0.66  | 0.02 | 3.9 | 2.574  |
| 384 | 2.2   | 0.02 | 3.9 | 8.58   | 1689 | 0.844 | 0.02 | 3.9 | 3.292  |
| 385 | 0.528 | 0.02 | 3.9 | 2.059  | 1690 | 0.44  | 0.02 | 3.9 | 1.716  |
| 386 | 0.18  | 0.02 | 3.9 | 0.702  | 1691 | 1.86  | 0.02 | 3.9 | 7.254  |
| 387 | 1.191 | 0.02 | 3.9 | 4.645  | 1692 | 0.42  | 0.02 | 3.9 | 1.638  |
| 388 | 0.18  | 0.02 | 3.9 | 0.702  | 1693 | 1.84  | 0.02 | 3.9 | 7.176  |
| 389 | 0.463 | 0.02 | 3.9 | 1.806  | 1694 | 0.29  | 0.02 | 3.9 | 1.131  |
| 390 | 5.818 | 0.02 | 3.9 | 22.69  | 1695 | 3.15  | 0.02 | 3.9 | 12.285 |
| 391 | 1.466 | 0.02 | 3.9 | 5.717  | 1696 | 0.62  | 0.02 | 3.9 | 2.418  |
| 392 | 0.52  | 0.02 | 3.9 | 2.028  | 1697 | 0.82  | 0.02 | 3.9 | 3.198  |
| 393 | 0.904 | 0.02 | 3.9 | 3.526  | 1698 | 0.6   | 0.02 | 3.9 | 2.34   |
| 394 | 0.5   | 0.02 | 3.9 | 1.95   | 1699 | 4.713 | 0.02 | 3.9 | 18.381 |
| 395 | 2.38  | 0.02 | 3.9 | 9.282  | 1700 | 6.36  | 0.02 | 3.9 | 24.804 |
| 396 | 5.818 | 0.02 | 3.9 | 22.69  | 1701 | 0.64  | 0.02 | 3.9 | 2.496  |
| 397 | 0.11  | 0.02 | 3.9 | 0.429  | 1702 | 0.08  | 0.02 | 3.9 | 0.312  |
| 398 | 0.18  | 0.02 | 3.9 | 0.702  | 1703 | 0.14  | 0.02 | 3.9 | 0.546  |

|     |       |      |     |        |      |       |       |     |        |
|-----|-------|------|-----|--------|------|-------|-------|-----|--------|
| 399 | 3.035 | 0.02 | 3.9 | 11.837 | 1704 | 0.06  | 0.02  | 3.9 | 0.234  |
| 400 | 0.18  | 0.02 | 3.9 | 0.702  | 1705 | 1.555 | 0.02  | 3.9 | 6.065  |
| 401 | 1.151 | 0.02 | 3.9 | 4.489  | 1706 | 0.122 | 0.02  | 3.9 | 0.476  |
| 402 | 1.48  | 0.02 | 3.9 | 5.772  | 1707 | 0.14  | 0.02  | 3.9 | 0.546  |
| 403 | 0.66  | 0.02 | 3.9 | 2.574  | 1708 | 0.148 | 0.02  | 3.9 | 0.577  |
| 404 | 1.46  | 0.02 | 3.9 | 5.694  | 1709 | 0.083 | 0.02  | 3.9 | 0.324  |
| 405 | 0.854 | 0.02 | 3.9 | 3.331  | 1710 | 1.542 | 0.02  | 3.9 | 6.014  |
| 406 | 5.818 | 0.02 | 3.9 | 22.69  | 1711 | 5.259 | 0.02  | 3.9 | 20.51  |
| 407 | 0.544 | 0.02 | 3.9 | 2.122  | 1712 | 2.53  | 0.02  | 3.9 | 9.867  |
| 408 | 0.68  | 0.02 | 3.9 | 2.652  | 1713 | 0.14  | 0.02  | 3.9 | 0.546  |
| 409 | 0.46  | 0.02 | 3.9 | 1.794  | 1714 | 5.29  | 0.02  | 3.9 | 20.631 |
| 410 | 0.66  | 0.02 | 3.9 | 2.574  | 1715 | 0.14  | 0.02  | 3.9 | 0.546  |
| 411 | 3.473 | 0.02 | 3.9 | 13.545 | 1716 | 2.6   | 0.02  | 3.9 | 10.14  |
| 412 | 0.646 | 0.02 | 3.9 | 2.519  | 1717 | 6.143 | 0.02  | 3.9 | 23.958 |
| 413 | 0.18  | 0.02 | 3.9 | 0.702  | 1718 | 0.209 | 0.02  | 3.9 | 0.815  |
| 414 | 0.202 | 0.02 | 3.9 | 0.788  | 1719 | 2.24  | 0.02  | 3.9 | 8.736  |
| 415 | 0.682 | 0.02 | 3.9 | 2.66   | 1720 | 3.839 | 0.02  | 3.9 | 14.972 |
| 416 | 2.67  | 0.02 | 3.9 | 10.413 | 1721 | 4.553 | 0.02  | 3.9 | 17.757 |
| 417 | 2.718 | 0.02 | 3.9 | 10.6   | 1722 | 0.56  | 0.02  | 3.9 | 2.184  |
| 418 | 1.612 | 0.02 | 3.9 | 6.287  | 1723 | 0.82  | 0.02  | 3.9 | 3.198  |
| 419 | 1.032 | 0.02 | 3.9 | 4.025  | 1724 | 0.54  | 0.02  | 3.9 | 2.106  |
| 420 | 0.62  | 0.02 | 3.9 | 2.418  | 1725 | 2.99  | 0.02  | 3.9 | 11.661 |
| 421 | 0.18  | 0.02 | 3.9 | 0.702  | 1726 | 0.13  | 0.02  | 3.9 | 0.507  |
| 422 | 0.683 | 0.02 | 3.9 | 2.664  | 1727 | 0.14  | 0.02  | 3.9 | 0.546  |
| 423 | 1.032 | 0.02 | 3.9 | 4.025  | 1728 | 0.79  | 0.02  | 3.9 | 3.081  |
| 424 | 2.801 | 0.02 | 3.9 | 10.924 | 1729 | 0.567 | 0.02  | 3.9 | 2.211  |
| 425 | 0.73  | 0.02 | 3.9 | 2.847  | 1730 | 0.77  | 0.017 | 3.9 | 3.003  |
| 426 | 3.363 | 0.02 | 3.9 | 13.116 | 1731 | 0.55  | 0.02  | 3.9 | 2.145  |
| 427 | 0.18  | 0.02 | 3.9 | 0.702  | 1732 | 0.59  | 0.02  | 3.9 | 2.301  |
| 428 | 2.433 | 0.02 | 3.9 | 9.489  | 1733 | 1.54  | 0.02  | 3.9 | 6.006  |
| 429 | 0.73  | 0.02 | 3.9 | 2.847  | 1734 | 0.57  | 0.02  | 3.9 | 2.223  |
| 430 | 1.982 | 0.02 | 3.9 | 7.73   | 1735 | 1.52  | 0.02  | 3.9 | 5.928  |
| 431 | 5.088 | 0.02 | 3.9 | 19.843 | 1736 | 4.6   | 0.02  | 3.9 | 17.94  |
| 432 | 1.157 | 0.02 | 3.9 | 4.512  | 1737 | 0.64  | 0.02  | 3.9 | 2.496  |
| 433 | 0.68  | 0.02 | 3.9 | 2.652  | 1738 | 0.08  | 0.02  | 3.9 | 0.312  |
| 434 | 0.46  | 0.02 | 3.9 | 1.794  | 1739 | 0.14  | 0.02  | 3.9 | 0.546  |
| 435 | 0.66  | 0.02 | 3.9 | 2.574  | 1740 | 0.06  | 0.02  | 3.9 | 0.234  |
| 436 | 3.473 | 0.02 | 3.9 | 13.545 | 1741 | 1.566 | 0.02  | 3.9 | 6.107  |
| 437 | 2.705 | 0.02 | 3.9 | 10.55  | 1742 | 0.095 | 0.02  | 3.9 | 0.371  |
| 438 | 0.18  | 0.02 | 3.9 | 0.702  | 1743 | 0.14  | 0.02  | 3.9 | 0.546  |
| 439 | 2.165 | 0.02 | 3.9 | 8.444  | 1744 | 0.16  | 0.02  | 3.9 | 0.624  |
| 440 | 0.724 | 0.02 | 3.9 | 2.824  | 1745 | 0.113 | 0.02  | 3.9 | 0.441  |
| 441 | 0.5   | 0.02 | 3.9 | 1.95   | 1746 | 1.322 | 0.02  | 3.9 | 5.156  |
| 442 | 3.223 | 0.02 | 3.9 | 12.57  | 1747 | 5.259 | 0.02  | 3.9 | 20.51  |
| 443 | 1.18  | 0.02 | 3.9 | 4.602  | 1748 | 2.315 | 0.02  | 3.9 | 9.029  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 444 | 0.16  | 0.02 | 3.9 | 0.624  | 1749 | 0.14  | 0.02 | 3.9 | 0.546  |
| 445 | 2.358 | 0.02 | 3.9 | 9.196  | 1750 | 4.555 | 0.02 | 3.9 | 17.764 |
| 446 | 0.28  | 0.02 | 3.9 | 1.092  | 1751 | 0.14  | 0.02 | 3.9 | 0.546  |
| 447 | 2.26  | 0.02 | 3.9 | 8.814  | 1752 | 2.08  | 0.02 | 3.9 | 8.112  |
| 448 | 0.231 | 0.02 | 3.9 | 0.901  | 1753 | 5.259 | 0.02 | 3.9 | 20.51  |
| 449 | 0.16  | 0.02 | 3.9 | 0.624  | 1754 | 1.323 | 0.02 | 3.9 | 5.16   |
| 450 | 0.511 | 0.02 | 3.9 | 1.993  | 1755 | 0.097 | 0.02 | 3.9 | 0.378  |
| 451 | 2.976 | 0.02 | 3.9 | 11.606 | 1756 | 0.14  | 0.02 | 3.9 | 0.546  |
| 452 | 2.91  | 0.02 | 3.9 | 11.349 | 1757 | 0.16  | 0.02 | 3.9 | 0.624  |
| 453 | 1.923 | 0.02 | 3.9 | 7.5    | 1758 | 0.095 | 0.02 | 3.9 | 0.371  |
| 454 | 0.18  | 0.02 | 3.9 | 0.702  | 1759 | 1.56  | 0.02 | 3.9 | 6.084  |
| 455 | 1.244 | 0.02 | 3.9 | 4.852  | 1760 | 0.08  | 0.02 | 3.9 | 0.312  |
| 456 | 0.282 | 0.02 | 3.9 | 1.1    | 1761 | 0.14  | 0.02 | 3.9 | 0.546  |
| 457 | 0.18  | 0.02 | 3.9 | 0.702  | 1762 | 0.06  | 0.02 | 3.9 | 0.234  |
| 458 | 0.262 | 0.02 | 3.9 | 1.022  | 1763 | 0.64  | 0.02 | 3.9 | 2.496  |
| 459 | 1.166 | 0.02 | 3.9 | 4.547  | 1764 | 0.319 | 0.02 | 3.9 | 1.244  |
| 460 | 0.18  | 0.02 | 3.9 | 0.702  | 1765 | 0.14  | 0.02 | 3.9 | 0.546  |
| 461 | 0.487 | 0.02 | 3.9 | 1.899  | 1766 | 0.06  | 0.02 | 3.9 | 0.234  |
| 462 | 2.39  | 0.02 | 3.9 | 9.321  | 1767 | 0.14  | 0.02 | 3.9 | 0.546  |
| 463 | 1.457 | 0.02 | 3.9 | 5.682  | 1768 | 0.059 | 0.02 | 3.9 | 0.23   |
| 464 | 2.39  | 0.02 | 3.9 | 9.321  | 1769 | 6.22  | 0.02 | 3.9 | 24.258 |
| 465 | 0.13  | 0.02 | 3.9 | 0.507  | 1771 | 0.15  | 0.02 | 3.9 | 0.585  |
| 466 | 0.16  | 0.02 | 3.9 | 0.624  | 1772 | 1.483 | 0.02 | 3.9 | 5.784  |
| 467 | 0.457 | 0.02 | 3.9 | 1.782  | 1773 | 0.13  | 0.02 | 3.9 | 0.507  |
| 468 | 0.18  | 0.02 | 3.9 | 0.702  | 1774 | 0.14  | 0.02 | 3.9 | 0.546  |
| 469 | 0.107 | 0.02 | 3.9 | 0.417  | 1775 | 0.88  | 0.02 | 3.9 | 3.432  |
| 470 | 2.39  | 0.02 | 3.9 | 9.321  | 1776 | 0.12  | 0.02 | 3.9 | 0.468  |
| 471 | 2.967 | 0.02 | 3.9 | 11.571 | 1777 | 0.13  | 0.02 | 3.9 | 0.507  |
| 472 | 0.36  | 0.02 | 3.9 | 1.404  | 1778 | 1.503 | 0.02 | 3.9 | 5.862  |
| 473 | 0.86  | 0.02 | 3.9 | 3.354  | 1779 | 0.33  | 0.02 | 3.9 | 1.287  |
| 474 | 2.03  | 0.02 | 3.9 | 7.917  | 1780 | 6.22  | 0.02 | 3.9 | 24.258 |
| 475 | 2.9   | 0.02 | 3.9 | 11.31  | 1781 | 0.695 | 0.02 | 3.9 | 2.71   |
| 476 | 0.18  | 0.02 | 3.9 | 0.702  | 1782 | 0.14  | 0.02 | 3.9 | 0.546  |
| 477 | 6.236 | 0.02 | 3.9 | 24.32  | 1783 | 0.105 | 0.02 | 3.9 | 0.409  |
| 478 | 0.18  | 0.02 | 3.9 | 0.702  | 1784 | 2.593 | 0.02 | 3.9 | 10.113 |
| 479 | 3.136 | 0.02 | 3.9 | 12.23  | 1785 | 0.12  | 0.02 | 3.9 | 0.468  |
| 480 | 2.39  | 0.02 | 3.9 | 9.321  | 1786 | 5.13  | 0.02 | 3.9 | 20.007 |
| 481 | 4.106 | 0.02 | 3.9 | 16.013 | 1787 | 0.08  | 0.02 | 3.9 | 0.312  |
| 482 | 2.39  | 0.02 | 3.9 | 9.321  | 1788 | 0.14  | 0.02 | 3.9 | 0.546  |
| 483 | 0.129 | 0.02 | 3.9 | 0.503  | 1789 | 0.3   | 0.02 | 3.9 | 1.17   |
| 484 | 0.18  | 0.02 | 3.9 | 0.702  | 1790 | 0.14  | 0.02 | 3.9 | 0.546  |
| 485 | 0.438 | 0.02 | 3.9 | 1.708  | 1791 | 0.06  | 0.02 | 3.9 | 0.234  |
| 486 | 0.18  | 0.02 | 3.9 | 0.702  | 1792 | 5.13  | 0.02 | 3.9 | 20.007 |
| 487 | 0.109 | 0.02 | 3.9 | 0.425  | 1793 | 0.14  | 0.02 | 3.9 | 0.546  |
| 488 | 2.39  | 0.02 | 3.9 | 9.321  | 1794 | 2.573 | 0.02 | 3.9 | 10.035 |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 489 | 1.827 | 0.02 | 3.9 | 7.125  | 1795 | 0.13  | 0.02 | 3.9 | 0.507  |
| 490 | 0.21  | 0.02 | 3.9 | 0.819  | 1796 | 0.12  | 0.02 | 3.9 | 0.468  |
| 491 | 0.59  | 0.02 | 3.9 | 2.301  | 1797 | 4.921 | 0.02 | 3.9 | 19.192 |
| 492 | 2.18  | 0.02 | 3.9 | 8.502  | 1798 | 0.14  | 0.02 | 3.9 | 0.546  |
| 493 | 1.488 | 0.02 | 3.9 | 5.803  | 1799 | 2.431 | 0.02 | 3.9 | 9.481  |
| 494 | 0.18  | 0.02 | 3.9 | 0.702  | 1800 | 5.259 | 0.02 | 3.9 | 20.51  |
| 495 | 4.164 | 0.02 | 3.9 | 16.24  | 1801 | 1.322 | 0.02 | 3.9 | 5.156  |
| 496 | 0.18  | 0.02 | 3.9 | 0.702  | 1802 | 0.093 | 0.02 | 3.9 | 0.363  |
| 497 | 2.476 | 0.02 | 3.9 | 9.656  | 1803 | 0.16  | 0.02 | 3.9 | 0.624  |
| 498 | 2.18  | 0.02 | 3.9 | 8.502  | 1804 | 0.16  | 0.02 | 3.9 | 0.624  |
| 499 | 0.12  | 0.02 | 3.9 | 0.468  | 1805 | 0.075 | 0.02 | 3.9 | 0.293  |
| 500 | 0.19  | 0.02 | 3.9 | 0.741  | 1806 | 1.566 | 0.02 | 3.9 | 6.107  |
| 501 | 0.724 | 0.02 | 3.9 | 2.824  | 1807 | 0.08  | 0.02 | 3.9 | 0.312  |
| 502 | 0.5   | 0.02 | 3.9 | 1.95   | 1808 | 0.12  | 0.02 | 3.9 | 0.468  |
| 503 | 2.602 | 0.02 | 3.9 | 10.148 | 1809 | 0.08  | 0.02 | 3.9 | 0.312  |
| 504 | 2.91  | 0.02 | 3.9 | 11.349 | 1810 | 0.66  | 0.02 | 3.9 | 2.574  |
| 505 | 0.13  | 0.02 | 3.9 | 0.507  | 1811 | 4.58  | 0.02 | 3.9 | 17.862 |
| 506 | 0.16  | 0.02 | 3.9 | 0.624  | 1812 | 0.64  | 0.02 | 3.9 | 2.496  |
| 507 | 0.29  | 0.02 | 3.9 | 1.131  | 1813 | 0.08  | 0.02 | 3.9 | 0.312  |
| 508 | 3.11  | 0.02 | 3.9 | 12.129 | 1814 | 0.14  | 0.02 | 3.9 | 0.546  |
| 509 | 2.097 | 0.02 | 3.9 | 8.178  | 1815 | 0.06  | 0.02 | 3.9 | 0.234  |
| 510 | 0.5   | 0.02 | 3.9 | 1.95   | 1816 | 1.56  | 0.02 | 3.9 | 6.084  |
| 511 | 0.924 | 0.02 | 3.9 | 3.604  | 1817 | 0.087 | 0.02 | 3.9 | 0.339  |
| 512 | 0.22  | 0.02 | 3.9 | 0.858  | 1818 | 0.16  | 0.02 | 3.9 | 0.624  |
| 513 | 1.475 | 0.02 | 3.9 | 5.753  | 1819 | 0.16  | 0.02 | 3.9 | 0.624  |
| 514 | 0.08  | 0.02 | 3.9 | 0.312  | 1820 | 0.077 | 0.02 | 3.9 | 0.3    |
| 515 | 0.674 | 0.02 | 3.9 | 2.629  | 1821 | 1.322 | 0.02 | 3.9 | 5.156  |
| 516 | 0.16  | 0.02 | 3.9 | 0.624  | 1822 | 5.259 | 0.02 | 3.9 | 20.51  |
| 517 | 0.75  | 0.02 | 3.9 | 2.925  | 1823 | 2.31  | 0.02 | 3.9 | 9.009  |
| 518 | 1.02  | 0.02 | 3.9 | 3.978  | 1824 | 0.12  | 0.02 | 3.9 | 0.468  |
| 519 | 1.957 | 0.02 | 3.9 | 7.632  | 1825 | 0.419 | 0.02 | 3.9 | 1.634  |
| 520 | 0.469 | 0.02 | 3.9 | 1.829  | 1826 | 0.14  | 0.02 | 3.9 | 0.546  |
| 521 | 1.604 | 0.02 | 3.9 | 6.256  | 1827 | 0.11  | 0.02 | 3.9 | 0.429  |
| 522 | 1.617 | 0.02 | 3.9 | 6.306  | 1828 | 0.14  | 0.02 | 3.9 | 0.546  |
| 523 | 0.251 | 0.02 | 3.9 | 0.979  | 1829 | 0.109 | 0.02 | 3.9 | 0.425  |
| 524 | 0.531 | 0.02 | 3.9 | 2.071  | 1830 | 1.653 | 0.02 | 3.9 | 6.447  |
| 525 | 2.38  | 0.02 | 3.9 | 9.282  | 1831 | 0.38  | 0.02 | 3.9 | 1.482  |
| 526 | 0.14  | 0.02 | 3.9 | 0.546  | 1832 | 1.47  | 0.02 | 3.9 | 5.733  |
| 527 | 3.003 | 0.02 | 3.9 | 11.712 | 1833 | 0.36  | 0.02 | 3.9 | 1.404  |
| 528 | 0.401 | 0.02 | 3.9 | 1.564  | 1834 | 7.723 | 0.02 | 3.9 | 30.12  |
| 529 | 0.14  | 0.02 | 3.9 | 0.546  | 1835 | 4.58  | 0.02 | 3.9 | 17.862 |
| 530 | 0.382 | 0.02 | 3.9 | 1.49   | 1836 | 0.08  | 0.02 | 3.9 | 0.312  |
| 531 | 2.297 | 0.02 | 3.9 | 8.958  | 1837 | 0.14  | 0.02 | 3.9 | 0.546  |
| 532 | 0.432 | 0.02 | 3.9 | 1.685  | 1838 | 0.3   | 0.02 | 3.9 | 1.17   |
| 533 | 0.273 | 0.02 | 3.9 | 1.065  | 1839 | 0.14  | 0.02 | 3.9 | 0.546  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 534 | 0.14  | 0.02 | 3.9 | 0.546  | 1840 | 0.06  | 0.02 | 3.9 | 0.234  |
| 535 | 0.101 | 0.02 | 3.9 | 0.394  | 1841 | 0.79  | 0.02 | 3.9 | 3.081  |
| 536 | 3.312 | 0.02 | 3.9 | 12.917 | 1842 | 0.567 | 0.02 | 3.9 | 2.211  |
| 537 | 5.968 | 0.02 | 3.9 | 23.275 | 1843 | 0.77  | 0.02 | 3.9 | 3.003  |
| 538 | 0.16  | 0.02 | 3.9 | 0.624  | 1844 | 0.547 | 0.02 | 3.9 | 2.133  |
| 539 | 0.202 | 0.02 | 3.9 | 0.788  | 1845 | 4.6   | 0.02 | 3.9 | 17.94  |
| 540 | 3.449 | 0.02 | 3.9 | 13.451 | 1846 | 0.64  | 0.02 | 3.9 | 2.496  |
| 541 | 0.14  | 0.02 | 3.9 | 0.546  | 1847 | 0.08  | 0.02 | 3.9 | 0.312  |
| 542 | 3.429 | 0.02 | 3.9 | 13.373 | 1848 | 0.14  | 0.02 | 3.9 | 0.546  |
| 543 | 5.299 | 0.02 | 3.9 | 20.666 | 1849 | 0.06  | 0.02 | 3.9 | 0.234  |
| 544 | 3.459 | 0.02 | 3.9 | 13.49  | 1850 | 1.566 | 0.02 | 3.9 | 6.107  |
| 545 | 0.12  | 0.02 | 3.9 | 0.468  | 1851 | 0.095 | 0.02 | 3.9 | 0.371  |
| 546 | 0.738 | 0.02 | 3.9 | 2.878  | 1852 | 0.168 | 0.02 | 3.9 | 0.655  |
| 547 | 2.36  | 0.02 | 3.9 | 9.204  | 1853 | 0.16  | 0.02 | 3.9 | 0.624  |
| 548 | 0.134 | 0.02 | 3.9 | 0.523  | 1854 | 0.093 | 0.02 | 3.9 | 0.363  |
| 549 | 0.12  | 0.02 | 3.9 | 0.468  | 1855 | 1.322 | 0.02 | 3.9 | 5.156  |
| 550 | 0.294 | 0.02 | 3.9 | 1.147  | 1856 | 5.259 | 0.02 | 3.9 | 20.51  |
| 551 | 2.5   | 0.02 | 3.9 | 9.75   | 1857 | 2.451 | 0.02 | 3.9 | 9.559  |
| 552 | 2.561 | 0.02 | 3.9 | 9.988  | 1858 | 0.14  | 0.02 | 3.9 | 0.546  |
| 553 | 0.134 | 0.02 | 3.9 | 0.523  | 1859 | 5.041 | 0.02 | 3.9 | 19.66  |
| 554 | 0.16  | 0.02 | 3.9 | 0.624  | 1860 | 0.14  | 0.02 | 3.9 | 0.546  |
| 555 | 5.816 | 0.02 | 3.9 | 22.682 | 1861 | 2.43  | 0.02 | 3.9 | 9.477  |
| 556 | 0.237 | 0.02 | 3.9 | 0.924  | 1862 | 5.259 | 0.02 | 3.9 | 20.51  |
| 557 | 0.16  | 0.02 | 3.9 | 0.624  | 1863 | 1.322 | 0.02 | 3.9 | 5.156  |
| 558 | 5.72  | 0.02 | 3.9 | 22.308 | 1864 | 0.097 | 0.02 | 3.9 | 0.378  |
| 559 | 0.3   | 0.02 | 3.9 | 1.17   | 1865 | 0.14  | 0.02 | 3.9 | 0.546  |
| 560 | 0.14  | 0.02 | 3.9 | 0.546  | 1866 | 0.16  | 0.02 | 3.9 | 0.624  |
| 561 | 0.28  | 0.02 | 3.9 | 1.092  | 1867 | 0.095 | 0.02 | 3.9 | 0.371  |
| 562 | 0.13  | 0.02 | 3.9 | 0.507  | 1868 | 1.56  | 0.02 | 3.9 | 6.084  |
| 563 | 0.14  | 0.02 | 3.9 | 0.546  | 1869 | 0.08  | 0.02 | 3.9 | 0.312  |
| 564 | 0.18  | 0.02 | 3.9 | 0.702  | 1870 | 0.14  | 0.02 | 3.9 | 0.546  |
| 565 | 2.215 | 0.02 | 3.9 | 8.638  | 1871 | 0.06  | 0.02 | 3.9 | 0.234  |
| 566 | 1.33  | 0.02 | 3.9 | 5.187  | 1872 | 0.64  | 0.02 | 3.9 | 2.496  |
| 567 | 0.36  | 0.02 | 3.9 | 1.404  | 1873 | 0.79  | 0.02 | 3.9 | 3.081  |
| 568 | 0.519 | 0.02 | 3.9 | 2.024  | 1874 | 0.57  | 0.02 | 3.9 | 2.223  |
| 569 | 2.39  | 0.02 | 3.9 | 9.321  | 1875 | 0.77  | 0.02 | 3.9 | 3.003  |
| 570 | 0.111 | 0.02 | 3.9 | 0.433  | 1876 | 0.547 | 0.02 | 3.9 | 2.133  |
| 571 | 0.14  | 0.02 | 3.9 | 0.546  | 1877 | 0.419 | 0.02 | 3.9 | 1.634  |
| 572 | 3.049 | 0.02 | 3.9 | 11.891 | 1878 | 0.14  | 0.02 | 3.9 | 0.546  |
| 573 | 0.14  | 0.02 | 3.9 | 0.546  | 1879 | 0.14  | 0.02 | 3.9 | 0.546  |
| 574 | 2.738 | 0.02 | 3.9 | 10.678 | 1880 | 0.109 | 0.02 | 3.9 | 0.425  |
| 575 | 2.23  | 0.02 | 3.9 | 8.697  | 1881 | 3.001 | 0.02 | 3.9 | 11.704 |
| 576 | 1.849 | 0.02 | 3.9 | 7.211  | 1882 | 0.385 | 0.02 | 3.9 | 1.502  |
| 577 | 2.735 | 0.02 | 3.9 | 10.666 | 1883 | 1.32  | 0.02 | 3.9 | 5.148  |
| 578 | 5.323 | 0.02 | 3.9 | 20.76  | 1884 | 0.365 | 0.02 | 3.9 | 1.424  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 579 | 5.816 | 0.02 | 3.9 | 22.682 | 1885 | 3.381 | 0.02 | 3.9 | 13.186 |
| 580 | 0.12  | 0.02 | 3.9 | 0.468  | 1886 | 0.08  | 0.02 | 3.9 | 0.312  |
| 581 | 0.651 | 0.02 | 3.9 | 2.539  | 1887 | 0.14  | 0.02 | 3.9 | 0.546  |
| 582 | 3.55  | 0.02 | 3.9 | 13.845 | 1888 | 0.3   | 0.02 | 3.9 | 1.17   |
| 583 | 0.632 | 0.02 | 3.9 | 2.465  | 1889 | 0.14  | 0.02 | 3.9 | 0.546  |
| 584 | 0.27  | 0.02 | 3.9 | 1.053  | 1890 | 0.06  | 0.02 | 3.9 | 0.234  |
| 585 | 1.014 | 0.02 | 3.9 | 3.955  | 1891 | 3.379 | 0.02 | 3.9 | 13.178 |
| 586 | 1.046 | 0.02 | 3.9 | 4.079  | 1892 | 0.295 | 0.02 | 3.9 | 1.15   |
| 587 | 0.87  | 0.02 | 3.9 | 3.393  | 1893 | 1.32  | 0.02 | 3.9 | 5.148  |
| 588 | 0.124 | 0.02 | 3.9 | 0.484  | 1894 | 0.275 | 0.02 | 3.9 | 1.073  |
| 589 | 0.14  | 0.02 | 3.9 | 0.546  | 1895 | 3.003 | 0.02 | 3.9 | 11.712 |
| 590 | 1.896 | 0.02 | 3.9 | 7.394  | 1896 | 0.11  | 0.02 | 3.9 | 0.429  |
| 591 | 0.14  | 0.02 | 3.9 | 0.546  | 1897 | 5.31  | 0.02 | 3.9 | 20.709 |
| 592 | 1.612 | 0.02 | 3.9 | 6.287  | 1898 | 0.14  | 0.02 | 3.9 | 0.546  |
| 593 | 0.87  | 0.02 | 3.9 | 3.393  | 1899 | 2.68  | 0.02 | 3.9 | 10.452 |
| 594 | 0.119 | 0.02 | 3.9 | 0.464  | 1900 | 5.259 | 0.02 | 3.9 | 20.51  |
| 595 | 0.424 | 0.02 | 3.9 | 1.654  | 1901 | 0.29  | 0.02 | 3.9 | 1.131  |
| 596 | 0.14  | 0.02 | 3.9 | 0.546  | 1902 | 0.864 | 0.02 | 3.9 | 3.37   |
| 597 | 0.114 | 0.02 | 3.9 | 0.445  | 1903 | 0.268 | 0.02 | 3.9 | 1.045  |
| 598 | 0.87  | 0.02 | 3.9 | 3.393  | 1904 | 2.24  | 0.02 | 3.9 | 8.736  |
| 599 | 0.14  | 0.02 | 3.9 | 0.546  | 1905 | 4.188 | 0.02 | 3.9 | 16.333 |
| 600 | 0.85  | 0.02 | 3.9 | 3.315  | 1906 | 2.29  | 0.02 | 3.9 | 8.931  |
| 601 | 0.13  | 0.02 | 3.9 | 0.507  | 1907 | 0.5   | 0.02 | 3.9 | 1.95   |
| 602 | 0.14  | 0.02 | 3.9 | 0.546  | 1908 | 0.67  | 0.02 | 3.9 | 2.613  |
| 603 | 0.13  | 0.02 | 3.9 | 0.507  | 1909 | 0.39  | 0.02 | 3.9 | 1.521  |
| 604 | 0.141 | 0.02 | 3.9 | 0.55   | 1910 | 4.223 | 0.02 | 3.9 | 16.47  |
| 605 | 0.693 | 0.02 | 3.9 | 2.703  | 1911 | 0.41  | 0.02 | 3.9 | 1.599  |
| 606 | 0.14  | 0.02 | 3.9 | 0.546  | 1912 | 1.16  | 0.02 | 3.9 | 4.524  |
| 607 | 0.378 | 0.02 | 3.9 | 1.474  | 1913 | 0.13  | 0.02 | 3.9 | 0.507  |
| 608 | 2.443 | 0.02 | 3.9 | 9.528  | 1914 | 0.14  | 0.02 | 3.9 | 0.546  |
| 609 | 1.512 | 0.02 | 3.9 | 5.897  | 1915 | 3.276 | 0.02 | 3.9 | 12.776 |
| 610 | 2.443 | 0.02 | 3.9 | 9.528  | 1916 | 0.127 | 0.02 | 3.9 | 0.495  |
| 611 | 0.129 | 0.02 | 3.9 | 0.503  | 1917 | 0.14  | 0.02 | 3.9 | 0.546  |
| 612 | 0.14  | 0.02 | 3.9 | 0.546  | 1918 | 0.107 | 0.02 | 3.9 | 0.417  |
| 613 | 1.777 | 0.02 | 3.9 | 6.93   | 1919 | 1.431 | 0.02 | 3.9 | 5.581  |
| 614 | 0.134 | 0.02 | 3.9 | 0.523  | 1920 | 0.27  | 0.02 | 3.9 | 1.053  |
| 615 | 0.14  | 0.02 | 3.9 | 0.546  | 1921 | 0.343 | 0.02 | 3.9 | 1.338  |
| 616 | 3.291 | 0.02 | 3.9 | 12.835 | 1922 | 2.989 | 0.02 | 3.9 | 11.657 |
| 617 | 0.12  | 0.02 | 3.9 | 0.468  | 1923 | 0.363 | 0.02 | 3.9 | 1.416  |
| 618 | 0.134 | 0.02 | 3.9 | 0.523  | 1924 | 0.271 | 0.02 | 3.9 | 1.057  |
| 619 | 0.134 | 0.02 | 3.9 | 0.523  | 1925 | 0.343 | 0.02 | 3.9 | 1.338  |
| 620 | 0.12  | 0.02 | 3.9 | 0.468  | 1926 | 2.344 | 0.02 | 3.9 | 9.142  |
| 621 | 0.134 | 0.02 | 3.9 | 0.523  | 1927 | 0.11  | 0.02 | 3.9 | 0.429  |
| 622 | 2.693 | 0.02 | 3.9 | 10.503 | 1928 | 1.762 | 0.02 | 3.9 | 6.872  |
| 623 | 2.443 | 0.02 | 3.9 | 9.528  | 1929 | 0.27  | 0.02 | 3.9 | 1.053  |



|     |       |      |     |        |      |       |       |     |        |
|-----|-------|------|-----|--------|------|-------|-------|-----|--------|
| 624 | 0.238 | 0.02 | 3.9 | 0.928  | 1930 | 0.14  | 0.02  | 3.9 | 0.546  |
| 625 | 0.26  | 0.02 | 3.9 | 1.014  | 1931 | 0.11  | 0.02  | 3.9 | 0.429  |
| 626 | 0.176 | 0.02 | 3.9 | 0.686  | 1932 | 7.357 | 0.02  | 3.9 | 28.692 |
| 627 | 0.14  | 0.02 | 3.9 | 0.546  | 1933 | 3.445 | 0.02  | 3.9 | 13.435 |
| 628 | 2.356 | 0.02 | 3.9 | 9.188  | 1934 | 0.53  | 0.02  | 3.9 | 2.067  |
| 629 | 0.14  | 0.02 | 3.9 | 0.546  | 1935 | 0.07  | 0.02  | 3.9 | 0.273  |
| 630 | 0.11  | 0.02 | 3.9 | 0.429  | 1936 | 4.873 | 0.02  | 3.9 | 19.005 |
| 631 | 2.723 | 0.02 | 3.9 | 10.62  | 1937 | 1.954 | 0.02  | 3.9 | 7.621  |
| 632 | 6.142 | 0.02 | 3.9 | 23.954 | 1939 | 1.755 | 0.02  | 3.9 | 6.844  |
| 633 | 0.12  | 0.02 | 3.9 | 0.468  | 1940 | 0.14  | 0.02  | 3.9 | 0.546  |
| 634 | 1.994 | 0.02 | 3.9 | 7.777  | 1941 | 1.735 | 0.02  | 3.9 | 6.767  |
| 635 | 0.13  | 0.02 | 3.9 | 0.507  | 1942 | 2.686 | 0.02  | 3.9 | 10.475 |
| 636 | 0.118 | 0.02 | 3.9 | 0.46   | 1943 | 0.32  | 0.02  | 3.9 | 1.248  |
| 637 | 0.163 | 0.02 | 3.9 | 0.636  | 1944 | 0.73  | 0.02  | 3.9 | 2.847  |
| 638 | 1.295 | 0.02 | 3.9 | 5.05   | 1945 | 0.77  | 0.029 | 3.9 | 3.003  |
| 639 | 1.902 | 0.02 | 3.9 | 7.418  | 1946 | 0.561 | 0.02  | 3.9 | 2.188  |
| 640 | 2.68  | 0.02 | 3.9 | 10.452 | 1947 | 0.93  | 0.02  | 3.9 | 3.627  |
| 641 | 2.066 | 0.02 | 3.9 | 8.057  | 1948 | 0.317 | 0.02  | 3.9 | 1.236  |
| 642 | 0.14  | 0.02 | 3.9 | 0.546  | 1949 | 6.569 | 0.02  | 3.9 | 25.619 |
| 643 | 4.252 | 0.02 | 3.9 | 16.583 | 1950 | 0.64  | 0.02  | 3.9 | 2.496  |
| 644 | 0.16  | 0.02 | 3.9 | 0.624  | 1951 | 0.08  | 0.02  | 3.9 | 0.312  |
| 645 | 2.046 | 0.02 | 3.9 | 7.979  | 1952 | 0.14  | 0.02  | 3.9 | 0.546  |
| 646 | 2.68  | 0.02 | 3.9 | 10.452 | 1953 | 0.06  | 0.02  | 3.9 | 0.234  |
| 647 | 1.923 | 0.02 | 3.9 | 7.5    | 1954 | 1.56  | 0.02  | 3.9 | 6.084  |
| 648 | 1.295 | 0.02 | 3.9 | 5.05   | 1955 | 0.094 | 0.02  | 3.9 | 0.367  |
| 649 | 0.14  | 0.02 | 3.9 | 0.546  | 1956 | 0.14  | 0.02  | 3.9 | 0.546  |
| 650 | 0.16  | 0.02 | 3.9 | 0.624  | 1957 | 0.16  | 0.02  | 3.9 | 0.624  |
| 651 | 0.11  | 0.02 | 3.9 | 0.429  | 1958 | 0.096 | 0.02  | 3.9 | 0.374  |
| 652 | 0.143 | 0.02 | 3.9 | 0.558  | 1959 | 1.316 | 0.02  | 3.9 | 5.132  |
| 653 | 0.093 | 0.02 | 3.9 | 0.363  | 1960 | 5.259 | 0.02  | 3.9 | 20.51  |
| 654 | 0.16  | 0.02 | 3.9 | 0.624  | 1961 | 2.45  | 0.02  | 3.9 | 9.555  |
| 655 | 3.446 | 0.02 | 3.9 | 13.439 | 1962 | 0.098 | 0.02  | 3.9 | 0.382  |
| 656 | 0.649 | 0.02 | 3.9 | 2.531  | 1963 | 0.68  | 0.02  | 3.9 | 2.652  |
| 657 | 0.1   | 0.02 | 3.9 | 0.39   | 1964 | 0.864 | 0.02  | 3.9 | 3.37   |
| 658 | 2.42  | 0.02 | 3.9 | 9.438  | 1965 | 0.66  | 0.02  | 3.9 | 2.574  |
| 659 | 0.08  | 0.02 | 3.9 | 0.312  | 1966 | 0.844 | 0.02  | 3.9 | 3.292  |
| 660 | 2.21  | 0.02 | 3.9 | 8.619  | 1967 | 0.79  | 0.02  | 3.9 | 3.081  |
| 661 | 3.466 | 0.02 | 3.9 | 13.517 | 1968 | 1.54  | 0.02  | 3.9 | 6.006  |
| 662 | 0.14  | 0.02 | 3.9 | 0.546  | 1969 | 0.08  | 0.02  | 3.9 | 0.312  |
| 663 | 3.446 | 0.02 | 3.9 | 13.439 | 1970 | 0.14  | 0.02  | 3.9 | 0.546  |
| 664 | 0.8   | 0.02 | 3.9 | 3.12   | 1971 | 0.06  | 0.02  | 3.9 | 0.234  |
| 665 | 0.836 | 0.02 | 3.9 | 3.26   | 1972 | 6.22  | 0.02  | 3.9 | 24.258 |
| 666 | 0.696 | 0.02 | 3.9 | 2.714  | 1973 | 0.68  | 0.02  | 3.9 | 2.652  |
| 667 | 0.12  | 0.02 | 3.9 | 0.468  | 1974 | 1.304 | 0.02  | 3.9 | 5.086  |
| 668 | 3.01  | 0.02 | 3.9 | 11.739 | 1975 | 0.06  | 0.02  | 3.9 | 0.234  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 669 | 0.16  | 0.02 | 3.9 | 0.624  | 1976 | 0.14  | 0.02 | 3.9 | 0.546  |
| 670 | 0.55  | 0.02 | 3.9 | 2.145  | 1977 | 0.88  | 0.02 | 3.9 | 3.432  |
| 671 | 1.588 | 0.02 | 3.9 | 6.193  | 1978 | 8.814 | 0.02 | 3.9 | 34.375 |
| 672 | 3.56  | 0.02 | 3.9 | 13.884 | 1979 | 0.63  | 0.02 | 3.9 | 2.457  |
| 673 | 0.13  | 0.02 | 3.9 | 0.507  | 1980 | 0.55  | 0.02 | 3.9 | 2.145  |
| 674 | 0.14  | 0.02 | 3.9 | 0.546  | 1981 | 4.6   | 0.02 | 3.9 | 17.94  |
| 675 | 3.635 | 0.02 | 3.9 | 14.176 | 1982 | 0.84  | 0.02 | 3.9 | 3.276  |
| 676 | 2.76  | 0.02 | 3.9 | 10.764 | 1983 | 0.08  | 0.02 | 3.9 | 0.312  |
| 677 | 1.615 | 0.02 | 3.9 | 6.299  | 1984 | 0.14  | 0.02 | 3.9 | 0.546  |
| 678 | 0.14  | 0.02 | 3.9 | 0.546  | 1985 | 0.06  | 0.02 | 3.9 | 0.234  |
| 679 | 0.714 | 0.02 | 3.9 | 2.785  | 1986 | 1.363 | 0.02 | 3.9 | 5.316  |
| 680 | 0.351 | 0.02 | 3.9 | 1.369  | 1987 | 0.103 | 0.02 | 3.9 | 0.402  |
| 681 | 0.14  | 0.02 | 3.9 | 0.546  | 1988 | 0.14  | 0.02 | 3.9 | 0.546  |
| 682 | 0.331 | 0.02 | 3.9 | 1.291  | 1989 | 0.16  | 0.02 | 3.9 | 0.624  |
| 683 | 0.655 | 0.02 | 3.9 | 2.555  | 1990 | 0.086 | 0.02 | 3.9 | 0.335  |
| 684 | 2.76  | 0.02 | 3.9 | 10.764 | 1991 | 1.322 | 0.02 | 3.9 | 5.156  |
| 685 | 3.431 | 0.02 | 3.9 | 13.381 | 1992 | 5.284 | 0.02 | 3.9 | 20.608 |
| 686 | 3.56  | 0.02 | 3.9 | 13.884 | 1993 | 2.28  | 0.02 | 3.9 | 8.892  |
| 687 | 4.012 | 0.02 | 3.9 | 15.647 | 1994 | 0.14  | 0.02 | 3.9 | 0.546  |
| 688 | 2.493 | 0.02 | 3.9 | 9.723  | 1995 | 4.26  | 0.02 | 3.9 | 16.614 |
| 689 | 1.016 | 0.02 | 3.9 | 3.962  | 1996 | 0.14  | 0.02 | 3.9 | 0.546  |
| 690 | 0.16  | 0.02 | 3.9 | 0.624  | 1997 | 1.82  | 0.02 | 3.9 | 7.098  |
| 691 | 0.109 | 0.02 | 3.9 | 0.425  | 1998 | 5.284 | 0.02 | 3.9 | 20.608 |
| 692 | 1.707 | 0.02 | 3.9 | 6.657  | 1999 | 1.322 | 0.02 | 3.9 | 5.156  |
| 693 | 0.14  | 0.02 | 3.9 | 0.546  | 2000 | 0.11  | 0.02 | 3.9 | 0.429  |
| 694 | 0.267 | 0.02 | 3.9 | 1.041  | 2001 | 0.14  | 0.02 | 3.9 | 0.546  |
| 695 | 2.708 | 0.02 | 3.9 | 10.561 | 2002 | 0.16  | 0.02 | 3.9 | 0.624  |
| 696 | 0.14  | 0.02 | 3.9 | 0.546  | 2003 | 0.089 | 0.02 | 3.9 | 0.347  |
| 697 | 2.688 | 0.02 | 3.9 | 10.483 | 2004 | 1.363 | 0.02 | 3.9 | 5.316  |
| 698 | 1.26  | 0.02 | 3.9 | 4.914  | 2005 | 0.08  | 0.02 | 3.9 | 0.312  |
| 699 | 3.698 | 0.02 | 3.9 | 14.422 | 2006 | 0.14  | 0.02 | 3.9 | 0.546  |
| 700 | 1.26  | 0.02 | 3.9 | 4.914  | 2007 | 0.84  | 0.02 | 3.9 | 3.276  |
| 701 | 0.11  | 0.02 | 3.9 | 0.429  | 2008 | 1.56  | 0.02 | 3.9 | 6.084  |
| 702 | 0.16  | 0.02 | 3.9 | 0.624  | 2009 | 0.57  | 0.02 | 3.9 | 2.223  |
| 703 | 0.27  | 0.02 | 3.9 | 1.053  | 2010 | 1.52  | 0.02 | 3.9 | 5.928  |
| 704 | 1.69  | 0.02 | 3.9 | 6.591  | 2011 | 0.57  | 0.02 | 3.9 | 2.223  |
| 705 | 0.14  | 0.02 | 3.9 | 0.546  | 2012 | 4.6   | 0.02 | 3.9 | 17.94  |
| 706 | 0.11  | 0.02 | 3.9 | 0.429  | 2013 | 0.84  | 0.02 | 3.9 | 3.276  |
| 707 | 1.844 | 0.02 | 3.9 | 7.192  | 2014 | 0.08  | 0.02 | 3.9 | 0.312  |
| 708 | 0.13  | 0.02 | 3.9 | 0.507  | 2015 | 0.14  | 0.02 | 3.9 | 0.546  |
| 709 | 0.14  | 0.02 | 3.9 | 0.546  | 2016 | 0.06  | 0.02 | 3.9 | 0.234  |
| 710 | 0.16  | 0.02 | 3.9 | 0.624  | 2017 | 1.363 | 0.02 | 3.9 | 5.316  |
| 711 | 0.818 | 0.02 | 3.9 | 3.19   | 2018 | 0.103 | 0.02 | 3.9 | 0.402  |
| 712 | 1.16  | 0.02 | 3.9 | 4.524  | 2019 | 0.14  | 0.02 | 3.9 | 0.546  |
| 713 | 0.305 | 0.02 | 3.9 | 1.19   | 2020 | 0.16  | 0.02 | 3.9 | 0.624  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 714 | 0.63  | 0.02 | 3.9 | 2.457  | 2021 | 0.083 | 0.02 | 3.9 | 0.324  |
| 715 | 2.155 | 0.02 | 3.9 | 8.404  | 2022 | 1.322 | 0.02 | 3.9 | 5.156  |
| 716 | 3.698 | 0.02 | 3.9 | 14.422 | 2023 | 5.284 | 0.02 | 3.9 | 20.608 |
| 717 | 3.198 | 0.02 | 3.9 | 12.472 | 2024 | 2.451 | 0.02 | 3.9 | 9.559  |
| 718 | 0.12  | 0.02 | 3.9 | 0.468  | 2025 | 0.14  | 0.02 | 3.9 | 0.546  |
| 719 | 3.489 | 0.02 | 3.9 | 13.607 | 2026 | 4.691 | 0.02 | 3.9 | 18.295 |
| 720 | 0.14  | 0.02 | 3.9 | 0.546  | 2027 | 0.14  | 0.02 | 3.9 | 0.546  |
| 721 | 0.11  | 0.02 | 3.9 | 0.429  | 2028 | 2.08  | 0.02 | 3.9 | 8.112  |
| 722 | 3.698 | 0.02 | 3.9 | 14.422 | 2029 | 5.284 | 0.02 | 3.9 | 20.608 |
| 723 | 0.13  | 0.02 | 3.9 | 0.507  | 2030 | 1.322 | 0.02 | 3.9 | 5.156  |
| 724 | 0.14  | 0.02 | 3.9 | 0.546  | 2031 | 0.098 | 0.02 | 3.9 | 0.382  |
| 725 | 0.11  | 0.02 | 3.9 | 0.429  | 2032 | 0.14  | 0.02 | 3.9 | 0.546  |
| 726 | 0.875 | 0.02 | 3.9 | 3.413  | 2033 | 0.16  | 0.02 | 3.9 | 0.624  |
| 727 | 0.14  | 0.02 | 3.9 | 0.546  | 2034 | 0.089 | 0.02 | 3.9 | 0.347  |
| 728 | 0.855 | 0.02 | 3.9 | 3.334  | 2035 | 1.363 | 0.02 | 3.9 | 5.316  |
| 729 | 2.16  | 0.02 | 3.9 | 8.424  | 2036 | 0.08  | 0.02 | 3.9 | 0.312  |
| 730 | 1.176 | 0.02 | 3.9 | 4.586  | 2037 | 0.14  | 0.02 | 3.9 | 0.546  |
| 731 | 0.165 | 0.02 | 3.9 | 0.644  | 2038 | 0.06  | 0.02 | 3.9 | 0.234  |
| 732 | 0.689 | 0.02 | 3.9 | 2.687  | 2039 | 0.84  | 0.02 | 3.9 | 3.276  |
| 733 | 2.345 | 0.02 | 3.9 | 9.146  | 2040 | 0.79  | 0.02 | 3.9 | 3.081  |
| 734 | 0.13  | 0.02 | 3.9 | 0.507  | 2041 | 0.57  | 0.02 | 3.9 | 2.223  |
| 735 | 0.14  | 0.02 | 3.9 | 0.546  | 2042 | 0.77  | 0.02 | 3.9 | 3.003  |
| 736 | 0.11  | 0.02 | 3.9 | 0.429  | 2043 | 0.55  | 0.02 | 3.9 | 2.145  |
| 737 | 0.585 | 0.02 | 3.9 | 2.282  | 2044 | 4.6   | 0.02 | 3.9 | 17.94  |
| 738 | 1.283 | 0.02 | 3.9 | 5.004  | 2045 | 0.84  | 0.02 | 3.9 | 3.276  |
| 739 | 0.14  | 0.02 | 3.9 | 0.546  | 2046 | 0.08  | 0.02 | 3.9 | 0.312  |
| 740 | 1.123 | 0.02 | 3.9 | 4.38   | 2047 | 0.14  | 0.02 | 3.9 | 0.546  |
| 741 | 2.379 | 0.02 | 3.9 | 9.278  | 2048 | 0.06  | 0.02 | 3.9 | 0.234  |
| 742 | 2.133 | 0.02 | 3.9 | 8.319  | 2049 | 1.363 | 0.02 | 3.9 | 5.316  |
| 743 | 2.379 | 0.02 | 3.9 | 9.278  | 2050 | 0.103 | 0.02 | 3.9 | 0.402  |
| 744 | 0.13  | 0.02 | 3.9 | 0.507  | 2051 | 0.14  | 0.02 | 3.9 | 0.546  |
| 745 | 0.14  | 0.02 | 3.9 | 0.546  | 2052 | 0.16  | 0.02 | 3.9 | 0.624  |
| 746 | 0.4   | 0.02 | 3.9 | 1.56   | 2053 | 0.085 | 0.02 | 3.9 | 0.332  |
| 747 | 0.14  | 0.02 | 3.9 | 0.546  | 2054 | 1.322 | 0.02 | 3.9 | 5.156  |
| 748 | 0.11  | 0.02 | 3.9 | 0.429  | 2055 | 5.284 | 0.02 | 3.9 | 20.608 |
| 749 | 2.379 | 0.02 | 3.9 | 9.278  | 2056 | 2.329 | 0.02 | 3.9 | 9.083  |
| 750 | 1.719 | 0.02 | 3.9 | 6.704  | 2057 | 0.14  | 0.02 | 3.9 | 0.546  |
| 751 | 2.379 | 0.02 | 3.9 | 9.278  | 2058 | 4.722 | 0.02 | 3.9 | 18.416 |
| 752 | 0.607 | 0.02 | 3.9 | 2.367  | 2059 | 0.14  | 0.02 | 3.9 | 0.546  |
| 753 | 0.16  | 0.02 | 3.9 | 0.624  | 2060 | 2.233 | 0.02 | 3.9 | 8.709  |
| 754 | 0.877 | 0.02 | 3.9 | 3.42   | 2061 | 5.284 | 0.02 | 3.9 | 20.608 |
| 755 | 0.14  | 0.02 | 3.9 | 0.546  | 2062 | 1.322 | 0.02 | 3.9 | 5.156  |
| 756 | 0.13  | 0.02 | 3.9 | 0.507  | 2063 | 0.098 | 0.02 | 3.9 | 0.382  |
| 757 | 2.379 | 0.02 | 3.9 | 9.278  | 2064 | 0.14  | 0.02 | 3.9 | 0.546  |
| 758 | 1.606 | 0.02 | 3.9 | 6.263  | 2065 | 0.16  | 0.02 | 3.9 | 0.624  |

|     |       |      |     |        |      |       |      |     |        |
|-----|-------|------|-----|--------|------|-------|------|-----|--------|
| 759 | 1.734 | 0.02 | 3.9 | 6.763  | 2066 | 0.089 | 0.02 | 3.9 | 0.347  |
| 760 | 0.16  | 0.02 | 3.9 | 0.624  | 2067 | 1.363 | 0.02 | 3.9 | 5.316  |
| 761 | 0.649 | 0.02 | 3.9 | 2.531  | 2068 | 0.08  | 0.02 | 3.9 | 0.312  |
| 762 | 0.796 | 0.02 | 3.9 | 3.104  | 2069 | 0.14  | 0.02 | 3.9 | 0.546  |
| 763 | 0.14  | 0.02 | 3.9 | 0.546  | 2070 | 0.06  | 0.02 | 3.9 | 0.234  |
| 764 | 4.402 | 0.02 | 3.9 | 17.168 | 2071 | 0.84  | 0.02 | 3.9 | 3.276  |
| 765 | 3.979 | 0.02 | 3.9 | 15.518 | 2072 | 0.79  | 0.02 | 3.9 | 3.081  |
| 766 | 0.14  | 0.02 | 3.9 | 0.546  | 2073 | 0.57  | 0.02 | 3.9 | 2.223  |
| 767 | 0.108 | 0.02 | 3.9 | 0.421  | 2074 | 0.77  | 0.02 | 3.9 | 3.003  |
| 768 | 5.187 | 0.02 | 3.9 | 20.229 | 2075 | 0.55  | 0.02 | 3.9 | 2.145  |
| 769 | 0.128 | 0.02 | 3.9 | 0.499  | 2076 | 0.32  | 0.02 | 3.9 | 1.248  |
| 770 | 0.14  | 0.02 | 3.9 | 0.546  | 2077 | 0.14  | 0.02 | 3.9 | 0.546  |
| 771 | 0.268 | 0.02 | 3.9 | 1.045  | 2078 | 0.06  | 0.02 | 3.9 | 0.234  |
| 772 | 0.472 | 0.02 | 3.9 | 1.841  | 2079 | 5.18  | 0.02 | 3.9 | 20.202 |
| 773 | 3.231 | 0.02 | 3.9 | 12.601 | 2080 | 0.165 | 0.02 | 3.9 | 0.644  |
| 774 | 0.294 | 0.02 | 3.9 | 1.147  | 2081 | 1.47  | 0.02 | 3.9 | 5.733  |
| 775 | 0.439 | 0.02 | 3.9 | 1.712  | 2082 | 0.145 | 0.02 | 3.9 | 0.566  |
| 776 | 0.14  | 0.02 | 3.9 | 0.546  | 2083 | 0.874 | 0.02 | 3.9 | 3.409  |
| 777 | 0.279 | 0.02 | 3.9 | 1.088  | 2084 | 0.251 | 0.02 | 3.9 | 0.979  |
| 778 | 3.25  | 0.02 | 3.9 | 12.675 | 2085 | 0.14  | 0.02 | 3.9 | 0.546  |
| 779 | 0.14  | 0.02 | 3.9 | 0.546  | 2086 | 0.639 | 0.02 | 3.9 | 2.492  |
| 780 | 0.109 | 0.02 | 3.9 | 0.425  | 2087 | 0.14  | 0.02 | 3.9 | 0.546  |
| 781 | 3.231 | 0.02 | 3.9 | 12.601 | 2088 | 0.227 | 0.02 | 3.9 | 0.885  |
| 782 | 1.864 | 0.02 | 3.9 | 7.27   | 2089 | 0.874 | 0.02 | 3.9 | 3.409  |
| 783 | 3.231 | 0.02 | 3.9 | 12.601 | 2090 | 0.215 | 0.02 | 3.9 | 0.839  |
| 784 | 0.875 | 0.02 | 3.9 | 3.413  | 2091 | 1.47  | 0.02 | 3.9 | 5.733  |
| 785 | 0.14  | 0.02 | 3.9 | 0.546  | 2092 | 0.195 | 0.02 | 3.9 | 0.76   |
| 786 | 0.855 | 0.02 | 3.9 | 3.334  | 2093 | 5.18  | 0.02 | 3.9 | 20.202 |
| 787 | 0.299 | 0.02 | 3.9 | 1.166  | 2094 | 0.08  | 0.02 | 3.9 | 0.312  |
| 788 | 0.124 | 0.02 | 3.9 | 0.484  | 2095 | 0.12  | 0.02 | 3.9 | 0.468  |
| 789 | 4.986 | 0.02 | 3.9 | 19.445 | 2096 | 0.86  | 0.02 | 3.9 | 3.354  |
| 790 | 0.074 | 0.02 | 3.9 | 0.289  | 2097 | 0.08  | 0.02 | 3.9 | 0.312  |
| 791 | 0.14  | 0.02 | 3.9 | 0.546  | 2098 | 0.14  | 0.02 | 3.9 | 0.546  |
| 792 | 0.401 | 0.02 | 3.9 | 1.564  | 2099 | 0.06  | 0.02 | 3.9 | 0.234  |
| 793 | 0.14  | 0.02 | 3.9 | 0.546  | 2100 | 1.363 | 0.02 | 3.9 | 5.316  |
| 794 | 0.162 | 0.02 | 3.9 | 0.632  | 2101 | 0.109 | 0.02 | 3.9 | 0.425  |
| 795 | 1.632 | 0.02 | 3.9 | 6.365  | 2102 | 0.14  | 0.02 | 3.9 | 0.546  |
| 796 | 0.53  | 0.02 | 3.9 | 2.067  | 2103 | 0.098 | 0.02 | 3.9 | 0.382  |
| 797 | 0.67  | 0.02 | 3.9 | 2.613  | 2104 | 0.14  | 0.02 | 3.9 | 0.546  |
| 798 | 0.51  | 0.02 | 3.9 | 1.989  | 2105 | 1.322 | 0.02 | 3.9 | 5.156  |
| 799 | 2.595 | 0.02 | 3.9 | 10.121 | 2106 | 5.284 | 0.02 | 3.9 | 20.608 |
| 800 | 0.421 | 0.02 | 3.9 | 1.642  | 2107 | 2.333 | 0.02 | 3.9 | 9.099  |
| 801 | 0.079 | 0.02 | 3.9 | 0.308  | 2108 | 0.14  | 0.02 | 3.9 | 0.546  |
| 802 | 0.12  | 0.02 | 3.9 | 0.468  | 2109 | 4.924 | 0.02 | 3.9 | 19.204 |
| 803 | 0.14  | 0.02 | 3.9 | 0.546  | 2110 | 0.14  | 0.02 | 3.9 | 0.546  |

|     |        |      |     |        |      |       |      |     |        |
|-----|--------|------|-----|--------|------|-------|------|-----|--------|
| 804 | 0.162  | 0.02 | 3.9 | 0.632  | 2111 | 1.911 | 0.02 | 3.9 | 7.453  |
| 805 | 0.524  | 0.02 | 3.9 | 2.044  | 2112 | 0.52  | 0.02 | 3.9 | 2.028  |
| 806 | 0.14   | 0.02 | 3.9 | 0.546  | 2113 | 0.5   | 0.02 | 3.9 | 1.95   |
| 807 | 0.244  | 0.02 | 3.9 | 0.952  | 2114 | 4.764 | 0.02 | 3.9 | 18.58  |
| 808 | 7.843  | 0.02 | 3.9 | 30.588 | 2115 | 1.322 | 0.02 | 3.9 | 5.156  |
| 809 | 3.725  | 0.02 | 3.9 | 14.528 | 2116 | 0.103 | 0.02 | 3.9 | 0.402  |
| 810 | 12.351 | 0.02 | 3.9 | 48.169 | 2117 | 0.14  | 0.02 | 3.9 | 0.546  |
| 811 | 0.14   | 0.02 | 3.9 | 0.546  | 2118 | 0.16  | 0.02 | 3.9 | 0.624  |
| 812 | 0.37   | 0.02 | 3.9 | 1.443  | 2119 | 0.083 | 0.02 | 3.9 | 0.324  |
| 813 | 1.945  | 0.02 | 3.9 | 7.585  | 2120 | 1.363 | 0.02 | 3.9 | 5.316  |
| 814 | 0.14   | 0.02 | 3.9 | 0.546  | 2121 | 0.08  | 0.02 | 3.9 | 0.312  |
| 815 | 1.925  | 0.02 | 3.9 | 7.508  | 2122 | 0.14  | 0.02 | 3.9 | 0.546  |
| 816 | 3.024  | 0.02 | 3.9 | 11.794 | 2123 | 0.06  | 0.02 | 3.9 | 0.234  |
| 817 | 0.53   | 0.02 | 3.9 | 2.067  | 2124 | 0.86  | 0.02 | 3.9 | 3.354  |
| 818 | 1.18   | 0.02 | 3.9 | 4.602  | 2125 | 4.56  | 0.02 | 3.9 | 17.784 |
| 819 | 2.505  | 0.02 | 3.9 | 9.769  | 2126 | 0.79  | 0.02 | 3.9 | 3.081  |
| 820 | 4.224  | 0.02 | 3.9 | 16.474 | 2127 | 0.569 | 0.02 | 3.9 | 2.219  |
| 821 | 0.13   | 0.02 | 3.9 | 0.507  | 2128 | 0.769 | 0.02 | 3.9 | 2.999  |
| 822 | 0.14   | 0.02 | 3.9 | 0.546  | 2129 | 0.55  | 0.02 | 3.9 | 2.145  |
| 823 | 0.4    | 0.02 | 3.9 | 1.56   | 2130 | 0.32  | 0.02 | 3.9 | 1.248  |
| 824 | 0.14   | 0.02 | 3.9 | 0.546  | 2131 | 0.14  | 0.02 | 3.9 | 0.546  |
| 825 | 0.11   | 0.02 | 3.9 | 0.429  | 2132 | 0.06  | 0.02 | 3.9 | 0.234  |
| 826 | 4.384  | 0.02 | 3.9 | 17.098 | 2133 | 6.08  | 0.02 | 3.9 | 23.712 |
| 827 | 3.175  | 0.02 | 3.9 | 12.382 | 2134 | 0.39  | 0.02 | 3.9 | 1.521  |
| 828 | 6.547  | 0.02 | 3.9 | 25.533 | 2135 | 1.444 | 0.02 | 3.9 | 5.632  |
| 829 | 0.73   | 0.02 | 3.9 | 2.847  | 2136 | 0.05  | 0.02 | 3.9 | 0.195  |
| 830 | 0.71   | 0.02 | 3.9 | 2.769  | 2137 | 0.156 | 0.02 | 3.9 | 0.608  |
| 831 | 2.994  | 0.02 | 3.9 | 11.677 | 2138 | 0.709 | 0.02 | 3.9 | 2.765  |
| 832 | 7.983  | 0.02 | 3.9 | 31.134 | 2139 | 0.156 | 0.02 | 3.9 | 0.608  |
| 833 | 0.1    | 0.02 | 3.9 | 0.39   | 2140 | 1.464 | 0.02 | 3.9 | 5.71   |
| 834 | 0.12   | 0.02 | 3.9 | 0.468  | 2141 | 0.07  | 0.02 | 3.9 | 0.273  |
| 835 | 0.16   | 0.02 | 3.9 | 0.624  | 2142 | 6.08  | 0.02 | 3.9 | 23.712 |
| 836 | 4.145  | 0.02 | 3.9 | 16.165 | 2143 | 0.08  | 0.02 | 3.9 | 0.312  |
| 837 | 1.758  | 0.02 | 3.9 | 6.856  | 2144 | 0.12  | 0.02 | 3.9 | 0.468  |
| 838 | 0.057  | 0.02 | 3.9 | 0.222  | 2145 | 4.58  | 0.02 | 3.9 | 17.862 |
| 839 | 0.14   | 0.02 | 3.9 | 0.546  | 2146 | 0.86  | 0.02 | 3.9 | 3.354  |
| 840 | 0.03   | 0.02 | 3.9 | 0.117  | 2147 | 0.08  | 0.02 | 3.9 | 0.312  |
| 841 | 1.043  | 0.02 | 3.9 | 4.068  | 2148 | 0.14  | 0.02 | 3.9 | 0.546  |
| 842 | 0.14   | 0.02 | 3.9 | 0.546  | 2149 | 0.06  | 0.02 | 3.9 | 0.234  |
| 843 | 0.16   | 0.02 | 3.9 | 0.624  | 2150 | 1.363 | 0.02 | 3.9 | 5.316  |
| 844 | 0.245  | 0.02 | 3.9 | 0.956  | 2151 | 0.103 | 0.02 | 3.9 | 0.402  |
| 845 | 2.307  | 0.02 | 3.9 | 8.997  | 2152 | 0.14  | 0.02 | 3.9 | 0.546  |
| 846 | 1.38   | 0.02 | 3.9 | 5.382  | 2153 | 0.16  | 0.02 | 3.9 | 0.624  |
| 847 | 0.284  | 0.02 | 3.9 | 1.108  | 2154 | 0.083 | 0.02 | 3.9 | 0.324  |
| 848 | 0.101  | 0.02 | 3.9 | 0.394  | 2155 | 1.322 | 0.02 | 3.9 | 5.156  |

|     |        |      |     |        |      |       |      |     |        |
|-----|--------|------|-----|--------|------|-------|------|-----|--------|
| 849 | 0.14   | 0.02 | 3.9 | 0.546  | 2156 | 5.284 | 0.02 | 3.9 | 20.608 |
| 850 | 0.081  | 0.02 | 3.9 | 0.316  | 2157 | 2.296 | 0.02 | 3.9 | 8.954  |
| 851 | 1.394  | 0.02 | 3.9 | 5.437  | 2158 | 0.14  | 0.02 | 3.9 | 0.546  |
| 852 | 0.14   | 0.02 | 3.9 | 0.546  | 2159 | 4.576 | 0.02 | 3.9 | 17.846 |
| 853 | 1.676  | 0.02 | 3.9 | 6.536  | 2160 | 0.14  | 0.02 | 3.9 | 0.546  |
| 854 | 2.14   | 0.02 | 3.9 | 8.346  | 2161 | 1.6   | 0.02 | 3.9 | 6.24   |
| 855 | 0.48   | 0.02 | 3.9 | 1.872  | 2162 | 0.52  | 0.02 | 3.9 | 2.028  |
| 856 | 0.67   | 0.02 | 3.9 | 2.613  | 2163 | 0.5   | 0.02 | 3.9 | 1.95   |
| 857 | 0.3    | 0.02 | 3.9 | 1.17   | 2164 | 4.764 | 0.02 | 3.9 | 18.58  |
| 858 | 1.465  | 0.02 | 3.9 | 5.714  | 2165 | 1.322 | 0.02 | 3.9 | 5.156  |
| 859 | 0.12   | 0.02 | 3.9 | 0.468  | 2166 | 0.098 | 0.02 | 3.9 | 0.382  |
| 860 | 1.518  | 0.02 | 3.9 | 5.92   | 2167 | 0.14  | 0.02 | 3.9 | 0.546  |
| 861 | 0.031  | 0.02 | 3.9 | 0.121  | 2168 | 0.16  | 0.02 | 3.9 | 0.624  |
| 862 | 0.152  | 0.02 | 3.9 | 0.593  | 2169 | 0.089 | 0.02 | 3.9 | 0.347  |
| 863 | 0.16   | 0.02 | 3.9 | 0.624  | 2170 | 1.363 | 0.02 | 3.9 | 5.316  |
| 864 | 7.24   | 0.02 | 3.9 | 28.236 | 2171 | 0.08  | 0.02 | 3.9 | 0.312  |
| 865 | 0.14   | 0.02 | 3.9 | 0.546  | 2172 | 0.14  | 0.02 | 3.9 | 0.546  |
| 866 | 0.483  | 0.02 | 3.9 | 1.884  | 2173 | 0.06  | 0.02 | 3.9 | 0.234  |
| 867 | 3.698  | 0.02 | 3.9 | 14.422 | 2174 | 0.84  | 0.02 | 3.9 | 3.276  |
| 868 | 0.203  | 0.02 | 3.9 | 0.792  | 2175 | 0.25  | 0.02 | 3.9 | 0.975  |
| 869 | 0.14   | 0.02 | 3.9 | 0.546  | 2176 | 0.94  | 0.02 | 3.9 | 3.666  |
| 870 | 0.473  | 0.02 | 3.9 | 1.845  | 2177 | 0.77  | 0.02 | 3.9 | 3.003  |
| 871 | 0.14   | 0.02 | 3.9 | 0.546  | 2178 | 0.57  | 0.02 | 3.9 | 2.223  |
| 872 | 0.13   | 0.02 | 3.9 | 0.507  | 2179 | 0.84  | 0.02 | 3.9 | 3.276  |
| 873 | 3.697  | 0.02 | 3.9 | 14.418 | 2180 | 0.97  | 0.02 | 3.9 | 3.783  |
| 874 | 4.76   | 0.02 | 3.9 | 18.564 | 2181 | 0.34  | 0.02 | 3.9 | 1.326  |
| 875 | 0.07   | 0.02 | 3.9 | 0.273  | 2182 | 0.14  | 0.02 | 3.9 | 0.546  |
| 876 | 0.14   | 0.02 | 3.9 | 0.546  | 2183 | 0.32  | 0.02 | 3.9 | 1.248  |
| 877 | 0.05   | 0.02 | 3.9 | 0.195  | 2184 | 1.58  | 0.02 | 3.9 | 6.162  |
| 878 | 1.657  | 0.02 | 3.9 | 6.462  | 2185 | 0.41  | 0.02 | 3.9 | 1.599  |
| 879 | 0.16   | 0.02 | 3.9 | 0.624  | 2186 | 0.62  | 0.02 | 3.9 | 2.418  |
| 880 | 0.288  | 0.02 | 3.9 | 1.123  | 2187 | 0.39  | 0.02 | 3.9 | 1.521  |
| 881 | 19.722 | 0.02 | 3.9 | 76.916 | 2188 | 4.14  | 0.02 | 3.9 | 16.146 |
| 882 | 0.14   | 0.02 | 3.9 | 0.546  | 2189 | 0.41  | 0.02 | 3.9 | 1.599  |
| 883 | 0.512  | 0.02 | 3.9 | 1.997  | 2190 | 1.164 | 0.02 | 3.9 | 4.54   |
| 884 | 5.325  | 0.02 | 3.9 | 20.768 | 2191 | 0.134 | 0.02 | 3.9 | 0.523  |
| 885 | 0.14   | 0.02 | 3.9 | 0.546  | 2192 | 0.14  | 0.02 | 3.9 | 0.546  |
| 886 | 2.368  | 0.02 | 3.9 | 9.235  | 2193 | 9.758 | 0.02 | 3.9 | 38.056 |
| 887 | 0.154  | 0.02 | 3.9 | 0.601  | 2194 | 4.149 | 0.02 | 3.9 | 16.181 |
| 888 | 0.16   | 0.02 | 3.9 | 0.624  | 2195 | 0.16  | 0.02 | 3.9 | 0.624  |
| 889 | 0.11   | 0.02 | 3.9 | 0.429  | 2196 | 0.147 | 0.02 | 3.9 | 0.573  |
| 890 | 2.777  | 0.02 | 3.9 | 10.83  | 2197 | 0.738 | 0.02 | 3.9 | 2.878  |
| 891 | 3.198  | 0.02 | 3.9 | 12.472 | 2198 | 0.492 | 0.02 | 3.9 | 1.919  |
| 892 | 1.817  | 0.02 | 3.9 | 7.086  | 2199 | 0.27  | 0.02 | 3.9 | 1.053  |
| 893 | 1.48   | 0.02 | 3.9 | 5.772  | 2200 | 0.29  | 0.02 | 3.9 | 1.131  |

|     |        |      |     |        |      |       |      |     |        |
|-----|--------|------|-----|--------|------|-------|------|-----|--------|
| 894 | 0.94   | 0.02 | 3.9 | 3.666  | 2201 | 0.342 | 0.02 | 3.9 | 1.334  |
| 895 | 0.628  | 0.02 | 3.9 | 2.449  | 2202 | 2.355 | 0.02 | 3.9 | 9.185  |
| 896 | 0.14   | 0.02 | 3.9 | 0.546  | 2203 | 0.11  | 0.02 | 3.9 | 0.429  |
| 897 | 0.768  | 0.02 | 3.9 | 2.995  | 2204 | 1.752 | 0.02 | 3.9 | 6.833  |
| 898 | 0.46   | 0.02 | 3.9 | 1.794  | 2205 | 1.795 | 0.02 | 3.9 | 7.001  |
| 899 | 1.32   | 0.02 | 3.9 | 5.148  | 2206 | 0.14  | 0.02 | 3.9 | 0.546  |
| 900 | 2.868  | 0.02 | 3.9 | 11.185 | 2207 | 1.635 | 0.02 | 3.9 | 6.377  |
| 901 | 0.14   | 0.02 | 3.9 | 0.546  | 2208 | 7.358 | 0.02 | 3.9 | 28.696 |
| 902 | 5.305  | 0.02 | 3.9 | 20.69  | 2209 | 3.445 | 0.02 | 3.9 | 13.435 |
| 903 | 15.651 | 0.02 | 3.9 | 61.039 | 2210 | 0.534 | 0.02 | 3.9 | 2.083  |
| 904 | 0.349  | 0.02 | 3.9 | 1.361  | 2211 | 0.07  | 0.02 | 3.9 | 0.273  |
| 905 | 0.16   | 0.02 | 3.9 | 0.624  | 2212 | 4.79  | 0.02 | 3.9 | 18.681 |
| 906 | 0.797  | 0.02 | 3.9 | 3.108  | 2213 | 0.09  | 0.02 | 3.9 | 0.351  |
| 907 | 0.16   | 0.02 | 3.9 | 0.624  | 2214 | 0.62  | 0.02 | 3.9 | 2.418  |
| 908 | 0.109  | 0.02 | 3.9 | 0.425  | 2215 | 0.07  | 0.02 | 3.9 | 0.273  |
| 909 | 0.88   | 0.02 | 3.9 | 3.432  | 2216 | 1.393 | 0.02 | 3.9 | 5.433  |
| 910 | 0.12   | 0.02 | 3.9 | 0.468  | 2217 | 0.32  | 0.02 | 3.9 | 1.248  |
| 911 | 6.311  | 0.02 | 3.9 | 24.613 | 2218 | 0.14  | 0.02 | 3.9 | 0.546  |
| 912 | 0.68   | 0.02 | 3.9 | 2.652  | 2219 | 0.3   | 0.02 | 3.9 | 1.17   |
| 913 | 1.32   | 0.02 | 3.9 | 5.148  | 2220 | 1.406 | 0.02 | 3.9 | 5.483  |
| 914 | 0.66   | 0.02 | 3.9 | 2.574  | 2221 | 0.44  | 0.02 | 3.9 | 1.716  |
| 915 | 0.824  | 0.02 | 3.9 | 3.214  | 2222 | 0.67  | 0.02 | 3.9 | 2.613  |
| 916 | 4.098  | 0.02 | 3.9 | 15.982 | 2223 | 0.42  | 0.02 | 3.9 | 1.638  |
| 917 | 4.077  | 0.02 | 3.9 | 15.9   | 2224 | 0.59  | 0.02 | 3.9 | 2.301  |
| 918 | 0.16   | 0.02 | 3.9 | 0.624  | 2225 | 0.49  | 0.02 | 3.9 | 1.911  |
| 919 | 0.46   | 0.02 | 3.9 | 1.794  | 2226 | 0.94  | 0.02 | 3.9 | 3.666  |
| 920 | 1.413  | 0.02 | 3.9 | 5.511  | 2227 | 0.47  | 0.02 | 3.9 | 1.833  |
| 921 | 0.12   | 0.02 | 3.9 | 0.468  | 2228 | 0.92  | 0.02 | 3.9 | 3.588  |
| 922 | 1.413  | 0.02 | 3.9 | 5.511  | 2229 | 1.06  | 0.02 | 1.7 | 1.802  |
| 923 | 3.457  | 0.02 | 3.9 | 13.482 | 2230 | 1.26  | 0.02 | 1.7 | 2.142  |
| 924 | 3.719  | 0.02 | 3.9 | 14.504 | 2231 | 1.26  | 0.02 | 1.7 | 2.142  |
| 925 | 3.457  | 0.02 | 3.9 | 13.482 | 2232 | 1.26  | 0.02 | 1.7 | 2.142  |
| 926 | 1.046  | 0.02 | 3.9 | 4.079  | 2233 | 1.26  | 0.02 | 1.7 | 2.142  |
| 927 | 0.14   | 0.02 | 3.9 | 0.546  | 2234 | 1.06  | 0.02 | 1.7 | 1.802  |
| 928 | 1.026  | 0.02 | 3.9 | 4.001  | 2235 | 1.26  | 0.02 | 1.7 | 2.142  |
| 929 | 0.48   | 0.02 | 3.9 | 1.872  | 2236 | 1.26  | 0.02 | 1.7 | 2.142  |
| 930 | 0.14   | 0.02 | 3.9 | 0.546  | 2237 | 1.26  | 0.02 | 1.7 | 2.142  |
| 931 | 5.432  | 0.02 | 3.9 | 21.185 | 2238 | 1.26  | 0.02 | 1.7 | 2.142  |
| 932 | 1.181  | 0.02 | 3.9 | 4.606  | 2239 | 1.26  | 0.02 | 1.7 | 2.142  |
| 933 | 0.82   | 0.02 | 3.9 | 3.198  | 2240 | 1.26  | 0.02 | 1.7 | 2.142  |
| 934 | 1.161  | 0.02 | 3.9 | 4.528  | 2241 | 1.06  | 0.02 | 1.7 | 1.802  |
| 935 | 0.214  | 0.02 | 3.9 | 0.835  | 2242 | 1.662 | 0.02 | 1.7 | 2.825  |
| 936 | 0.181  | 0.02 | 3.9 | 0.706  | 2243 | 1.662 | 0.02 | 1.7 | 2.825  |
| 937 | 0.14   | 0.02 | 3.9 | 0.546  | 2244 | 1.062 | 0.02 | 1.7 | 1.805  |
| 938 | 0.021  | 0.02 | 3.9 | 0.082  | 2245 | 1.062 | 0.02 | 1.7 | 1.805  |

|     |       |      |     |        |      |       |      |     |       |
|-----|-------|------|-----|--------|------|-------|------|-----|-------|
| 939 | 2.089 | 0.02 | 3.9 | 8.147  | 2246 | 0.86  | 0.02 | 1.7 | 1.462 |
| 940 | 2.114 | 0.02 | 3.9 | 8.245  | 2247 | 0.86  | 0.02 | 1.7 | 1.462 |
| 941 | 2.089 | 0.02 | 3.9 | 8.147  | 2248 | 1.06  | 0.02 | 1.7 | 1.802 |
| 942 | 1.213 | 0.02 | 3.9 | 4.731  | 2249 | 1.26  | 0.02 | 1.7 | 2.142 |
| 943 | 0.14  | 0.02 | 3.9 | 0.546  | 2250 | 1.26  | 0.02 | 1.7 | 2.142 |
| 944 | 0.248 | 0.02 | 3.9 | 0.967  | 2251 | 1.261 | 0.02 | 1.7 | 2.144 |
| 945 | 0.135 | 0.02 | 3.9 | 0.527  | 2252 | 1.261 | 0.02 | 1.7 | 2.144 |
| 946 | 0.14  | 0.02 | 3.9 | 0.546  | 2253 | 1.26  | 0.02 | 1.7 | 2.142 |
| 947 | 0.115 | 0.02 | 3.9 | 0.449  | 2254 | 1.26  | 0.02 | 1.7 | 2.142 |
| 948 | 0.785 | 0.02 | 3.9 | 3.062  | 2255 | 1.082 | 0.02 | 1.7 | 1.839 |
| 949 | 3.301 | 0.02 | 3.9 | 12.874 | 2256 | 0.86  | 0.02 | 1.7 | 1.462 |
| 950 | 1.676 | 0.02 | 3.9 | 6.536  | 2257 | 0.86  | 0.02 | 1.7 | 1.462 |
| 951 | 1.879 | 0.02 | 3.9 | 7.328  | 2258 | 0.86  | 0.02 | 1.7 | 1.462 |
| 952 | 0.891 | 0.02 | 3.9 | 3.475  | 2259 | 0.96  | 0.02 | 1.7 | 1.632 |
| 953 | 0.408 | 0.02 | 3.9 | 1.591  | 2260 | 0.96  | 0.02 | 1.7 | 1.632 |
| 954 | 0.14  | 0.02 | 3.9 | 0.546  | 2261 | 0.86  | 0.02 | 1.7 | 1.462 |
| 955 | 0.248 | 0.02 | 3.9 | 0.967  | 2262 | 0.96  | 0.02 | 1.7 | 1.632 |
| 956 | 2.059 | 0.02 | 3.9 | 8.03   | 2263 | 0.96  | 0.02 | 1.7 | 1.632 |
| 957 | 0.14  | 0.02 | 3.9 | 0.546  | 2264 | 0.86  | 0.02 | 1.7 | 1.462 |
| 958 | 1.148 | 0.02 | 3.9 | 4.477  | 2265 | 0.86  | 0.02 | 1.7 | 1.462 |
| 959 | 1.879 | 0.02 | 3.9 | 7.328  | 2266 | 0.86  | 0.02 | 1.7 | 1.462 |
| 960 | 2.26  | 0.02 | 3.9 | 8.814  | 2267 | 0.86  | 0.02 | 1.7 | 1.462 |
| 961 | 1.879 | 0.02 | 3.9 | 7.328  | 2268 | 0.86  | 0.02 | 1.7 | 1.462 |
| 962 | 0.13  | 0.02 | 3.9 | 0.507  | 2269 | 0.86  | 0.02 | 1.7 | 1.462 |
| 963 | 0.14  | 0.02 | 3.9 | 0.546  | 2270 | 1.26  | 0.02 | 1.7 | 2.142 |
| 964 | 0.27  | 0.02 | 3.9 | 1.053  | 2271 | 1.26  | 0.02 | 1.7 | 2.142 |
| 965 | 2.019 | 0.02 | 3.9 | 7.874  | 2272 | 0.86  | 0.02 | 1.7 | 1.462 |
| 966 | 6.019 | 0.02 | 3.9 | 23.474 | 2273 | 0.86  | 0.02 | 1.7 | 1.462 |
| 967 | 2.745 | 0.02 | 3.9 | 10.706 | 2274 | 1.26  | 0.02 | 1.7 | 2.142 |
| 968 | 0.86  | 0.02 | 3.9 | 3.354  | 2275 | 1.26  | 0.02 | 1.7 | 2.142 |
| 969 | 0.88  | 0.02 | 3.9 | 3.432  | 2276 | 0.96  | 0.02 | 1.7 | 1.632 |
| 970 | 3.864 | 0.02 | 3.9 | 15.07  | 2277 | 0.96  | 0.02 | 1.7 | 1.632 |
| 971 | 0.18  | 0.02 | 3.9 | 0.702  | 2278 | 0.86  | 0.02 | 1.7 | 1.462 |
| 972 | 0.86  | 0.02 | 3.9 | 3.354  | 2279 | 0.86  | 0.02 | 1.7 | 1.462 |
| 973 | 3.328 | 0.02 | 3.9 | 12.979 | 2280 | 0.86  | 0.02 | 1.7 | 1.462 |
| 974 | 0.52  | 0.02 | 3.9 | 2.028  | 2281 | 0.86  | 0.02 | 1.7 | 1.462 |
| 975 | 0.864 | 0.02 | 3.9 | 3.37   | 2282 | 0.96  | 0.02 | 1.7 | 1.632 |
| 976 | 0.5   | 0.02 | 3.9 | 1.95   | 2283 | 0.957 | 0.02 | 1.7 | 1.627 |
| 977 | 3.308 | 0.02 | 3.9 | 12.901 | 2284 | 0.86  | 0.02 | 1.7 | 1.462 |
| 978 | 0.659 | 0.02 | 3.9 | 2.57   | 2285 | 0.86  | 0.02 | 1.7 | 1.462 |
| 979 | 0.44  | 0.02 | 3.9 | 1.716  | 2286 | 0.86  | 0.02 | 1.7 | 1.462 |
| 980 | 0.659 | 0.02 | 3.9 | 2.57   | 2287 | 0.86  | 0.02 | 1.7 | 1.462 |
| 981 | 7.02  | 0.02 | 3.9 | 27.378 | 2288 | 0.86  | 0.02 | 1.7 | 1.462 |
| 982 | 0.28  | 0.02 | 3.9 | 1.092  | 2289 | 0.86  | 0.02 | 1.7 | 1.462 |
| 983 | 0.66  | 0.02 | 3.9 | 2.574  | 2290 | 0.86  | 0.02 | 1.7 | 1.462 |



|      |        |      |     |        |      |       |       |     |       |
|------|--------|------|-----|--------|------|-------|-------|-----|-------|
| 984  | 0.44   | 0.02 | 3.9 | 1.716  | 2291 | 0.86  | 0.02  | 1.7 | 1.462 |
| 985  | 0.664  | 0.02 | 3.9 | 2.59   | 2292 | 1.062 | 0.02  | 1.7 | 1.805 |
| 986  | 0.7    | 0.02 | 3.9 | 2.73   | 2293 | 1.062 | 0.02  | 1.7 | 1.805 |
| 988  | 0.18   | 0.02 | 3.9 | 0.702  | 2295 | 1.26  | 0.02  | 1.7 | 2.142 |
| 989  | 0.86   | 0.02 | 3.9 | 3.354  | 2296 | 1.26  | 0.02  | 1.7 | 2.142 |
| 990  | 5.444  | 0.02 | 3.9 | 21.232 | 2297 | 1.26  | 0.02  | 1.7 | 2.142 |
| 991  | 0.18   | 0.02 | 3.9 | 0.702  | 2298 | 1.26  | 0.02  | 1.7 | 2.142 |
| 992  | 1.43   | 0.02 | 3.9 | 5.577  | 2299 | 1.26  | 0.02  | 1.7 | 2.142 |
| 993  | 0.544  | 0.02 | 3.9 | 2.122  | 2300 | 1.26  | 0.02  | 1.7 | 2.142 |
| 994  | 0.66   | 0.02 | 3.9 | 2.574  | 2301 | 1.26  | 0.02  | 1.7 | 2.142 |
| 995  | 0.7    | 0.02 | 3.9 | 2.73   | 2302 | 1.062 | 0.014 | 1.7 | 1.805 |
| 996  | 4.69   | 0.02 | 3.9 | 18.291 | 2303 | 1.062 | 0.02  | 1.7 | 1.805 |
| 997  | 0.176  | 0.02 | 3.9 | 0.686  | 2304 | 1.145 | 0.02  | 1.7 | 1.946 |
| 998  | 1.161  | 0.02 | 3.9 | 4.528  | 2305 | 1.102 | 0.02  | 1.7 | 1.873 |
| 999  | 12.267 | 0.02 | 3.9 | 47.841 | 2306 | 1.3   | 0.02  | 1.7 | 2.21  |
| 1000 | 12.267 | 0.02 | 3.9 | 47.841 | 2307 | 1.28  | 0.02  | 1.7 | 2.176 |
| 1001 | 0.12   | 0.02 | 3.9 | 0.468  | 2308 | 1.28  | 0.02  | 1.7 | 2.176 |
| 1002 | 0.12   | 0.02 | 3.9 | 0.468  | 2309 | 1.28  | 0.02  | 1.7 | 2.176 |
| 1003 | 0.89   | 0.02 | 3.9 | 3.471  | 2310 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1004 | 0.87   | 0.02 | 3.9 | 3.393  | 2311 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1005 | 0.869  | 0.02 | 3.9 | 3.389  | 2312 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1006 | 0.85   | 0.02 | 3.9 | 3.315  | 2313 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1007 | 1.08   | 0.02 | 3.9 | 4.212  | 2314 | 1.062 | 0.02  | 1.7 | 1.805 |
| 1008 | 1      | 0.02 | 3.9 | 3.9    | 2315 | 1.062 | 0.02  | 1.7 | 1.805 |
| 1009 | 1.06   | 0.02 | 3.9 | 4.134  | 2316 | 1.04  | 0.02  | 1.7 | 1.768 |
| 1010 | 0.98   | 0.02 | 3.9 | 3.822  | 2317 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1011 | 0.071  | 0.02 | 3.9 | 0.277  | 2318 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1012 | 0.14   | 0.02 | 3.9 | 0.546  | 2319 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1013 | 0.231  | 0.02 | 3.9 | 0.901  | 2320 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1014 | 1.849  | 0.02 | 3.9 | 7.211  | 2321 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1015 | 1.562  | 0.02 | 3.9 | 6.092  | 2322 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1016 | 0.142  | 0.02 | 3.9 | 0.554  | 2323 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1017 | 0.14   | 0.02 | 3.9 | 0.546  | 2324 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1018 | 0.282  | 0.02 | 3.9 | 1.1    | 2325 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1019 | 0.979  | 0.02 | 3.9 | 3.818  | 2326 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1020 | 0.52   | 0.02 | 3.9 | 2.028  | 2327 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1021 | 0.704  | 0.02 | 3.9 | 2.746  | 2328 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1022 | 2.348  | 0.02 | 3.9 | 9.157  | 2329 | 1.06  | 0.02  | 1.7 | 1.802 |
| 1023 | 3.152  | 0.02 | 3.9 | 12.293 | 2330 | 1.062 | 0.02  | 1.7 | 1.805 |
| 1024 | 4.877  | 0.02 | 3.9 | 19.02  | 2331 | 1.062 | 0.02  | 1.7 | 1.805 |
| 1025 | 1.429  | 0.02 | 3.9 | 5.573  | 2332 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1026 | 0.446  | 0.02 | 3.9 | 1.739  | 2333 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1027 | 0.14   | 0.02 | 3.9 | 0.546  | 2334 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1028 | 0.426  | 0.02 | 3.9 | 1.661  | 2335 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1029 | 0.051  | 0.02 | 3.9 | 0.199  | 2336 | 1.26  | 0.02  | 1.7 | 2.142 |

|      |       |      |     |        |      |       |      |     |       |
|------|-------|------|-----|--------|------|-------|------|-----|-------|
| 1030 | 0.14  | 0.02 | 3.9 | 0.546  | 2337 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1031 | 1.911 | 0.02 | 3.9 | 7.453  | 2338 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1032 | 0.14  | 0.02 | 3.9 | 0.546  | 2339 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1033 | 0.111 | 0.02 | 3.9 | 0.433  | 2340 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1034 | 6.746 | 0.02 | 3.9 | 26.309 | 2341 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1035 | 0.14  | 0.02 | 3.9 | 0.546  | 2342 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1036 | 1.689 | 0.02 | 3.9 | 6.587  | 2343 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1037 | 3.152 | 0.02 | 3.9 | 12.293 | 2344 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1038 | 1.322 | 0.02 | 3.9 | 5.156  | 2345 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1039 | 0.14  | 0.02 | 3.9 | 0.546  | 2346 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1040 | 0.16  | 0.02 | 3.9 | 0.624  | 2347 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1041 | 3.517 | 0.02 | 3.9 | 13.716 | 2348 | 1.06  | 0.02 | 1.7 | 1.802 |
| 1042 | 1.2   | 0.02 | 3.9 | 4.68   | 2349 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1043 | 1.161 | 0.02 | 3.9 | 4.528  | 2350 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1044 | 0.248 | 0.02 | 3.9 | 0.967  | 2351 | 1.66  | 0.02 | 1.7 | 2.822 |
| 1045 | 0.14  | 0.02 | 3.9 | 0.546  | 2352 | 1.66  | 0.02 | 1.7 | 2.822 |
| 1046 | 0.46  | 0.02 | 3.9 | 1.794  | 2353 | 1.56  | 0.02 | 1.7 | 2.652 |
| 1047 | 1.046 | 0.02 | 3.9 | 4.079  | 2354 | 1.56  | 0.02 | 1.7 | 2.652 |
| 1048 | 0.14  | 0.02 | 3.9 | 0.546  | 2355 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1049 | 1.027 | 0.02 | 3.9 | 4.005  | 2356 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1050 | 3.457 | 0.02 | 3.9 | 13.482 | 2357 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1051 | 3.721 | 0.02 | 3.9 | 14.512 | 2358 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1052 | 3.457 | 0.02 | 3.9 | 13.482 | 2359 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1053 | 1.413 | 0.02 | 3.9 | 5.511  | 2360 | 1.028 | 0.02 | 1.7 | 1.748 |
| 1054 | 0.14  | 0.02 | 3.9 | 0.546  | 2361 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1055 | 1.393 | 0.02 | 3.9 | 5.433  | 2362 | 1.064 | 0.02 | 1.7 | 1.809 |
| 1056 | 0.48  | 0.02 | 3.9 | 1.872  | 2363 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1057 | 0.14  | 0.02 | 3.9 | 0.546  | 2364 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1058 | 0.719 | 0.02 | 3.9 | 2.804  | 2365 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1059 | 0.13  | 0.02 | 3.9 | 0.507  | 2366 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1060 | 0.14  | 0.02 | 3.9 | 0.546  | 2367 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1061 | 0.11  | 0.02 | 3.9 | 0.429  | 2368 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1062 | 3.198 | 0.02 | 3.9 | 12.472 | 2369 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1063 | 0.13  | 0.02 | 3.9 | 0.507  | 2370 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1064 | 0.14  | 0.02 | 3.9 | 0.546  | 2371 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1065 | 3.991 | 0.02 | 3.9 | 15.565 | 2372 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1066 | 0.349 | 0.02 | 3.9 | 1.361  | 2373 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1067 | 1.149 | 0.02 | 3.9 | 4.481  | 2374 | 1.064 | 0.02 | 1.7 | 1.809 |
| 1068 | 1.02  | 0.02 | 3.9 | 3.978  | 2375 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1069 | 0.72  | 0.02 | 3.9 | 2.808  | 2376 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1070 | 2.155 | 0.02 | 3.9 | 8.404  | 2377 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1071 | 1.224 | 0.02 | 3.9 | 4.774  | 2378 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1072 | 0.14  | 0.02 | 3.9 | 0.546  | 2379 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1073 | 0.16  | 0.02 | 3.9 | 0.624  | 2380 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1074 | 0.407 | 0.02 | 3.9 | 1.587  | 2381 | 1.26  | 0.02 | 1.7 | 2.142 |

|      |       |      |     |        |      |       |      |     |       |
|------|-------|------|-----|--------|------|-------|------|-----|-------|
| 1075 | 0.14  | 0.02 | 3.9 | 0.546  | 2382 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1076 | 0.16  | 0.02 | 3.9 | 0.624  | 2383 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1077 | 1.204 | 0.02 | 3.9 | 4.696  | 2384 | 1.064 | 0.02 | 1.7 | 1.809 |
| 1078 | 0.033 | 0.02 | 3.9 | 0.129  | 2385 | 1.56  | 0.02 | 1.7 | 2.652 |
| 1079 | 0.14  | 0.02 | 3.9 | 0.546  | 2386 | 1.56  | 0.02 | 1.7 | 2.652 |
| 1080 | 0.463 | 0.02 | 3.9 | 1.806  | 2387 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1081 | 8.736 | 0.02 | 3.9 | 34.07  | 2388 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1082 | 0.13  | 0.02 | 3.9 | 0.507  | 2389 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1083 | 0.14  | 0.02 | 3.9 | 0.546  | 2390 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1084 | 0.11  | 0.02 | 3.9 | 0.429  | 2391 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1085 | 1.789 | 0.02 | 3.9 | 6.977  | 2392 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1086 | 3.485 | 0.02 | 3.9 | 13.592 | 2393 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1087 | 1.789 | 0.02 | 3.9 | 6.977  | 2394 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1088 | 2.495 | 0.02 | 3.9 | 9.731  | 2395 | 1.28  | 0.02 | 1.7 | 2.176 |
| 1089 | 0.14  | 0.02 | 3.9 | 0.546  | 2396 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1090 | 2.475 | 0.02 | 3.9 | 9.653  | 2397 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1091 | 1.404 | 0.02 | 3.9 | 5.476  | 2398 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1092 | 0.267 | 0.02 | 3.9 | 1.041  | 2399 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1093 | 0.14  | 0.02 | 3.9 | 0.546  | 2400 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1094 | 0.107 | 0.02 | 3.9 | 0.417  | 2401 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1095 | 8.978 | 0.02 | 3.9 | 35.014 | 2402 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1096 | 0.379 | 0.02 | 3.9 | 1.478  | 2403 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1097 | 0.14  | 0.02 | 3.9 | 0.546  | 2404 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1098 | 5.06  | 0.02 | 3.9 | 19.734 | 2405 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1099 | 0.14  | 0.02 | 3.9 | 0.546  | 2406 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1100 | 2.428 | 0.02 | 3.9 | 9.469  | 2407 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1101 | 5.858 | 0.02 | 3.9 | 22.846 | 2408 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1102 | 1.126 | 0.02 | 3.9 | 4.391  | 2409 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1103 | 0.092 | 0.02 | 3.9 | 0.359  | 2410 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1104 | 0.14  | 0.02 | 3.9 | 0.546  | 2411 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1105 | 0.188 | 0.02 | 3.9 | 0.733  | 2412 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1106 | 0.091 | 0.02 | 3.9 | 0.355  | 2413 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1107 | 2.226 | 0.02 | 3.9 | 8.681  | 2414 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1108 | 0.16  | 0.02 | 3.9 | 0.624  | 2415 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1109 | 4.222 | 0.02 | 3.9 | 16.466 | 2416 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1110 | 0.14  | 0.02 | 3.9 | 0.546  | 2417 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1111 | 2.226 | 0.02 | 3.9 | 8.681  | 2418 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1112 | 0.099 | 0.02 | 3.9 | 0.386  | 2419 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1113 | 0.16  | 0.02 | 3.9 | 0.624  | 2420 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1114 | 0.083 | 0.02 | 3.9 | 0.324  | 2421 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1115 | 1.126 | 0.02 | 3.9 | 4.391  | 2422 | 1.062 | 0.02 | 1.7 | 1.805 |
| 1116 | 5.858 | 0.02 | 3.9 | 22.846 | 2423 | 0.88  | 0.02 | 1.7 | 1.496 |
| 1117 | 2.453 | 0.02 | 3.9 | 9.567  | 2424 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1118 | 0.12  | 0.02 | 3.9 | 0.468  | 2425 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1119 | 0.16  | 0.02 | 3.9 | 0.624  | 2426 | 1.26  | 0.02 | 1.7 | 2.142 |

|      |       |      |     |        |      |       |       |     |       |
|------|-------|------|-----|--------|------|-------|-------|-----|-------|
| 1120 | 0.398 | 0.02 | 3.9 | 1.552  | 2427 | 1.24  | 0.02  | 1.7 | 2.108 |
| 1121 | 0.14  | 0.02 | 3.9 | 0.546  | 2428 | 1.24  | 0.02  | 1.7 | 2.108 |
| 1122 | 0.112 | 0.02 | 3.9 | 0.437  | 2429 | 0.82  | 0.02  | 1.7 | 1.394 |
| 1123 | 3.194 | 0.02 | 3.9 | 12.457 | 2430 | 0.82  | 0.02  | 1.7 | 1.394 |
| 1124 | 0.45  | 0.02 | 3.9 | 1.755  | 2431 | 0.942 | 0.02  | 1.7 | 1.601 |
| 1125 | 0.82  | 0.02 | 3.9 | 3.198  | 2432 | 0.942 | 0.02  | 1.7 | 1.601 |
| 1126 | 0.43  | 0.02 | 3.9 | 1.677  | 2433 | 1.52  | 0.02  | 1.7 | 2.584 |
| 1127 | 4.264 | 0.02 | 3.9 | 16.63  | 2434 | 1.52  | 0.02  | 1.7 | 2.584 |
| 1128 | 0.35  | 0.02 | 3.9 | 1.365  | 2435 | 1.022 | 0.02  | 1.7 | 1.737 |
| 1129 | 0.66  | 0.02 | 3.9 | 2.574  | 2436 | 1.44  | 0.02  | 1.7 | 2.448 |
| 1130 | 0.049 | 0.02 | 3.9 | 0.191  | 2437 | 1.44  | 0.02  | 1.7 | 2.448 |
| 1131 | 0.14  | 0.02 | 3.9 | 0.546  | 2438 | 0.94  | 0.02  | 1.7 | 1.598 |
| 1132 | 0.918 | 0.02 | 3.9 | 3.58   | 2439 | 0.94  | 0.02  | 1.7 | 1.598 |
| 1133 | 0.14  | 0.02 | 3.9 | 0.546  | 2440 | 1.86  | 0.02  | 1.7 | 3.162 |
| 1134 | 0.209 | 0.02 | 3.9 | 0.815  | 2441 | 1.86  | 0.02  | 1.7 | 3.162 |
| 1135 | 0.68  | 0.02 | 3.9 | 2.652  | 2442 | 1.56  | 0.02  | 1.7 | 2.652 |
| 1136 | 0.13  | 0.02 | 3.9 | 0.507  | 2443 | 1.556 | 0.02  | 1.7 | 2.645 |
| 1137 | 4.264 | 0.02 | 3.9 | 16.63  | 2444 | 0.94  | 0.02  | 1.7 | 1.598 |
| 1138 | 0.25  | 0.02 | 3.9 | 0.975  | 2445 | 0.94  | 0.02  | 1.7 | 1.598 |
| 1139 | 0.82  | 0.02 | 3.9 | 3.198  | 2446 | 1.837 | 0.02  | 1.7 | 3.123 |
| 1140 | 0.23  | 0.02 | 3.9 | 0.897  | 2447 | 1.837 | 0.02  | 1.7 | 3.123 |
| 1141 | 3.193 | 0.02 | 3.9 | 12.453 | 2448 | 0.82  | 0.02  | 1.7 | 1.394 |
| 1142 | 0.106 | 0.02 | 3.9 | 0.413  | 2449 | 0.82  | 0.02  | 1.7 | 1.394 |
| 1143 | 5.032 | 0.02 | 3.9 | 19.625 | 2450 | 0.82  | 0.02  | 1.7 | 1.394 |
| 1144 | 0.14  | 0.02 | 3.9 | 0.546  | 2451 | 0.838 | 0.02  | 1.7 | 1.425 |
| 1145 | 2.397 | 0.02 | 3.9 | 9.348  | 2452 | 1.46  | 0.02  | 1.7 | 2.482 |
| 1146 | 5.858 | 0.02 | 3.9 | 22.846 | 2453 | 1.46  | 0.02  | 1.7 | 2.482 |
| 1147 | 1.126 | 0.02 | 3.9 | 4.391  | 2454 | 1.56  | 0.02  | 1.7 | 2.652 |
| 1148 | 0.092 | 0.02 | 3.9 | 0.359  | 2455 | 1.56  | 0.02  | 1.7 | 2.652 |
| 1149 | 0.14  | 0.02 | 3.9 | 0.546  | 2456 | 1.46  | 0.02  | 1.7 | 2.482 |
| 1150 | 0.16  | 0.02 | 3.9 | 0.624  | 2457 | 1.46  | 0.02  | 1.7 | 2.482 |
| 1151 | 0.091 | 0.02 | 3.9 | 0.355  | 2458 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1152 | 2.226 | 0.02 | 3.9 | 8.681  | 2459 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1153 | 0.16  | 0.02 | 3.9 | 0.624  | 2460 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1154 | 0.16  | 0.02 | 3.9 | 0.624  | 2461 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1155 | 2.226 | 0.02 | 3.9 | 8.681  | 2462 | 1.716 | 0.02  | 1.7 | 2.917 |
| 1156 | 0.079 | 0.02 | 3.9 | 0.308  | 2463 | 1.716 | 0.021 | 1.7 | 2.917 |
| 1157 | 0.16  | 0.02 | 3.9 | 0.624  | 2464 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1158 | 0.16  | 0.02 | 3.9 | 0.624  | 2465 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1159 | 0.103 | 0.02 | 3.9 | 0.402  | 2466 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1160 | 1.126 | 0.02 | 3.9 | 4.391  | 2467 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1161 | 5.858 | 0.02 | 3.9 | 22.846 | 2468 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1162 | 2.454 | 0.02 | 3.9 | 9.571  | 2469 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1163 | 0.12  | 0.02 | 3.9 | 0.468  | 2470 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1164 | 0.16  | 0.02 | 3.9 | 0.624  | 2471 | 0.96  | 0.02  | 1.7 | 1.632 |

|      |       |      |     |        |      |       |      |     |       |
|------|-------|------|-----|--------|------|-------|------|-----|-------|
| 1165 | 0.43  | 0.02 | 3.9 | 1.677  | 2472 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1166 | 0.14  | 0.02 | 3.9 | 0.546  | 2473 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1167 | 0.107 | 0.02 | 3.9 | 0.417  | 2474 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1168 | 8.978 | 0.02 | 3.9 | 35.014 | 2475 | 1.46  | 0.02 | 1.7 | 2.482 |
| 1169 | 0.379 | 0.02 | 3.9 | 1.478  | 2476 | 1.46  | 0.02 | 1.7 | 2.482 |
| 1170 | 0.14  | 0.02 | 3.9 | 0.546  | 2477 | 1.46  | 0.02 | 1.7 | 2.482 |
| 1171 | 0.16  | 0.02 | 3.9 | 0.624  | 2478 | 1.46  | 0.02 | 1.7 | 2.482 |
| 1172 | 0.199 | 0.02 | 3.9 | 0.776  | 2479 | 0.82  | 0.02 | 1.7 | 1.394 |
| 1173 | 0.88  | 0.02 | 3.9 | 3.432  | 2480 | 0.82  | 0.02 | 1.7 | 1.394 |
| 1174 | 0.16  | 0.02 | 3.9 | 0.624  | 2481 | 0.82  | 0.02 | 1.7 | 1.394 |
| 1175 | 4.204 | 0.02 | 3.9 | 16.396 | 2482 | 0.82  | 0.02 | 1.7 | 1.394 |
| 1176 | 0.28  | 0.02 | 3.9 | 1.092  | 2483 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1177 | 2.02  | 0.02 | 3.9 | 7.878  | 2484 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1178 | 0.252 | 0.02 | 3.9 | 0.983  | 2485 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1179 | 1.853 | 0.02 | 3.9 | 7.227  | 2486 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1180 | 0.143 | 0.02 | 3.9 | 0.558  | 2487 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1181 | 5.06  | 0.02 | 3.9 | 19.734 | 2488 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1182 | 0.14  | 0.02 | 3.9 | 0.546  | 2489 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1183 | 2.433 | 0.02 | 3.9 | 9.489  | 2490 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1184 | 5.858 | 0.02 | 3.9 | 22.846 | 2491 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1185 | 1.126 | 0.02 | 3.9 | 4.391  | 2492 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1186 | 0.103 | 0.02 | 3.9 | 0.402  | 2493 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1187 | 0.14  | 0.02 | 3.9 | 0.546  | 2494 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1188 | 0.188 | 0.02 | 3.9 | 0.733  | 2495 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1189 | 0.079 | 0.02 | 3.9 | 0.308  | 2496 | 0.962 | 0.02 | 1.7 | 1.635 |
| 1190 | 2.226 | 0.02 | 3.9 | 8.681  | 2497 | 0.962 | 0.02 | 1.7 | 1.635 |
| 1191 | 0.16  | 0.02 | 3.9 | 0.624  | 2498 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1192 | 0.16  | 0.02 | 3.9 | 0.624  | 2499 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1193 | 2.226 | 0.02 | 3.9 | 8.681  | 2500 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1194 | 0.111 | 0.02 | 3.9 | 0.433  | 2501 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1195 | 0.14  | 0.02 | 3.9 | 0.546  | 2502 | 0.82  | 0.02 | 1.7 | 1.394 |
| 1196 | 0.16  | 0.02 | 3.9 | 0.624  | 2503 | 0.82  | 0.02 | 1.7 | 1.394 |
| 1197 | 0.072 | 0.02 | 3.9 | 0.281  | 2504 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1198 | 1.126 | 0.02 | 3.9 | 4.391  | 2505 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1199 | 5.858 | 0.02 | 3.9 | 22.846 | 2506 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1200 | 2.447 | 0.02 | 3.9 | 9.543  | 2507 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1201 | 0.12  | 0.02 | 3.9 | 0.468  | 2508 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1202 | 0.42  | 0.02 | 3.9 | 1.638  | 2509 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1203 | 0.14  | 0.02 | 3.9 | 0.546  | 2510 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1204 | 0.14  | 0.02 | 3.9 | 0.546  | 2511 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1205 | 1.351 | 0.02 | 3.9 | 5.269  | 2512 | 1.26  | 0.02 | 1.7 | 2.142 |
| 1206 | 0.31  | 0.02 | 3.9 | 1.209  | 2513 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1207 | 0.66  | 0.02 | 3.9 | 2.574  | 2514 | 0.96  | 0.02 | 1.7 | 1.632 |
| 1208 | 0.277 | 0.02 | 3.9 | 1.08   | 2515 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1209 | 6.066 | 0.02 | 3.9 | 23.657 | 2516 | 0.96  | 0.02 | 1.7 | 1.632 |

|      |       |      |     |        |      |       |       |     |       |
|------|-------|------|-----|--------|------|-------|-------|-----|-------|
| 1210 | 0.14  | 0.02 | 3.9 | 0.546  | 2517 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1211 | 0.86  | 0.02 | 3.9 | 3.354  | 2518 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1212 | 0.239 | 0.02 | 3.9 | 0.932  | 2519 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1213 | 0.14  | 0.02 | 3.9 | 0.546  | 2520 | 1.66  | 0.02  | 1.7 | 2.822 |
| 1214 | 0.16  | 0.02 | 3.9 | 0.624  | 2521 | 1.66  | 0.02  | 1.7 | 2.822 |
| 1215 | 0.339 | 0.02 | 3.9 | 1.322  | 2522 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1216 | 0.88  | 0.02 | 3.9 | 3.432  | 2523 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1217 | 2.704 | 0.02 | 3.9 | 10.546 | 2524 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1218 | 0.28  | 0.02 | 3.9 | 1.092  | 2525 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1219 | 2.02  | 0.02 | 3.9 | 7.878  | 2526 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1220 | 0.26  | 0.02 | 3.9 | 1.014  | 2527 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1221 | 1.322 | 0.02 | 3.9 | 5.156  | 2528 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1222 | 0.21  | 0.02 | 3.9 | 0.819  | 2529 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1223 | 0.66  | 0.02 | 3.9 | 2.574  | 2530 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1224 | 0.19  | 0.02 | 3.9 | 0.741  | 2531 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1225 | 1.351 | 0.02 | 3.9 | 5.269  | 2532 | 1.66  | 0.02  | 1.7 | 2.822 |
| 1226 | 0.113 | 0.02 | 3.9 | 0.441  | 2533 | 1.66  | 0.02  | 1.7 | 2.822 |
| 1227 | 5.06  | 0.02 | 3.9 | 19.734 | 2534 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1228 | 0.14  | 0.02 | 3.9 | 0.546  | 2535 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1229 | 2.433 | 0.02 | 3.9 | 9.489  | 2536 | 1.66  | 0.02  | 1.7 | 2.822 |
| 1230 | 5.858 | 0.02 | 3.9 | 22.846 | 2537 | 1.68  | 0.02  | 1.7 | 2.856 |
| 1231 | 1.126 | 0.02 | 3.9 | 4.391  | 2538 | 1.06  | 0.02  | 1.7 | 1.802 |
| 1232 | 0.103 | 0.02 | 3.9 | 0.402  | 2539 | 1.06  | 0.02  | 1.7 | 1.802 |
| 1233 | 0.14  | 0.02 | 3.9 | 0.546  | 2540 | 1.66  | 0.02  | 1.7 | 2.822 |
| 1234 | 0.16  | 0.02 | 3.9 | 0.624  | 2541 | 1.66  | 0.02  | 1.7 | 2.822 |
| 1235 | 0.079 | 0.02 | 3.9 | 0.308  | 2542 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1236 | 2.226 | 0.02 | 3.9 | 8.681  | 2543 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1237 | 0.16  | 0.02 | 3.9 | 0.624  | 2544 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1238 | 0.16  | 0.02 | 3.9 | 0.624  | 2545 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1239 | 2.226 | 0.02 | 3.9 | 8.681  | 2546 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1240 | 0.111 | 0.02 | 3.9 | 0.433  | 2547 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1241 | 0.14  | 0.02 | 3.9 | 0.546  | 2548 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1242 | 0.16  | 0.02 | 3.9 | 0.624  | 2549 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1243 | 0.072 | 0.02 | 3.9 | 0.281  | 2550 | 1.46  | 0.02  | 1.7 | 2.482 |
| 1244 | 1.126 | 0.02 | 3.9 | 4.391  | 2551 | 1.46  | 0.021 | 1.7 | 2.482 |
| 1245 | 5.858 | 0.02 | 3.9 | 22.846 | 2552 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1246 | 2.448 | 0.02 | 3.9 | 9.547  | 2553 | 0.96  | 0.02  | 1.7 | 1.632 |
| 1247 | 0.12  | 0.02 | 3.9 | 0.468  | 2554 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1248 | 0.132 | 0.02 | 3.9 | 0.515  | 2555 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1249 | 0.14  | 0.02 | 3.9 | 0.546  | 2556 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1250 | 0.4   | 0.02 | 3.9 | 1.56   | 2557 | 1.26  | 0.02  | 1.7 | 2.142 |
| 1251 | 0.14  | 0.02 | 3.9 | 0.546  | 2558 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1252 | 0.107 | 0.02 | 3.9 | 0.417  | 2559 | 0.86  | 0.02  | 1.7 | 1.462 |
| 1253 | 4.053 | 0.02 | 3.9 | 15.807 | 2560 | 1.262 | 0.02  | 1.7 | 2.145 |
| 1254 | 0.2   | 0.02 | 3.9 | 0.78   | 2561 | 1.262 | 0.02  | 1.7 | 2.145 |

|      |       |      |     |        |      |       |      |     |       |
|------|-------|------|-----|--------|------|-------|------|-----|-------|
| 1255 | 1.32  | 0.02 | 3.9 | 5.148  | 2562 | 1.46  | 0.02 | 1.7 | 2.482 |
| 1256 | 0.18  | 0.02 | 3.9 | 0.702  | 2563 | 1.46  | 0.02 | 1.7 | 2.482 |
| 1257 | 3.584 | 0.02 | 3.9 | 13.978 | 2564 | 1.262 | 0.02 | 1.7 | 2.145 |
| 1258 | 0.379 | 0.02 | 3.9 | 1.478  | 2565 | 1.262 | 0.02 | 1.7 | 2.145 |
| 1259 | 0.14  | 0.02 | 3.9 | 0.546  | 2566 | 0.962 | 0.02 | 1.7 | 1.635 |
| 1260 | 0.16  | 0.02 | 3.9 | 0.624  | 2567 | 0.962 | 0.02 | 1.7 | 1.635 |
| 1261 | 0.199 | 0.02 | 3.9 | 0.776  | 2568 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1262 | 0.88  | 0.02 | 3.9 | 3.432  | 2569 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1263 | 0.16  | 0.02 | 3.9 | 0.624  | 2570 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1264 | 2.704 | 0.02 | 3.9 | 10.546 | 2571 | 0.86  | 0.02 | 1.7 | 1.462 |
| 1265 | 0.48  | 0.02 | 3.9 | 1.872  | 2572 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1266 | 1.32  | 0.02 | 3.9 | 5.148  | 2573 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1267 | 0.46  | 0.02 | 3.9 | 1.794  | 2574 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1268 | 4.053 | 0.02 | 3.9 | 15.807 | 2575 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1269 | 4.71  | 0.02 | 3.9 | 18.369 | 2576 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1270 | 0.14  | 0.02 | 3.9 | 0.546  | 2577 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1271 | 2.077 | 0.02 | 3.9 | 8.1    | 2578 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1272 | 5.858 | 0.02 | 3.9 | 22.846 | 2579 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1273 | 1.126 | 0.02 | 3.9 | 4.391  | 2580 | 1.43  | 0.02 | 2.5 | 3.575 |
| 1274 | 0.092 | 0.02 | 3.9 | 0.359  | 2581 | 1.43  | 0.02 | 2.5 | 3.575 |
| 1275 | 0.14  | 0.02 | 3.9 | 0.546  | 2582 | 1.421 | 0.02 | 2.5 | 3.553 |
| 1276 | 0.16  | 0.02 | 3.9 | 0.624  | 2583 | 1.385 | 0.02 | 2.5 | 3.463 |
| 1277 | 0.091 | 0.02 | 3.9 | 0.355  | 2584 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1278 | 2.226 | 0.02 | 3.9 | 8.681  | 2585 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1279 | 0.14  | 0.02 | 3.9 | 0.546  | 2586 | 1.39  | 0.02 | 2.5 | 3.475 |
| 1280 | 0.16  | 0.02 | 3.9 | 0.624  | 2587 | 1.47  | 0.02 | 2.5 | 3.675 |
| 1281 | 2.226 | 0.02 | 3.9 | 8.681  | 2588 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1282 | 0.099 | 0.02 | 3.9 | 0.386  | 2589 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1283 | 0.14  | 0.02 | 3.9 | 0.546  | 2590 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1284 | 0.16  | 0.02 | 3.9 | 0.624  | 2591 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1285 | 0.083 | 0.02 | 3.9 | 0.324  | 2592 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1286 | 1.126 | 0.02 | 3.9 | 4.391  | 2593 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1287 | 5.858 | 0.02 | 3.9 | 22.846 | 2594 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1288 | 2.453 | 0.02 | 3.9 | 9.567  | 2595 | 1.409 | 0.02 | 2.5 | 3.523 |
| 1289 | 0.12  | 0.02 | 3.9 | 0.468  | 2596 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1290 | 0.94  | 0.02 | 3.9 | 3.666  | 2597 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1291 | 0.14  | 0.02 | 3.9 | 0.546  | 2598 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1292 | 0.11  | 0.02 | 3.9 | 0.429  | 2599 | 1.409 | 0.02 | 2.5 | 3.523 |
| 1293 | 0.52  | 0.02 | 3.9 | 2.028  | 2600 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1294 | 0.333 | 0.02 | 3.9 | 1.299  | 2601 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1295 | 0.12  | 0.02 | 3.9 | 0.468  | 2602 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1296 | 0.13  | 0.02 | 3.9 | 0.507  | 2603 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1297 | 0.52  | 0.02 | 3.9 | 2.028  | 2604 | 1.414 | 0.02 | 2.5 | 3.535 |
| 1298 | 0.147 | 0.02 | 3.9 | 0.573  | 2605 | 1.41  | 0.02 | 2.5 | 3.525 |
| 1299 | 2.673 | 0.02 | 3.9 | 10.425 | 2606 | 1.41  | 0.02 | 2.5 | 3.525 |

|      |       |      |     |        |      |      |      |     |       |
|------|-------|------|-----|--------|------|------|------|-----|-------|
| 1300 | 2.673 | 0.02 | 3.9 | 10.425 | 2607 | 1.41 | 0.02 | 2.5 | 3.525 |
| 1301 | 0.15  | 0.02 | 3.9 | 0.585  | 2608 | 3.03 | 0.02 | 2.5 | 7.575 |
| 1302 | 0.335 | 0.02 | 3.9 | 1.307  | 2609 | 1.41 | 0.02 | 2.5 | 3.525 |
| 1303 | 1.02  | 0.02 | 3.9 | 3.978  |      |      |      |     |       |
| 1304 | 1.02  | 0.02 | 3.9 | 3.978  |      |      |      |     |       |
| 1305 | 0.13  | 0.02 | 3.9 | 0.507  |      |      |      |     |       |

## 9.2.2- Quantity Of Building:

Table 12 Quantity of building for third floor

| Wall number | Length (m) | Width (m) | Height (m) | Area (m <sup>2</sup> ) | Wall number | Length (m) | Width (m) | Height (m) | Area (m <sup>2</sup> ) |
|-------------|------------|-----------|------------|------------------------|-------------|------------|-----------|------------|------------------------|
| W1          | 4.538      | 0.12      | 3.9        | 17.6982                | W621        | 0.134      | 0.12      | 3.9        | 0.5226                 |
| W2          | 1.667      | 0.12      | 3.9        | 6.5013                 | W622        | 0.05       | 0.12      | 3.9        | 0.195                  |
| W3          | 3.143      | 0.12      | 3.9        | 12.2577                | W623        | 0.12       | 0.104     | 3.9        | 0.468                  |
| W4          | 1.959      | 0.12      | 3.9        | 7.6401                 | W624        | 0.05       | 0.12      | 3.9        | 0.195                  |
| W5          | 0.21       | 0.12      | 3.9        | 0.819                  | W625        | 0.12       | 0.104     | 3.9        | 0.468                  |
| W6          | 1.934      | 0.12      | 3.9        | 7.5426                 | W626        | 0.05       | 0.12      | 3.9        | 0.195                  |
| W7          | 2.642      | 0.12      | 3.9        | 10.3038                | W627        | 0.05       | 0.12      | 3.9        | 0.195                  |
| W8          | 0.168      | 0.12      | 3.9        | 0.6552                 | W628        | 0.05       | 0.12      | 3.9        | 0.195                  |
| W9          | 0.339      | 0.12      | 3.9        | 1.3221                 | W629        | 0.071      | 0.12      | 3.9        | 0.2769                 |
| W10         | 0.52       | 0.12      | 3.9        | 2.028                  | W630        | 0.05       | 0.12      | 3.9        | 0.195                  |
| W11         | 0.52       | 0.12      | 3.9        | 2.028                  | W631        | 0.12       | 0.104     | 3.9        | 0.468                  |
| W12         | 0.4        | 0.12      | 3.9        | 1.56                   | W632        | 0.05       | 0.12      | 3.9        | 0.195                  |
| W13         | 1.373      | 0.119     | 3.9        | 5.3547                 | W633        | 0.12       | 0.104     | 3.9        | 0.468                  |
| W14         | 3.407      | 0.12      | 3.9        | 13.2873                | W634        | 0.085      | 0.12      | 3.9        | 0.3315                 |
| W15         | 1.541      | 0.12      | 3.9        | 6.0099                 | W635        | 0.05       | 0.12      | 3.9        | 0.195                  |
| W16         | 4.991      | 0.12      | 3.9        | 19.4649                | W636        | 0.05       | 0.12      | 3.9        | 0.195                  |
| W17         | 3.127      | 0.12      | 3.9        | 12.1953                | W637        | 0.071      | 0.12      | 3.9        | 0.2769                 |
| W18         | 0.659      | 0.12      | 3.9        | 2.5701                 | W638        | 5.218      | 0.12      | 3.9        | 20.3502                |
| W19         | 2.093      | 0.12      | 3.9        | 8.1627                 | W639        | 1.877      | 0.15      | 3.9        | 7.3203                 |
| W20         | 0.54       | 0.12      | 3.9        | 2.106                  | W640        | 0.409      | 0.12      | 3.9        | 1.5951                 |
| W21         | 0.52       | 0.12      | 3.9        | 2.028                  | W641        | 3.907      | 0.115     | 3.9        | 15.2373                |
| W22         | 0.701      | 0.12      | 3.9        | 2.7339                 | W642        | 0.65       | 0.23      | 3.9        | 2.535                  |
| W23         | 0.171      | 0.12      | 3.9        | 0.6669                 | W643        | 2.81       | 0.12      | 3.9        | 10.959                 |
| W24         | 1.336      | 0.12      | 3.9        | 5.2104                 | W644        | 0.25       | 0.213     | 3.9        | 0.975                  |
| W25         | 1.598      | 0.12      | 3.9        | 6.2322                 | W645        | 2.75       | 0.12      | 3.9        | 10.725                 |
| W26         | 0.905      | 0.121     | 3.9        | 3.5295                 | W646        | 4.18       | 0.12      | 3.9        | 16.302                 |
| W27         | 1.979      | 0.12      | 3.9        | 7.7181                 | W647        | 0.649      | 0.23      | 3.9        | 2.5311                 |
| W28         | 3.921      | 0.12      | 3.9        | 15.2919                | W648        | 0.378      | 0.12      | 3.9        | 1.4742                 |
| W29         | 1.061      | 0.12      | 3.9        | 4.1379                 | W649        | 3.234      | 0.12      | 3.9        | 12.6126                |
| W30         | 1.531      | 0.12      | 3.9        | 5.9709                 | W650        | 4.304      | 0.12      | 3.9        | 16.7856                |



|     |       |       |     |         |      |       |       |     |         |
|-----|-------|-------|-----|---------|------|-------|-------|-----|---------|
| W31 | 4.33  | 0.12  | 3.9 | 16.887  | W651 | 0.05  | 0.12  | 3.9 | 0.195   |
| W32 | 2.25  | 0.12  | 3.9 | 8.775   | W652 | 4.205 | 0.12  | 3.9 | 16.3995 |
| W33 | 6.451 | 0.12  | 3.9 | 25.1589 | W653 | 2.188 | 0.12  | 3.9 | 8.5332  |
| W34 | 0.25  | 0.12  | 3.9 | 0.975   | W654 | 0.52  | 0.12  | 3.9 | 2.028   |
| W35 | 0.17  | 0.12  | 3.9 | 0.663   | W655 | 0.52  | 0.12  | 3.9 | 2.028   |
| W36 | 0.13  | 0.12  | 3.9 | 0.507   | W656 | 0.604 | 0.12  | 3.9 | 2.3556  |
| W37 | 5.69  | 0.12  | 3.9 | 22.191  | W657 | 2.48  | 0.12  | 3.9 | 9.672   |
| W38 | 0.13  | 0.12  | 3.9 | 0.507   | W658 | 2.296 | 0.12  | 3.9 | 8.9544  |
| W39 | 0.77  | 0.12  | 3.9 | 3.003   | W659 | 2.188 | 0.12  | 3.9 | 8.5332  |
| W40 | 3.51  | 0.12  | 3.9 | 13.689  | W660 | 0.096 | 0.12  | 3.9 | 0.3744  |
| W41 | 0.52  | 0.12  | 3.9 | 2.028   | W661 | 5.955 | 0.12  | 3.9 | 23.2245 |
| W42 | 0.604 | 0.12  | 3.9 | 2.3556  | W662 | 5.026 | 0.12  | 3.9 | 19.6014 |
| W43 | 4.92  | 0.12  | 3.9 | 19.188  | W663 | 3.485 | 0.12  | 3.9 | 13.5915 |
| W44 | 0.13  | 0.12  | 3.9 | 0.507   | W664 | 0.363 | 0.25  | 3.9 | 1.4157  |
| W45 | 0.362 | 0.25  | 3.9 | 1.4118  | W665 | 0.336 | 0.25  | 3.9 | 1.3104  |
| W46 | 5.975 | 0.12  | 3.9 | 23.3025 | W666 | 0.388 | 0.25  | 3.9 | 1.5132  |
| W47 | 3.483 | 0.12  | 3.9 | 13.5837 | W667 | 0.362 | 0.251 | 3.9 | 1.4118  |
| W48 | 0.25  | 0.12  | 3.9 | 0.975   | W668 | 0.336 | 0.251 | 3.9 | 1.3104  |
| W49 | 1.35  | 0.12  | 3.9 | 5.265   | W669 | 0.388 | 0.251 | 3.9 | 1.5132  |
| W50 | 1.798 | 0.12  | 3.9 | 7.0122  | W670 | 1.373 | 0.12  | 3.9 | 5.3547  |
| W51 | 0.953 | 0.12  | 3.9 | 3.7167  | W671 | 0.24  | 0.12  | 3.9 | 0.936   |
| W52 | 6.41  | 0.117 | 3.9 | 24.999  | W672 | 1.855 | 0.12  | 3.9 | 7.2345  |
| W53 | 0.52  | 0.12  | 3.9 | 2.028   | W673 | 0.32  | 0.12  | 3.9 | 1.248   |
| W54 | 0.604 | 0.12  | 3.9 | 2.3556  | W674 | 1.905 | 0.12  | 3.9 | 7.4295  |
| W55 | 0.4   | 0.12  | 3.9 | 1.56    | W675 | 1.363 | 0.12  | 3.9 | 5.3157  |
| W56 | 0.733 | 0.08  | 3.9 | 2.8587  | W676 | 0.362 | 0.25  | 3.9 | 1.4118  |
| W57 | 0.85  | 0.12  | 3.9 | 3.315   | W677 | 3.485 | 0.12  | 3.9 | 13.5915 |
| W58 | 0.52  | 0.128 | 3.9 | 2.028   | W678 | 5.02  | 0.12  | 3.9 | 19.578  |
| W59 | 0.722 | 0.12  | 3.9 | 2.8158  | W679 | 5.898 | 0.12  | 3.9 | 23.0022 |
| W60 | 0.4   | 0.112 | 3.9 | 1.56    | W680 | 2.296 | 0.12  | 3.9 | 8.9544  |
| W61 | 6.82  | 0.12  | 3.9 | 26.598  | W681 | 2.48  | 0.12  | 3.9 | 9.672   |
| W62 | 0.338 | 0.05  | 3.9 | 1.3182  | W682 | 0.844 | 0.12  | 3.9 | 3.2916  |
| W63 | 1.331 | 0.12  | 3.9 | 5.1909  | W683 | 0.4   | 0.12  | 3.9 | 1.56    |
| W64 | 0.121 | 0.12  | 3.9 | 0.4719  | W684 | 0.4   | 0.12  | 3.9 | 1.56    |
| W65 | 0.736 | 0.12  | 3.9 | 2.8704  | W685 | 4.263 | 0.12  | 3.9 | 16.6257 |
| W66 | 4.473 | 0.121 | 3.9 | 17.4447 | W686 | 2.179 | 0.12  | 3.9 | 8.4981  |
| W67 | 1.803 | 0.05  | 3.9 | 7.0317  | W687 | 2.188 | 0.12  | 3.9 | 8.5332  |
| W68 | 0.36  | 0.05  | 3.9 | 1.404   | W688 | 0.049 | 0.12  | 3.9 | 0.1911  |
| W69 | 0.266 | 0.05  | 3.9 | 1.0374  | W689 | 0.067 | 0.12  | 3.9 | 0.2613  |
| W70 | 4.391 | 0.12  | 3.9 | 17.1249 | W690 | 0.05  | 0.12  | 3.9 | 0.195   |
| W71 | 0.38  | 0.12  | 3.9 | 1.482   | W691 | 0.12  | 0.104 | 3.9 | 0.468   |
| W72 | 1.798 | 0.05  | 3.9 | 7.0122  | W692 | 0.05  | 0.12  | 3.9 | 0.195   |
| W73 | 0.36  | 0.05  | 3.9 | 1.404   | W693 | 0.12  | 0.104 | 3.9 | 0.468   |

|      |       |       |     |         |      |       |       |     |         |
|------|-------|-------|-----|---------|------|-------|-------|-----|---------|
| W74  | 0.339 | 0.05  | 3.9 | 1.3221  | W694 | 0.085 | 0.12  | 3.9 | 0.3315  |
| W75  | 1.338 | 0.12  | 3.9 | 5.2182  | W695 | 0.05  | 0.12  | 3.9 | 0.195   |
| W76  | 0.13  | 0.124 | 3.9 | 0.507   | W696 | 0.05  | 0.12  | 3.9 | 0.195   |
| W77  | 0.37  | 0.124 | 3.9 | 1.443   | W697 | 0.071 | 0.12  | 3.9 | 0.2769  |
| W78  | 3.971 | 0.12  | 3.9 | 15.4869 | W698 | 2.938 | 0.12  | 3.9 | 11.4582 |
| W79  | 6.831 | 0.121 | 3.9 | 26.6409 | W699 | 3.057 | 0.12  | 3.9 | 11.9223 |
| W80  | 0.901 | 0.12  | 3.9 | 3.5139  | W700 | 0.215 | 0.12  | 3.9 | 0.8385  |
| W81  | 0.363 | 0.25  | 3.9 | 1.4157  | W701 | 6.587 | 0.12  | 3.9 | 25.6893 |
| W82  | 1.95  | 0.12  | 3.9 | 7.605   | W702 | 7.1   | 0.12  | 3.9 | 27.69   |
| W83  | 2.662 | 0.12  | 3.9 | 10.3818 | W703 | 0.247 | 0.12  | 3.9 | 0.9633  |
| W84  | 1.798 | 0.12  | 3.9 | 7.0122  | W704 | 3.234 | 0.121 | 3.9 | 12.6126 |
| W85  | 0.724 | 0.12  | 3.9 | 2.8236  | W705 | 3.904 | 0.119 | 3.9 | 15.2256 |
| W86  | 0.4   | 0.12  | 3.9 | 1.56    | W706 | 6.054 | 0.12  | 3.9 | 23.6106 |
| W87  | 8.071 | 0.12  | 3.9 | 31.4769 | W707 | 0.096 | 0.12  | 3.9 | 0.3744  |
| W88  | 5.38  | 0.12  | 3.9 | 20.982  | W708 | 0.52  | 0.12  | 3.9 | 2.028   |
| W89  | 0.127 | 0.12  | 3.9 | 0.4953  | W709 | 0.604 | 0.12  | 3.9 | 2.3556  |
| W90  | 0.603 | 0.12  | 3.9 | 2.3517  | W710 | 4.765 | 0.12  | 3.9 | 18.5835 |
| W91  | 5.224 | 0.12  | 3.9 | 20.3736 | W711 | 0.861 | 0.12  | 3.9 | 3.3579  |
| W92  | 1.486 | 0.12  | 3.9 | 5.7954  | W712 | 3.247 | 0.12  | 3.9 | 12.6633 |
| W93  | 0.127 | 0.12  | 3.9 | 0.4953  | W713 | 0.937 | 0.12  | 3.9 | 3.6543  |
| W94  | 2.313 | 0.12  | 3.9 | 9.0207  | W714 | 0.13  | 0.12  | 3.9 | 0.507   |
| W95  | 4.092 | 0.131 | 3.9 | 15.9588 | W715 | 1.503 | 0.12  | 3.9 | 5.8617  |
| W96  | 7.521 | 0.12  | 3.9 | 29.3319 | W716 | 0.25  | 0.12  | 3.9 | 0.975   |
| W97  | 0.4   | 0.12  | 3.9 | 1.56    | W717 | 2.577 | 0.12  | 3.9 | 10.0503 |
| W98  | 0.52  | 0.12  | 3.9 | 2.028   | W718 | 0.38  | 0.12  | 3.9 | 1.482   |
| W99  | 0.604 | 0.12  | 3.9 | 2.3556  | W719 | 2.577 | 0.12  | 3.9 | 10.0503 |
| W100 | 2.541 | 0.12  | 3.9 | 9.9099  | W720 | 0.89  | 0.12  | 3.9 | 3.471   |
| W101 | 2.797 | 0.84  | 3.9 | 10.9083 | W721 | 0.253 | 0.12  | 3.9 | 0.9867  |
| W102 | 0.5   | 0.545 | 3.9 | 1.95    | W722 | 3.514 | 0.12  | 3.9 | 13.7046 |
| W103 | 1.52  | 0.12  | 3.9 | 5.928   | W723 | 0.362 | 0.249 | 3.9 | 1.4118  |
| W104 | 2.108 | 0.12  | 3.9 | 8.2212  | W724 | 0.361 | 0.25  | 3.9 | 1.4079  |
| W105 | 0.38  | 0.12  | 3.9 | 1.482   | W725 | 4.355 | 0.12  | 3.9 | 16.9845 |
| W106 | 0.427 | 0.12  | 3.9 | 1.6653  | W726 | 0.52  | 0.12  | 3.9 | 2.028   |
| W107 | 0.12  | 0.088 | 3.9 | 0.468   | W727 | 0.4   | 0.12  | 3.9 | 1.56    |
| W108 | 0.659 | 0.12  | 3.9 | 2.5701  | W728 | 0.85  | 0.12  | 3.9 | 3.315   |
| W109 | 1.389 | 0.12  | 3.9 | 5.4171  | W729 | 2.977 | 0.12  | 3.9 | 11.6103 |
| W110 | 1.572 | 0.12  | 3.9 | 6.1308  | W730 | 0.667 | 0.12  | 3.9 | 2.6013  |
| W111 | 4.768 | 0.12  | 3.9 | 18.5952 | W731 | 0.547 | 0.12  | 3.9 | 2.1333  |
| W112 | 2.162 | 0.12  | 3.9 | 8.4318  | W732 | 0.328 | 0.25  | 3.9 | 1.2792  |
| W113 | 0.126 | 0.12  | 3.9 | 0.4914  | W733 | 0.376 | 0.25  | 3.9 | 1.4664  |
| W114 | 0.25  | 0.12  | 3.9 | 0.975   | W734 | 1.891 | 0.12  | 3.9 | 7.3749  |
| W115 | 2.221 | 0.12  | 3.9 | 8.6619  | W735 | 0.13  | 0.12  | 3.9 | 0.507   |
| W116 | 0.13  | 0.12  | 3.9 | 0.507   | W736 | 1.756 | 0.12  | 3.9 | 6.8484  |

|      |       |       |     |         |      |       |       |     |         |
|------|-------|-------|-----|---------|------|-------|-------|-----|---------|
| W117 | 2.863 | 0.12  | 3.9 | 11.1657 | W737 | 3.795 | 0.12  | 3.9 | 14.8005 |
| W118 | 0.7   | 0.12  | 3.9 | 2.73    | W738 | 0.53  | 0.12  | 3.9 | 2.067   |
| W119 | 1.798 | 0.12  | 3.9 | 7.0122  | W739 | 0.618 | 0.12  | 3.9 | 2.4102  |
| W120 | 3.328 | 0.12  | 3.9 | 12.9792 | W740 | 3.757 | 0.12  | 3.9 | 14.6523 |
| W121 | 3.475 | 0.12  | 3.9 | 13.5525 | W741 | 4.98  | 0.12  | 3.9 | 19.422  |
| W122 | 0.363 | 0.25  | 3.9 | 1.4157  | W742 | 0.667 | 0.12  | 3.9 | 2.6013  |
| W123 | 3.663 | 0.12  | 3.9 | 14.2857 | W743 | 1.362 | 0.12  | 3.9 | 5.3118  |
| W124 | 0.363 | 0.25  | 3.9 | 1.4157  | W744 | 0.397 | 0.12  | 3.9 | 1.5483  |
| W125 | 2.852 | 0.12  | 3.9 | 11.1228 | W745 | 3.587 | 0.12  | 3.9 | 13.9893 |
| W126 | 3.475 | 0.12  | 3.9 | 13.5525 | W746 | 0.07  | 0.05  | 3.9 | 0.273   |
| W127 | 0.234 | 0.4   | 3.9 | 0.9126  | W747 | 0.658 | 0.05  | 3.9 | 2.5662  |
| W128 | 0.64  | 0.12  | 3.9 | 2.496   | W748 | 1.8   | 0.05  | 3.9 | 7.02    |
| W129 | 0.52  | 0.12  | 3.9 | 2.028   | W749 | 0.387 | 0.12  | 3.9 | 1.5093  |
| W130 | 0.52  | 0.12  | 3.9 | 2.028   | W750 | 4.667 | 0.12  | 3.9 | 18.2013 |
| W131 | 0.4   | 0.12  | 3.9 | 1.56    | W751 | 0.13  | 0.05  | 3.9 | 0.507   |
| W132 | 1.627 | 0.12  | 3.9 | 6.3453  | W752 | 0.13  | 0.05  | 3.9 | 0.507   |
| W133 | 0.25  | 0.12  | 3.9 | 0.975   | W753 | 0.658 | 0.05  | 3.9 | 2.5662  |
| W134 | 3.033 | 0.12  | 3.9 | 11.8287 | W754 | 1.8   | 0.05  | 3.9 | 7.02    |
| W135 | 2.901 | 0.12  | 3.9 | 11.3139 | W755 | 1.224 | 0.12  | 3.9 | 4.7736  |
| W136 | 0.13  | 0.12  | 3.9 | 0.507   | W756 | 5.71  | 0.12  | 3.9 | 22.269  |
| W137 | 0.52  | 0.12  | 3.9 | 2.028   | W757 | 0.57  | 0.15  | 3.9 | 2.223   |
| W138 | 0.4   | 0.12  | 3.9 | 1.56    | W758 | 5.814 | 0.12  | 3.9 | 22.6746 |
| W139 | 2.803 | 0.12  | 3.9 | 10.9317 | W759 | 0.362 | 0.25  | 3.9 | 1.4118  |
| W140 | 4.259 | 0.12  | 3.9 | 16.6101 | W760 | 2.095 | 0.12  | 3.9 | 8.1705  |
| W141 | 1.191 | 0.12  | 3.9 | 4.6449  | W761 | 0.882 | 0.12  | 3.9 | 3.4398  |
| W142 | 0.444 | 0.12  | 3.9 | 1.7316  | W762 | 0.254 | 0.12  | 3.9 | 0.9906  |
| W143 | 0.294 | 0.12  | 3.9 | 1.1466  | W763 | 3.49  | 0.12  | 3.9 | 13.611  |
| W144 | 2.504 | 0.123 | 3.9 | 9.7656  | W764 | 2.857 | 0.12  | 3.9 | 11.1423 |
| W145 | 1.612 | 0.12  | 3.9 | 6.2868  | W765 | 0.377 | 0.12  | 3.9 | 1.4703  |
| W146 | 1.612 | 0.117 | 3.9 | 6.2868  | W766 | 4.532 | 0.118 | 3.9 | 17.6748 |
| W147 | 0.724 | 0.12  | 3.9 | 2.8236  | W767 | 3.242 | 0.12  | 3.9 | 12.6438 |
| W148 | 0.4   | 0.12  | 3.9 | 1.56    | W768 | 0.885 | 0.12  | 3.9 | 3.4515  |
| W149 | 0.174 | 0.12  | 3.9 | 0.6786  | W769 | 0.12  | 0.132 | 3.9 | 0.468   |
| W150 | 0.126 | 0.12  | 3.9 | 0.4914  | W770 | 0.12  | 0.132 | 3.9 | 0.468   |
| W151 | 4.247 | 0.12  | 3.9 | 16.5633 | W771 | 0.772 | 0.123 | 3.9 | 3.0108  |
| W152 | 2.362 | 0.12  | 3.9 | 9.2118  | W772 | 0.184 | 0.12  | 3.9 | 0.7176  |
| W153 | 2.101 | 0.12  | 3.9 | 8.1939  | W773 | 1.6   | 0.12  | 3.9 | 6.24    |
| W154 | 1.075 | 0.12  | 3.9 | 4.1925  | W774 | 5.827 | 0.122 | 3.9 | 22.7253 |
| W155 | 0.245 | 0.12  | 3.9 | 0.9555  | W775 | 0.52  | 0.122 | 3.9 | 2.028   |
| W156 | 3.738 | 0.12  | 3.9 | 14.5782 | W776 | 0.604 | 0.122 | 3.9 | 2.3556  |
| W157 | 4.768 | 0.12  | 3.9 | 18.5952 | W777 | 0.07  | 0.05  | 3.9 | 0.273   |
| W158 | 0.13  | 0.12  | 3.9 | 0.507   | W778 | 3.739 | 0.12  | 3.9 | 14.5821 |
| W159 | 0.891 | 0.12  | 3.9 | 3.4749  | W779 | 1.415 | 0.12  | 3.9 | 5.5185  |

|      |       |       |     |         |      |        |      |     |         |
|------|-------|-------|-----|---------|------|--------|------|-----|---------|
| W160 | 0.042 | 0.12  | 3.9 | 0.1638  | W780 | 5.523  | 0.12 | 3.9 | 21.5397 |
| W161 | 1.27  | 0.12  | 3.9 | 4.953   | W781 | 0.131  | 0.12 | 3.9 | 0.5109  |
| W162 | 0.62  | 0.12  | 3.9 | 2.418   | W782 | 1.279  | 0.12 | 3.9 | 4.9881  |
| W163 | 2.493 | 0.12  | 3.9 | 9.7227  | W783 | 4.945  | 0.12 | 3.9 | 19.2855 |
| W164 | 0.377 | 0.12  | 3.9 | 1.4703  | W784 | 0.4    | 0.12 | 3.9 | 1.56    |
| W165 | 2.493 | 0.12  | 3.9 | 9.7227  | W785 | 4.202  | 0.12 | 3.9 | 16.3878 |
| W166 | 0.89  | 0.12  | 3.9 | 3.471   | W786 | 0.098  | 0.12 | 3.9 | 0.3822  |
| W167 | 3.692 | 0.12  | 3.9 | 14.3988 | W787 | 0.52   | 0.12 | 3.9 | 2.028   |
| W168 | 0.25  | 0.12  | 3.9 | 0.975   | W788 | 0.724  | 0.12 | 3.9 | 2.8236  |
| W169 | 1.813 | 0.12  | 3.9 | 7.0707  | W789 | 0.4    | 0.12 | 3.9 | 1.56    |
| W170 | 0.64  | 0.12  | 3.9 | 2.496   | W790 | 8.675  | 0.12 | 3.9 | 33.8325 |
| W171 | 0.724 | 0.12  | 3.9 | 2.8236  | W791 | 0.13   | 0.12 | 3.9 | 0.507   |
| W172 | 0.724 | 0.12  | 3.9 | 2.8236  | W792 | 2.42   | 0.12 | 3.9 | 9.438   |
| W173 | 0.4   | 0.12  | 3.9 | 1.56    | W793 | 1.088  | 0.12 | 3.9 | 4.2432  |
| W174 | 7.25  | 0.12  | 3.9 | 28.275  | W794 | 2.188  | 0.12 | 3.9 | 8.5332  |
| W175 | 7.25  | 0.12  | 3.9 | 28.275  | W795 | 0.05   | 0.12 | 3.9 | 0.195   |
| W176 | 0.64  | 0.12  | 3.9 | 2.496   | W796 | 0.071  | 0.12 | 3.9 | 0.2769  |
| W177 | 0.724 | 0.12  | 3.9 | 2.8236  | W797 | 2.45   | 0.12 | 3.9 | 9.555   |
| W178 | 0.52  | 0.12  | 3.9 | 2.028   | W798 | 0.25   | 0.12 | 3.9 | 0.975   |
| W179 | 0.604 | 0.12  | 3.9 | 2.3556  | W799 | 9.32   | 0.12 | 3.9 | 36.348  |
| W180 | 4.39  | 0.12  | 3.9 | 17.121  | W800 | 7.88   | 0.12 | 3.9 | 30.732  |
| W181 | 1.714 | 0.12  | 3.9 | 6.6846  | W801 | 3.301  | 0.12 | 3.9 | 12.8739 |
| W182 | 2.805 | 0.12  | 3.9 | 10.9395 | W802 | 0.87   | 0.12 | 3.9 | 3.393   |
| W183 | 0.73  | 0.12  | 3.9 | 2.847   | W803 | 7.987  | 0.12 | 3.9 | 31.1493 |
| W184 | 0.377 | 0.12  | 3.9 | 1.4703  | W804 | 4.18   | 0.12 | 3.9 | 16.302  |
| W185 | 2.071 | 0.12  | 3.9 | 8.0769  | W805 | 3.736  | 0.12 | 3.9 | 14.5704 |
| W186 | 0.28  | 0.12  | 3.9 | 1.092   | W806 | 2.97   | 0.12 | 3.9 | 11.583  |
| W187 | 0.503 | 0.12  | 3.9 | 1.9617  | W807 | 0.38   | 0.12 | 3.9 | 1.482   |
| W188 | 2.071 | 0.12  | 3.9 | 8.0769  | W808 | 4.261  | 0.12 | 3.9 | 16.6179 |
| W189 | 0.253 | 0.12  | 3.9 | 0.9867  | W809 | 4.44   | 0.12 | 3.9 | 17.316  |
| W190 | 2.005 | 0.12  | 3.9 | 7.8195  | W810 | 10.845 | 0.12 | 3.9 | 42.2955 |
| W191 | 1.859 | 0.12  | 3.9 | 7.2501  | W811 | 5.171  | 0.12 | 3.9 | 20.1669 |
| W192 | 0.578 | 0.12  | 3.9 | 2.2542  | W812 | 1.868  | 0.12 | 3.9 | 7.2852  |
| W193 | 0.724 | 0.12  | 3.9 | 2.8236  | W813 | 5.982  | 0.12 | 3.9 | 23.3298 |
| W194 | 0.4   | 0.123 | 3.9 | 1.56    | W814 | 3.599  | 0.12 | 3.9 | 14.0361 |
| W195 | 0.815 | 0.12  | 3.9 | 3.1785  | W815 | 4.96   | 0.12 | 3.9 | 19.344  |
| W196 | 0.12  | 0.02  | 3.9 | 0.468   | W816 | 0.251  | 0.12 | 3.9 | 0.9789  |
| W197 | 1.214 | 0.12  | 3.9 | 4.7346  | W817 | 5.019  | 0.12 | 3.9 | 19.5741 |
| W198 | 5.411 | 0.12  | 3.9 | 21.1029 | W818 | 9.018  | 0.12 | 3.9 | 35.1702 |
| W199 | 0.088 | 0.12  | 3.9 | 0.3432  | W819 | 2.662  | 0.12 | 3.9 | 10.3818 |
| W200 | 0.13  | 0.12  | 3.9 | 0.507   | W820 | 0.132  | 0.12 | 3.9 | 0.5148  |
| W201 | 4.388 | 0.12  | 3.9 | 17.1132 | W821 | 0.072  | 0.12 | 3.9 | 0.2808  |
| W202 | 0.198 | 0.12  | 3.9 | 0.7722  | W822 | 0.285  | 0.12 | 3.9 | 1.1115  |

|      |       |       |     |         |      |       |       |     |         |
|------|-------|-------|-----|---------|------|-------|-------|-----|---------|
| W203 | 3.057 | 0.12  | 3.9 | 11.9223 | W823 | 2.171 | 0.12  | 3.9 | 8.4669  |
| W204 | 0.25  | 0.12  | 3.9 | 0.975   | W824 | 2.296 | 0.12  | 3.9 | 8.9544  |
| W205 | 0.25  | 0.12  | 3.9 | 0.975   | W825 | 0.259 | 0.121 | 3.9 | 1.0101  |
| W206 | 3.03  | 0.12  | 3.9 | 11.817  | W826 | 2.363 | 0.12  | 3.9 | 9.2157  |
| W207 | 5.066 | 0.12  | 3.9 | 19.7574 | W827 | 0.05  | 0.12  | 3.9 | 0.195   |
| W208 | 7.39  | 0.12  | 3.9 | 28.821  | W828 | 0.05  | 0.12  | 3.9 | 0.195   |
| W209 | 3.353 | 0.123 | 3.9 | 13.0767 | W829 | 4.12  | 0.12  | 3.9 | 16.068  |
| W210 | 0.65  | 0.12  | 3.9 | 2.535   | W830 | 0.804 | 0.12  | 3.9 | 3.1356  |
| W211 | 0.52  | 0.123 | 3.9 | 2.028   | W831 | 5.605 | 0.12  | 3.9 | 21.8595 |
| W212 | 0.4   | 0.12  | 3.9 | 1.56    | W832 | 4.488 | 0.12  | 3.9 | 17.5032 |
| W213 | 3.904 | 0.123 | 3.9 | 15.2256 | W833 | 3.057 | 0.12  | 3.9 | 11.9223 |
| W214 | 2.358 | 0.12  | 3.9 | 9.1962  | W834 | 0.38  | 0.12  | 3.9 | 1.482   |
| W215 | 0.05  | 0.12  | 3.9 | 0.195   | W835 | 1.015 | 0.12  | 3.9 | 3.9585  |
| W216 | 0.162 | 0.12  | 3.9 | 0.6318  | W836 | 7.603 | 0.12  | 3.9 | 29.6517 |
| W217 | 4.04  | 0.12  | 3.9 | 15.756  | W837 | 4.171 | 0.12  | 3.9 | 16.2669 |
| W218 | 0.52  | 0.12  | 3.9 | 2.028   | W838 | 0.38  | 0.12  | 3.9 | 1.482   |
| W219 | 0.724 | 0.12  | 3.9 | 2.8236  | W839 | 0.316 | 0.12  | 3.9 | 1.2324  |
| W220 | 0.4   | 0.12  | 3.9 | 1.56    | W840 | 0.52  | 0.12  | 3.9 | 2.028   |
| W221 | 2.48  | 0.12  | 3.9 | 9.672   | W841 | 0.4   | 0.12  | 3.9 | 1.56    |
| W222 | 2.296 | 0.12  | 3.9 | 8.9544  | W842 | 0.52  | 0.12  | 3.9 | 2.028   |
| W223 | 0.085 | 0.12  | 3.9 | 0.3315  | W843 | 3.233 | 0.118 | 3.9 | 12.6087 |
| W224 | 0.05  | 0.12  | 3.9 | 0.195   | W844 | 1.664 | 0.12  | 3.9 | 6.4896  |
| W225 | 2.188 | 0.12  | 3.9 | 8.5332  | W845 | 2.28  | 0.12  | 3.9 | 8.892   |
| W226 | 0.071 | 0.12  | 3.9 | 0.2769  | W846 | 0.644 | 0.12  | 3.9 | 2.5116  |
| W227 | 0.201 | 0.12  | 3.9 | 0.7839  | W847 | 0.32  | 0.12  | 3.9 | 1.248   |
| W228 | 0.159 | 0.12  | 3.9 | 0.6201  | W848 | 0.6   | 0.12  | 3.9 | 2.34    |
| W229 | 2.913 | 0.64  | 3.9 | 11.3607 | W849 | 4.16  | 0.12  | 3.9 | 16.224  |
| W230 | 3.041 | 0.12  | 3.9 | 11.8599 | W850 | 0.52  | 0.12  | 3.9 | 2.028   |
| W231 | 3.041 | 0.12  | 3.9 | 11.8599 | W851 | 0.604 | 0.12  | 3.9 | 2.3556  |
| W232 | 5.02  | 0.12  | 3.9 | 19.578  | W852 | 0.52  | 0.12  | 3.9 | 2.028   |
| W233 | 4.87  | 0.12  | 3.9 | 18.993  | W853 | 8.555 | 0.12  | 3.9 | 33.3645 |
| W234 | 5.299 | 0.12  | 3.9 | 20.6661 | W854 | 2.188 | 0.12  | 3.9 | 8.5332  |
| W235 | 2.689 | 0.12  | 3.9 | 10.4871 | W855 | 2.188 | 0.12  | 3.9 | 8.5332  |
| W236 | 0.12  | 0.104 | 3.9 | 0.468   | W856 | 0.186 | 0.12  | 3.9 | 0.7254  |
| W237 | 0.12  | 0.104 | 3.9 | 0.468   | W857 | 0.179 | 0.12  | 3.9 | 0.6981  |
| W238 | 0.724 | 0.12  | 3.9 | 2.8236  | W858 | 2.296 | 0.12  | 3.9 | 8.9544  |
| W239 | 0.724 | 0.12  | 3.9 | 2.8236  | W859 | 2.157 | 0.12  | 3.9 | 8.4123  |
| W240 | 0.4   | 0.12  | 3.9 | 1.56    | W860 | 0.417 | 0.12  | 3.9 | 1.6263  |
| W241 | 2.28  | 0.12  | 3.9 | 8.892   | W861 | 0.093 | 0.12  | 3.9 | 0.3627  |
| W242 | 2.182 | 0.12  | 3.9 | 8.5098  | W862 | 0.32  | 0.12  | 3.9 | 1.248   |
| W243 | 0.05  | 0.12  | 3.9 | 0.195   | W863 | 0.263 | 0.12  | 3.9 | 1.0257  |
| W244 | 2.189 | 0.12  | 3.9 | 8.5371  | W864 | 2.731 | 0.12  | 3.9 | 10.6509 |
| W245 | 0.05  | 0.12  | 3.9 | 0.195   | W865 | 1.899 | 0.12  | 3.9 | 7.4061  |

|      |       |       |     |         |      |       |       |     |         |
|------|-------|-------|-----|---------|------|-------|-------|-----|---------|
| W246 | 4.56  | 0.12  | 3.9 | 17.784  | W866 | 2.258 | 0.12  | 3.9 | 8.8062  |
| W247 | 0.12  | 0.08  | 3.9 | 0.468   | W867 | 0.05  | 0.12  | 3.9 | 0.195   |
| W248 | 0.12  | 0.08  | 3.9 | 0.468   | W868 | 0.085 | 0.12  | 3.9 | 0.3315  |
| W249 | 0.12  | 0.08  | 3.9 | 0.468   | W869 | 0.05  | 0.12  | 3.9 | 0.195   |
| W250 | 5.278 | 0.12  | 3.9 | 20.5842 | W870 | 0.071 | 0.12  | 3.9 | 0.2769  |
| W251 | 2.267 | 0.12  | 3.9 | 8.8413  | W871 | 2.59  | 0.12  | 3.9 | 10.101  |
| W252 | 0.38  | 0.12  | 3.9 | 1.482   | W872 | 0.13  | 0.12  | 3.9 | 0.507   |
| W253 | 0.88  | 0.12  | 3.9 | 3.432   | W873 | 3.563 | 0.12  | 3.9 | 13.8957 |
| W254 | 0.203 | 0.12  | 3.9 | 0.7917  | W874 | 0.13  | 0.11  | 3.9 | 0.507   |
| W255 | 0.203 | 0.12  | 3.9 | 0.7917  | W875 | 1.399 | 0.12  | 3.9 | 5.4561  |
| W256 | 7.393 | 0.12  | 3.9 | 28.8327 | W876 | 2.47  | 0.12  | 3.9 | 9.633   |
| W257 | 0.12  | 0.08  | 3.9 | 0.468   | W877 | 2.11  | 0.12  | 3.9 | 8.229   |
| W258 | 0.12  | 0.08  | 3.9 | 0.468   | W878 | 0.37  | 0.88  | 3.9 | 1.443   |
| W259 | 4.56  | 0.12  | 3.9 | 17.784  | W879 | 3.15  | 0.12  | 3.9 | 12.285  |
| W260 | 2.184 | 0.12  | 3.9 | 8.5176  | W880 | 0.25  | 0.12  | 3.9 | 0.975   |
| W261 | 0.05  | 0.12  | 3.9 | 0.195   | W881 | 2.882 | 0.12  | 3.9 | 11.2398 |
| W262 | 2.48  | 0.12  | 3.9 | 9.672   | W882 | 2.47  | 0.12  | 3.9 | 9.633   |
| W263 | 0.844 | 0.12  | 3.9 | 3.2916  | W883 | 0.25  | 0.12  | 3.9 | 0.975   |
| W264 | 0.399 | 0.12  | 3.9 | 1.5561  | W884 | 2.001 | 0.12  | 3.9 | 7.8039  |
| W265 | 0.4   | 0.12  | 3.9 | 1.56    | W885 | 2.248 | 0.12  | 3.9 | 8.7672  |
| W266 | 0.12  | 0.08  | 3.9 | 0.468   | W886 | 2.26  | 0.117 | 3.9 | 8.814   |
| W267 | 0.12  | 0.08  | 3.9 | 0.468   | W887 | 0.132 | 0.12  | 3.9 | 0.5148  |
| W268 | 2.184 | 0.12  | 3.9 | 8.5176  | W888 | 5.624 | 0.12  | 3.9 | 21.9336 |
| W269 | 0.071 | 0.12  | 3.9 | 0.2769  | W889 | 5.121 | 0.12  | 3.9 | 19.9719 |
| W270 | 2.689 | 0.12  | 3.9 | 10.4871 | W890 | 1.354 | 0.12  | 3.9 | 5.2806  |
| W271 | 5.324 | 0.12  | 3.9 | 20.7636 | W891 | 0.724 | 0.12  | 3.9 | 2.8236  |
| W272 | 4.238 | 0.12  | 3.9 | 16.5282 | W892 | 0.4   | 0.12  | 3.9 | 1.56    |
| W273 | 0.085 | 0.12  | 3.9 | 0.3315  | W893 | 0.18  | 0.12  | 3.9 | 0.702   |
| W274 | 0.05  | 0.12  | 3.9 | 0.195   | W894 | 0.43  | 0.12  | 3.9 | 1.677   |
| W275 | 4.33  | 0.12  | 3.9 | 16.887  | W895 | 1.99  | 0.12  | 3.9 | 7.761   |
| W276 | 5.898 | 0.12  | 3.9 | 23.0022 | W896 | 2.569 | 0.12  | 3.9 | 10.0191 |
| W277 | 2.395 | 0.12  | 3.9 | 9.3405  | W897 | 3.001 | 0.12  | 3.9 | 11.7039 |
| W278 | 2.48  | 0.12  | 3.9 | 9.672   | W898 | 2.861 | 0.12  | 3.9 | 11.1579 |
| W279 | 0.844 | 0.12  | 3.9 | 3.2916  | W899 | 1.47  | 0.12  | 3.9 | 5.733   |
| W280 | 0.4   | 0.12  | 3.9 | 1.56    | W900 | 1.109 | 0.12  | 3.9 | 4.3251  |
| W281 | 0.4   | 0.12  | 3.9 | 1.56    | W901 | 0.4   | 0.12  | 3.9 | 1.56    |
| W282 | 2.188 | 0.12  | 3.9 | 8.5332  | W902 | 0.4   | 0.095 | 3.9 | 1.56    |
| W283 | 2.188 | 0.12  | 3.9 | 8.5332  | W903 | 0.25  | 0.12  | 3.9 | 0.975   |
| W284 | 4.16  | 0.12  | 3.9 | 16.224  | W904 | 4.091 | 0.12  | 3.9 | 15.9549 |
| W285 | 0.224 | 0.12  | 3.9 | 0.8736  | W905 | 0.25  | 0.12  | 3.9 | 0.975   |
| W286 | 0.136 | 0.12  | 4.2 | 0.5712  | W906 | 0.25  | 0.12  | 3.9 | 0.975   |
| W287 | 0.12  | 0.104 | 3.9 | 0.468   | W907 | 1.851 | 0.12  | 3.9 | 7.2189  |
| W288 | 0.12  | 0.104 | 3.9 | 0.468   | W908 | 0.4   | 0.13  | 3.9 | 1.56    |

|      |       |       |     |         |      |       |        |     |         |
|------|-------|-------|-----|---------|------|-------|--------|-----|---------|
| W289 | 0.05  | 0.12  | 3.9 | 0.195   | W909 | 0.394 | 0.25   | 3.9 | 1.5366  |
| W290 | 0.05  | 0.12  | 3.9 | 0.195   | W910 | 3.21  | 0.12   | 3.9 | 12.519  |
| W291 | 0.08  | 0.12  | 3.9 | 0.312   | W911 | 2.232 | 0.12   | 3.9 | 8.7048  |
| W292 | 0.08  | 0.12  | 3.9 | 0.312   | W912 | 0.23  | 0.12   | 3.9 | 0.897   |
| W293 | 6.774 | 0.12  | 3.9 | 26.4186 | W913 | 0.095 | 0.116  | 3.9 | 0.3705  |
| W294 | 0.64  | 0.12  | 3.9 | 2.496   | W914 | 3.925 | 0.12   | 3.9 | 15.3075 |
| W295 | 0.496 | 0.12  | 3.9 | 1.9344  | W915 | 8.194 | 0.12   | 3.9 | 31.9566 |
| W296 | 0.52  | 0.096 | 3.9 | 2.028   | W916 | 0.13  | 0.12   | 3.9 | 0.507   |
| W297 | 0.4   | 0.12  | 3.9 | 1.56    | W917 | 5.111 | 0.12   | 3.9 | 19.9329 |
| W298 | 0.9   | 0.12  | 3.9 | 3.51    | W918 | 1.38  | 0.12   | 3.9 | 5.382   |
| W299 | 0.9   | 0.12  | 3.9 | 3.51    | W919 | 1.63  | 0.12   | 3.9 | 6.357   |
| W300 | 0.52  | 0.12  | 3.9 | 2.028   | W920 | 1.475 | 0.12   | 3.9 | 5.7525  |
| W301 | 0.52  | 0.12  | 3.9 | 2.028   | W921 | 1.38  | 0.12   | 3.9 | 5.382   |
| W302 | 0.4   | 0.12  | 3.9 | 1.56    | W922 | 2.569 | 0.12   | 3.9 | 10.0191 |
| W303 | 2.713 | 0.12  | 3.9 | 10.5807 | W923 | 0.25  | 0.12   | 3.9 | 0.975   |
| W304 | 0.226 | 0.12  | 3.9 | 0.8814  | W924 | 2.681 | 0.12   | 3.9 | 10.4559 |
| W305 | 4.254 | 0.12  | 3.9 | 16.5906 | W925 | 2.17  | 0.12   | 3.9 | 8.463   |
| W306 | 0.134 | 0.12  | 3.9 | 0.5226  | W926 | 0.376 | 0.12   | 3.9 | 1.4664  |
| W307 | 0.12  | 0.05  | 3.9 | 0.468   | W927 | 2.242 | 0.12   | 3.9 | 8.7438  |
| W308 | 4.194 | 0.12  | 3.9 | 16.3566 | W928 | 0.132 | 0.12   | 3.9 | 0.5148  |
| W309 | 2.188 | 0.12  | 3.9 | 8.5332  | W929 | 9.018 | 0.12   | 3.9 | 35.1702 |
| W310 | 0.52  | 0.12  | 3.9 | 2.028   | W930 | 2.022 | 0.12   | 3.9 | 7.8858  |
| W311 | 0.724 | 0.12  | 3.9 | 2.8236  | W931 | 2.223 | 0.12   | 3.9 | 8.6697  |
| W312 | 0.4   | 0.12  | 3.9 | 1.56    | W932 | 0.173 | 0.12   | 3.9 | 0.6747  |
| W313 | 2.48  | 0.12  | 3.9 | 9.672   | W933 | 0.173 | 0.12   | 3.9 | 0.6747  |
| W314 | 2.296 | 0.12  | 3.9 | 8.9544  | W934 | 0.521 | 0.12   | 3.9 | 2.0319  |
| W315 | 2.188 | 0.12  | 3.9 | 8.5332  | W935 | 0.604 | 0.12   | 3.9 | 2.3556  |
| W316 | 0.186 | 0.12  | 3.9 | 0.7254  | W936 | 0.18  | 0.15   | 3.9 | 0.702   |
| W317 | 3.046 | 0.64  | 3.9 | 11.8794 | W937 | 1.08  | 0.12   | 3.9 | 4.212   |
| W318 | 2.908 | 0.12  | 3.9 | 11.3412 | W938 | 2.188 | 0.123  | 3.9 | 8.5332  |
| W319 | 2.908 | 0.12  | 3.9 | 11.3412 | W939 | 2.233 | 0.12   | 3.9 | 8.7087  |
| W320 | 5.02  | 0.12  | 3.9 | 19.578  | W940 | 0.183 | 0.12   | 3.9 | 0.7137  |
| W321 | 0.05  | 0.12  | 3.9 | 0.195   | W941 | 0.18  | 0.12   | 3.9 | 0.702   |
| W322 | 0.085 | 0.12  | 3.9 | 0.3315  | W942 | 2.908 | 0.12   | 3.9 | 11.3412 |
| W323 | 0.071 | 0.12  | 3.9 | 0.2769  | W943 | 1.13  | 0.12   | 3.9 | 4.407   |
| W324 | 0.05  | 0.12  | 3.9 | 0.195   | W944 | 0.12  | 0.104  | 3.9 | 0.468   |
| W325 | 4.595 | 0.12  | 3.9 | 17.9205 | W945 | 0.05  | 0.12   | 3.9 | 0.195   |
| W326 | 5.299 | 0.12  | 3.9 | 20.6661 | W946 | 1.08  | 0.12   | 3.9 | 4.212   |
| W327 | 2.689 | 0.12  | 3.9 | 10.4871 | W947 | 0.05  | 0.12   | 3.9 | 0.195   |
| W328 | 0.724 | 0.12  | 3.9 | 2.8236  | W948 | 2.438 | 0.12   | 3.9 | 9.5082  |
| W329 | 0.52  | 0.12  | 3.9 | 2.028   | W949 | 3.057 | 0.12   | 3.9 | 11.9223 |
| W330 | 0.604 | 0.12  | 3.9 | 2.3556  | W950 | 0.64  | 12.036 | 3.9 | 2.496   |
| W331 | 2.28  | 0.12  | 3.9 | 8.892   | W951 | 2.506 | 0.11   | 3.9 | 9.7734  |

|      |       |       |     |         |      |       |       |     |        |
|------|-------|-------|-----|---------|------|-------|-------|-----|--------|
| W332 | 2.182 | 0.12  | 3.9 | 8.5098  | W952 | 2.157 | 0.12  | 3.9 | 8.4123 |
| W333 | 2.189 | 0.12  | 3.9 | 8.5371  | W953 | 0.83  | 0.12  | 3.9 | 3.237  |
| W334 | 4.56  | 0.12  | 3.9 | 17.784  | W954 | 1.897 | 1.14  | 3.9 | 7.3983 |
| W335 | 0.08  | 0.12  | 3.9 | 0.312   | W955 | 1.433 | 0.65  | 3.9 | 5.5887 |
| W336 | 0.08  | 0.12  | 3.9 | 0.312   | W956 | 0.25  | 0.13  | 3.9 | 0.975  |
| W337 | 0.12  | 0.104 | 3.9 | 0.468   | W957 | 6.19  | 0.12  | 3.9 | 24.141 |
| W338 | 0.05  | 0.12  | 3.9 | 0.195   | W958 | 0.52  | 0.12  | 3.9 | 2.028  |
| W339 | 0.12  | 0.104 | 3.9 | 0.468   | W959 | 0.604 | 0.12  | 3.9 | 2.3556 |
| W340 | 0.05  | 0.12  | 3.9 | 0.195   | W960 | 1.45  | 0.12  | 3.9 | 5.655  |
| W341 | 4.56  | 0.12  | 3.9 | 17.784  | W961 | 5.52  | 0.12  | 3.9 | 21.528 |
| W342 | 2.184 | 0.12  | 3.9 | 8.5176  | W962 | 1.3   | 1.196 | 3.9 | 5.07   |
| W343 | 2.48  | 0.12  | 3.9 | 9.672   | W963 | 2.023 | 0.12  | 3.9 | 7.8897 |
| W344 | 0.844 | 0.12  | 3.9 | 3.2916  | W964 | 1.961 | 0.12  | 3.9 | 7.6479 |
| W345 | 0.399 | 0.12  | 3.9 | 1.5561  | W965 | 0.085 | 0.12  | 3.9 | 0.3315 |
| W346 | 0.4   | 0.12  | 3.9 | 1.56    | WD1  | 0.12  | 1.1   | 1.7 | 0.204  |
| W347 | 2.689 | 0.12  | 3.9 | 10.4871 | WD2  | 0.12  | 1.3   | 1.7 | 0.204  |
| W348 | 2.184 | 0.12  | 3.9 | 8.5176  | WD3  | 0.12  | 1.3   | 1.7 | 0.204  |
| W349 | 0.08  | 0.12  | 3.9 | 0.312   | WD4  | 0.12  | 1.3   | 1.7 | 0.204  |
| W350 | 0.08  | 0.12  | 3.9 | 0.312   | WD5  | 0.12  | 1.1   | 1.7 | 0.204  |
| W351 | 0.08  | 0.12  | 3.9 | 0.312   | WD6  | 0.12  | 1.3   | 1.7 | 0.204  |
| W352 | 5.324 | 0.12  | 3.9 | 20.7636 | WD7  | 0.12  | 1.3   | 1.7 | 0.204  |
| W353 | 4.671 | 0.12  | 3.9 | 18.2169 | WD8  | 0.12  | 1.1   | 1.7 | 0.204  |
| W354 | 4.67  | 0.12  | 3.9 | 18.213  | WD9  | 0.05  | 0.802 | 1.7 | 0.085  |
| W355 | 5.898 | 0.12  | 3.9 | 23.0022 | WD10 | 0.05  | 0.802 | 1.7 | 0.085  |
| W356 | 2.296 | 0.12  | 3.9 | 8.9544  | WD11 | 0.12  | 1.102 | 1.7 | 0.204  |
| W357 | 2.48  | 0.12  | 3.9 | 9.672   | WD12 | 0.05  | 0.802 | 1.7 | 0.085  |
| W358 | 0.844 | 0.12  | 3.9 | 3.2916  | WD13 | 0.05  | 1.14  | 1.7 | 0.085  |
| W359 | 0.4   | 0.12  | 3.9 | 1.56    | WD14 | 0.12  | 1.102 | 1.7 | 0.204  |
| W360 | 0.4   | 0.12  | 3.9 | 1.56    | WD15 | 0.124 | 0.9   | 1.7 | 0.2108 |
| W361 | 2.188 | 0.12  | 3.9 | 8.5332  | WD16 | 0.12  | 1.1   | 1.7 | 0.204  |
| W362 | 4.267 | 0.12  | 3.9 | 16.6413 | WD17 | 0.12  | 1.3   | 1.7 | 0.204  |
| W363 | 2.188 | 0.12  | 3.9 | 8.5332  | WD18 | 0.12  | 1.3   | 1.7 | 0.204  |
| W364 | 0.05  | 0.12  | 3.9 | 0.195   | WD19 | 0.12  | 1.681 | 1.7 | 0.204  |
| W365 | 0.05  | 0.12  | 3.9 | 0.195   | WD20 | 0.12  | 1.3   | 1.7 | 0.204  |
| W366 | 0.12  | 0.104 | 3.9 | 0.468   | WD21 | 0.12  | 1.102 | 1.7 | 0.204  |
| W367 | 0.12  | 0.104 | 3.9 | 0.468   | WD22 | 0.12  | 0.9   | 1.7 | 0.204  |
| W368 | 0.085 | 0.12  | 3.9 | 0.3315  | WD23 | 0.12  | 0.9   | 1.7 | 0.204  |
| W369 | 0.05  | 0.12  | 3.9 | 0.195   | WD24 | 0.12  | 1.5   | 1.7 | 0.204  |
| W370 | 0.071 | 0.12  | 3.9 | 0.2769  | WD25 | 0.12  | 1     | 1.7 | 0.204  |
| W371 | 0.05  | 0.12  | 3.9 | 0.195   | WD26 | 0.12  | 1.3   | 1.7 | 0.204  |
| W372 | 5.369 | 0.12  | 3.9 | 20.9391 | WD27 | 0.12  | 1     | 1.7 | 0.204  |
| W373 | 1.577 | 0.12  | 3.9 | 6.1503  | WD28 | 0.12  | 1.3   | 1.7 | 0.204  |
| W374 | 0.38  | 0.12  | 3.9 | 1.482   | WD29 | 0.12  | 0.9   | 1.7 | 0.204  |



|      |       |      |     |         |      |      |       |     |       |
|------|-------|------|-----|---------|------|------|-------|-----|-------|
| W375 | 0.622 | 0.12 | 3.9 | 2.4258  | WD30 | 0.12 | 0.9   | 1.7 | 0.204 |
| W376 | 0.193 | 0.4  | 3.9 | 0.7527  | WD31 | 0.12 | 1     | 1.7 | 0.204 |
| W377 | 4.82  | 0.12 | 3.9 | 18.798  | WD32 | 0.12 | 0.9   | 1.7 | 0.204 |
| W378 | 0.28  | 0.12 | 3.9 | 1.092   | WD33 | 0.12 | 0.9   | 1.7 | 0.204 |
| W379 | 1.363 | 0.12 | 3.9 | 5.3157  | WD34 | 0.12 | 0.9   | 1.7 | 0.204 |
| W380 | 5.91  | 0.12 | 3.9 | 23.049  | WD35 | 0.12 | 0.9   | 1.7 | 0.204 |
| W381 | 0.08  | 0.12 | 3.9 | 0.312   | WD36 | 0.12 | 0.9   | 1.7 | 0.204 |
| W382 | 0.08  | 0.12 | 3.9 | 0.312   | WD37 | 0.12 | 0.9   | 1.7 | 0.204 |
| W383 | 1.204 | 0.12 | 3.9 | 4.6956  | WD38 | 0.12 | 0.9   | 1.7 | 0.204 |
| W384 | 0.559 | 0.12 | 3.9 | 2.1801  | WD39 | 0.12 | 0.9   | 1.7 | 0.204 |
| W385 | 0.38  | 0.12 | 3.9 | 1.482   | WD40 | 0.12 | 1     | 1.7 | 0.204 |
| W386 | 4.093 | 0.12 | 3.9 | 15.9627 | WD41 | 0.12 | 0.9   | 1.7 | 0.204 |
| W387 | 2.744 | 0.12 | 3.9 | 10.7016 | WD42 | 0.12 | 1.102 | 1.7 | 0.204 |
| W388 | 0.224 | 0.12 | 3.9 | 0.8736  | WD43 | 0.12 | 1.102 | 1.7 | 0.204 |
| W389 | 0.064 | 0.12 | 3.9 | 0.2496  | WD44 | 0.12 | 1.303 | 1.7 | 0.204 |
| W390 | 0.198 | 0.12 | 3.9 | 0.7722  | WD45 | 0.12 | 1.3   | 1.7 | 0.204 |
| W391 | 2.308 | 0.12 | 3.9 | 9.0012  | WD46 | 0.12 | 1.3   | 1.7 | 0.204 |
| W392 | 0.162 | 0.12 | 3.9 | 0.6318  | WD47 | 0.12 | 1.3   | 1.7 | 0.204 |
| W393 | 4.04  | 0.12 | 3.9 | 15.756  | WD48 | 0.12 | 1.102 | 1.7 | 0.204 |
| W394 | 2.188 | 0.12 | 3.9 | 8.5332  | WD49 | 0.12 | 1.102 | 1.7 | 0.204 |
| W395 | 0.52  | 0.12 | 3.9 | 2.028   | WD50 | 0.12 | 1.102 | 1.7 | 0.204 |
| W396 | 0.724 | 0.12 | 3.9 | 2.8236  | WD51 | 0.12 | 1.102 | 1.7 | 0.204 |
| W397 | 0.4   | 0.12 | 3.9 | 1.56    | WD52 | 0.12 | 1.3   | 1.7 | 0.204 |
| W398 | 2.48  | 0.12 | 3.9 | 9.672   | WD53 | 0.12 | 1.3   | 1.7 | 0.204 |
| W399 | 2.296 | 0.12 | 3.9 | 8.9544  | WD54 | 0.12 | 1.3   | 1.7 | 0.204 |
| W400 | 0.201 | 0.12 | 3.9 | 0.7839  | WD55 | 0.12 | 1.3   | 1.7 | 0.204 |
| W401 | 3.622 | 0.64 | 3.9 | 14.1258 | WD56 | 0.12 | 1.102 | 1.7 | 0.204 |
| W402 | 2.332 | 0.12 | 3.9 | 9.0948  | WD57 | 0.12 | 1.102 | 1.7 | 0.204 |
| W403 | 2.332 | 0.12 | 3.9 | 9.0948  | WD58 | 0.12 | 1.102 | 1.7 | 0.204 |
| W404 | 5.02  | 0.12 | 3.9 | 19.578  | WD59 | 0.12 | 1.102 | 1.7 | 0.204 |
| W405 | 0.159 | 0.12 | 3.9 | 0.6201  | WD60 | 0.12 | 1.3   | 1.7 | 0.204 |
| W406 | 4.854 | 0.12 | 3.9 | 18.9306 | WD61 | 0.12 | 1.3   | 1.7 | 0.204 |
| W407 | 5.299 | 0.12 | 3.9 | 20.6661 | WD62 | 0.12 | 1.3   | 1.7 | 0.204 |
| W408 | 2.689 | 0.12 | 3.9 | 10.4871 | WD63 | 0.12 | 1.3   | 1.7 | 0.204 |
| W409 | 0.724 | 0.12 | 3.9 | 2.8236  | WD64 | 0.12 | 1.102 | 1.7 | 0.204 |
| W410 | 0.52  | 0.12 | 3.9 | 2.028   | WD65 | 0.12 | 1.102 | 1.7 | 0.204 |
| W411 | 0.604 | 0.12 | 3.9 | 2.3556  | WD66 | 0.12 | 1.102 | 1.7 | 0.204 |
| W412 | 2.28  | 0.12 | 3.9 | 8.892   | WD67 | 0.12 | 1.102 | 1.7 | 0.204 |
| W413 | 4.56  | 0.12 | 3.9 | 17.784  | WD68 | 0.12 | 1.3   | 1.7 | 0.204 |
| W414 | 2.182 | 0.12 | 3.9 | 8.5098  | WD69 | 0.12 | 1.3   | 1.7 | 0.204 |
| W415 | 0.12  | 0.08 | 3.9 | 0.468   | WD70 | 0.12 | 1.3   | 1.7 | 0.204 |
| W416 | 2.189 | 0.12 | 3.9 | 8.5371  | WD71 | 0.12 | 1.3   | 1.7 | 0.204 |
| W417 | 0.12  | 0.08 | 3.9 | 0.468   | WD72 | 0.12 | 1.102 | 1.7 | 0.204 |


|      |       |       |     |         |       |       |       |     |        |
|------|-------|-------|-----|---------|-------|-------|-------|-----|--------|
| W418 | 0.12  | 0.08  | 3.9 | 0.468   | WD73  | 0.12  | 1.102 | 1.7 | 0.204  |
| W419 | 0.05  | 0.12  | 3.9 | 0.195   | WD74  | 0.12  | 1.102 | 1.7 | 0.204  |
| W420 | 0.12  | 0.104 | 3.9 | 0.468   | WD75  | 0.12  | 1.102 | 1.7 | 0.204  |
| W421 | 0.05  | 0.12  | 3.9 | 0.195   | WD76  | 0.12  | 1.3   | 1.7 | 0.204  |
| W422 | 0.12  | 0.104 | 3.9 | 0.468   | WD77  | 0.12  | 1.3   | 1.7 | 0.204  |
| W423 | 0.085 | 0.12  | 3.9 | 0.3315  | WD78  | 0.12  | 1.3   | 1.7 | 0.204  |
| W424 | 0.05  | 0.12  | 3.9 | 0.195   | WD79  | 0.12  | 1.3   | 1.7 | 0.204  |
| W425 | 0.071 | 0.12  | 3.9 | 0.2769  | WD80  | 0.12  | 1.102 | 1.7 | 0.204  |
| W426 | 0.05  | 0.12  | 3.9 | 0.195   | WD81  | 0.12  | 1.102 | 1.7 | 0.204  |
| W427 | 5.218 | 0.12  | 3.9 | 20.3502 | WD82  | 0.12  | 1.102 | 1.7 | 0.204  |
| W428 | 1.727 | 0.12  | 3.9 | 6.7353  | WD83  | 0.12  | 1.102 | 1.7 | 0.204  |
| W429 | 0.38  | 0.12  | 3.9 | 1.482   | WD84  | 0.12  | 1.3   | 1.7 | 0.204  |
| W430 | 0.379 | 0.12  | 3.9 | 1.4781  | WD85  | 0.12  | 1.3   | 1.7 | 0.204  |
| W431 | 1.693 | 0.12  | 3.9 | 6.6027  | WD86  | 0.12  | 1.3   | 1.7 | 0.204  |
| W432 | 5.753 | 0.12  | 3.9 | 22.4367 | WD87  | 0.12  | 1.3   | 1.7 | 0.204  |
| W433 | 6.35  | 0.12  | 3.9 | 24.765  | WD88  | 0.12  | 1.102 | 1.7 | 0.204  |
| W434 | 0.08  | 0.12  | 3.9 | 0.312   | WD89  | 0.12  | 1.102 | 1.7 | 0.204  |
| W435 | 0.08  | 0.12  | 3.9 | 0.312   | WD90  | 0.12  | 1.102 | 1.7 | 0.204  |
| W436 | 0.914 | 0.12  | 3.9 | 3.5646  | WD91  | 0.12  | 1.102 | 1.7 | 0.204  |
| W437 | 0.5   | 0.12  | 3.9 | 1.95    | WD92  | 0.12  | 1.3   | 1.7 | 0.204  |
| W438 | 0.38  | 0.12  | 3.9 | 1.482   | WD93  | 0.12  | 1.3   | 1.7 | 0.204  |
| W439 | 1.391 | 0.12  | 3.9 | 5.4249  | WD94  | 0.12  | 1.3   | 1.7 | 0.204  |
| W440 | 0.64  | 0.12  | 3.9 | 2.496   | WD95  | 0.12  | 1.3   | 1.7 | 0.204  |
| W441 | 0.52  | 0.12  | 3.9 | 2.028   | WD96  | 0.12  | 1.102 | 1.7 | 0.204  |
| W442 | 0.52  | 0.12  | 3.9 | 2.028   | WD97  | 0.12  | 1.102 | 1.7 | 0.204  |
| W443 | 0.4   | 0.12  | 3.9 | 1.56    | WD98  | 0.12  | 1.102 | 1.7 | 0.204  |
| W444 | 1.362 | 0.12  | 3.9 | 5.3118  | WD99  | 0.12  | 1.102 | 1.7 | 0.204  |
| W445 | 2.744 | 0.12  | 3.9 | 10.7016 | WD100 | 0.12  | 1.3   | 1.7 | 0.204  |
| W446 | 0.134 | 0.12  | 3.9 | 0.5226  | WD101 | 0.12  | 1.3   | 1.7 | 0.204  |
| W447 | 4.56  | 0.12  | 3.9 | 17.784  | WD102 | 0.12  | 1.3   | 1.7 | 0.204  |
| W448 | 2.184 | 0.12  | 3.9 | 8.5176  | WD103 | 0.12  | 1.3   | 1.7 | 0.204  |
| W449 | 2.184 | 0.12  | 3.9 | 8.5176  | WD104 | 0.12  | 1.102 | 1.7 | 0.204  |
| W450 | 2.48  | 0.12  | 3.9 | 9.672   | WD105 | 0.12  | 1.102 | 1.7 | 0.204  |
| W451 | 0.844 | 0.12  | 3.9 | 3.2916  | WD106 | 0.12  | 1.102 | 1.7 | 0.204  |
| W452 | 0.399 | 0.12  | 3.9 | 1.5561  | WD107 | 0.12  | 1.102 | 1.7 | 0.204  |
| W453 | 0.4   | 0.12  | 3.9 | 1.56    | WD108 | 0.12  | 1.3   | 1.7 | 0.204  |
| W454 | 2.689 | 0.12  | 3.9 | 10.4871 | WD109 | 0.12  | 1.3   | 1.7 | 0.204  |
| W455 | 0.08  | 0.12  | 3.9 | 0.312   | WD110 | 0.136 | 1.3   | 1.7 | 0.2312 |
| W456 | 0.08  | 0.12  | 3.9 | 0.312   | WD111 | 0.12  | 1.3   | 1.7 | 0.204  |
| W457 | 5.324 | 0.12  | 3.9 | 20.7636 | WD112 | 0.12  | 1.102 | 1.7 | 0.204  |
| W458 | 4.838 | 0.12  | 3.9 | 18.8682 | WD113 | 0.12  | 1.102 | 1.7 | 0.204  |
| W459 | 5.02  | 0.12  | 3.9 | 19.578  | WD114 | 0.12  | 1.102 | 1.7 | 0.204  |
| W460 | 5.898 | 0.12  | 3.9 | 23.0022 | WD115 | 0.12  | 1.102 | 1.7 | 0.204  |

|      |       |       |     |         |       |      |       |     |       |
|------|-------|-------|-----|---------|-------|------|-------|-----|-------|
| W461 | 2.296 | 0.12  | 3.9 | 8.9544  | WD116 | 0.12 | 1.3   | 1.7 | 0.204 |
| W462 | 2.48  | 0.12  | 3.9 | 9.672   | WD117 | 0.12 | 1.3   | 1.7 | 0.204 |
| W463 | 2.188 | 0.12  | 3.9 | 8.5332  | WD118 | 0.12 | 1.3   | 1.7 | 0.204 |
| W464 | 2.188 | 0.12  | 3.9 | 8.5332  | WD119 | 0.12 | 1.3   | 1.7 | 0.204 |
| W465 | 0.844 | 0.12  | 3.9 | 3.2916  | WD120 | 0.12 | 1.102 | 1.7 | 0.204 |
| W466 | 0.4   | 0.12  | 3.9 | 1.56    | WD121 | 0.12 | 1.102 | 1.7 | 0.204 |
| W467 | 0.4   | 0.12  | 3.9 | 1.56    | WD122 | 0.12 | 1.102 | 1.7 | 0.204 |
| W468 | 4.16  | 0.12  | 3.9 | 16.224  | WD123 | 0.12 | 1.102 | 1.7 | 0.204 |
| W469 | 0.136 | 0.12  | 3.9 | 0.5304  | WD124 | 0.12 | 1.3   | 1.7 | 0.204 |
| W470 | 0.226 | 0.12  | 3.9 | 0.8814  | WD125 | 0.12 | 1.3   | 1.7 | 0.204 |
| W471 | 0.05  | 0.12  | 3.9 | 0.195   | WD126 | 0.12 | 1.6   | 1.7 | 0.204 |
| W472 | 0.12  | 0.104 | 3.9 | 0.468   | WD127 | 0.12 | 1.6   | 1.7 | 0.204 |
| W473 | 0.05  | 0.12  | 3.9 | 0.195   | WD128 | 0.12 | 1.3   | 1.7 | 0.204 |
| W474 | 0.12  | 0.104 | 3.9 | 0.468   | WD129 | 0.12 | 1.3   | 1.7 | 0.204 |
| W475 | 0.085 | 0.12  | 3.9 | 0.3315  | WD130 | 0.12 | 1.102 | 1.7 | 0.204 |
| W476 | 0.05  | 0.12  | 3.9 | 0.195   | WD131 | 0.12 | 1.102 | 1.7 | 0.204 |
| W477 | 0.071 | 0.12  | 3.9 | 0.2769  | WD132 | 0.12 | 1.5   | 1.7 | 0.204 |
| W478 | 0.05  | 0.12  | 3.9 | 0.195   | WD133 | 0.12 | 1.5   | 1.7 | 0.204 |
| W479 | 0.4   | 0.12  | 3.9 | 1.56    | WD134 | 0.12 | 1.5   | 1.7 | 0.204 |
| W480 | 4.205 | 0.12  | 3.9 | 16.3995 | WD135 | 0.12 | 1.5   | 1.7 | 0.204 |
| W481 | 2.188 | 0.12  | 3.9 | 8.5332  | WD136 | 0.12 | 1.5   | 1.7 | 0.204 |
| W482 | 2.188 | 0.12  | 3.9 | 8.5332  | WD137 | 0.12 | 1.5   | 1.7 | 0.204 |
| W483 | 0.52  | 0.12  | 3.9 | 2.028   | WD138 | 0.12 | 1.5   | 1.7 | 0.204 |
| W484 | 0.724 | 0.12  | 3.9 | 2.8236  | WD139 | 0.12 | 1.5   | 1.7 | 0.204 |
| W485 | 0.4   | 0.12  | 3.9 | 1.56    | WD140 | 0.12 | 1.5   | 1.7 | 0.204 |
| W486 | 2.48  | 0.12  | 3.9 | 9.672   | WD141 | 0.12 | 1.5   | 1.7 | 0.204 |
| W487 | 2.296 | 0.12  | 3.9 | 8.9544  | WD142 | 0.12 | 1.5   | 1.7 | 0.204 |
| W488 | 5.955 | 0.12  | 3.9 | 23.2245 | WD143 | 0.12 | 1.5   | 1.7 | 0.204 |
| W489 | 5.02  | 0.12  | 3.9 | 19.578  | WD144 | 0.12 | 1.5   | 1.7 | 0.204 |
| W490 | 5.021 | 0.12  | 3.9 | 19.5819 | WD145 | 0.12 | 1.5   | 1.7 | 0.204 |
| W491 | 5.299 | 0.12  | 3.9 | 20.6661 | WD146 | 0.09 | 1.5   | 1.7 | 0.153 |
| W492 | 2.689 | 0.12  | 3.9 | 10.4871 | WD147 | 0.12 | 1.5   | 1.7 | 0.204 |
| W493 | 0.724 | 0.12  | 3.9 | 2.8236  | WD148 | 0.12 | 1.5   | 1.7 | 0.204 |
| W494 | 0.724 | 0.12  | 3.9 | 2.8236  | WD149 | 0.12 | 1.5   | 1.7 | 0.204 |
| W495 | 0.4   | 0.12  | 3.9 | 1.56    | WD150 | 0.12 | 1.5   | 1.7 | 0.204 |
| W496 | 2.28  | 0.12  | 3.9 | 8.892   | WD151 | 0.12 | 1.5   | 1.7 | 0.204 |
| W497 | 2.182 | 0.12  | 3.9 | 8.5098  | WD152 | 0.12 | 1.5   | 1.7 | 0.204 |
| W498 | 4.56  | 0.12  | 3.9 | 17.784  | WD153 | 0.12 | 1.5   | 1.7 | 0.204 |
| W499 | 2.189 | 0.12  | 3.9 | 8.5371  | WD154 | 0.12 | 1.5   | 1.7 | 0.204 |
| W500 | 0.12  | 0.08  | 3.9 | 0.468   | WD155 | 0.12 | 1.5   | 1.7 | 0.204 |
| W501 | 0.12  | 0.08  | 3.9 | 0.468   | WD156 | 0.12 | 1.5   | 1.7 | 0.204 |
| W502 | 0.186 | 0.12  | 3.9 | 0.7254  | WD157 | 0.12 | 1.5   | 1.7 | 0.204 |
| W503 | 0.08  | 0.12  | 3.9 | 0.312   | WD158 | 0.12 | 1.5   | 1.7 | 0.204 |

|      |       |       |     |         |       |       |       |     |        |
|------|-------|-------|-----|---------|-------|-------|-------|-----|--------|
| W504 | 0.08  | 0.12  | 3.9 | 0.312   | WD159 | 0.12  | 1.5   | 1.7 | 0.204  |
| W505 | 4.56  | 0.12  | 3.9 | 17.784  | WD160 | 0.12  | 1.5   | 1.7 | 0.204  |
| W506 | 2.184 | 0.12  | 3.9 | 8.5176  | WD161 | 0.12  | 1.5   | 1.7 | 0.204  |
| W507 | 2.184 | 0.12  | 3.9 | 8.5176  | WD162 | 0.12  | 1.5   | 1.7 | 0.204  |
| W508 | 0.12  | 0.08  | 3.9 | 0.468   | WD163 | 0.12  | 1.5   | 1.7 | 0.204  |
| W509 | 2.48  | 0.12  | 3.9 | 9.672   | WD164 | 0.12  | 0.9   | 1.7 | 0.204  |
| W510 | 0.844 | 0.12  | 3.9 | 3.2916  | WD165 | 0.12  | 0.9   | 1.7 | 0.204  |
| W511 | 0.399 | 0.12  | 3.9 | 1.5561  | WD166 | 0.12  | 0.9   | 1.7 | 0.204  |
| W512 | 0.4   | 0.12  | 3.9 | 1.56    | WD167 | 0.12  | 1     | 1.7 | 0.204  |
| W513 | 0.12  | 0.08  | 3.9 | 0.468   | WD168 | 0.12  | 0.9   | 1.7 | 0.204  |
| W514 | 2.689 | 0.12  | 3.9 | 10.4871 | WD169 | 0.12  | 1.7   | 1.7 | 0.204  |
| W515 | 5.324 | 0.12  | 3.9 | 20.7636 | WD170 | 0.12  | 0.9   | 1.7 | 0.204  |
| W516 | 0.52  | 0.12  | 3.9 | 2.028   | WD171 | 0.12  | 1     | 1.7 | 0.204  |
| W517 | 0.4   | 0.12  | 3.9 | 1.56    | WD172 | 0.12  | 0.9   | 1.7 | 0.204  |
| W518 | 4.903 | 0.12  | 3.9 | 19.1217 | WD173 | 0.12  | 1.7   | 1.7 | 0.204  |
| W519 | 5.02  | 0.12  | 3.9 | 19.578  | WD174 | 0.12  | 1.102 | 1.7 | 0.204  |
| W520 | 5.898 | 0.12  | 3.9 | 23.0022 | WD175 | 0.05  | 0.8   | 1.7 | 0.085  |
| W521 | 2.296 | 0.12  | 3.9 | 8.9544  | WD176 | 0.05  | 0.8   | 1.7 | 0.085  |
| W522 | 2.48  | 0.12  | 3.9 | 9.672   | WD177 | 0.12  | 1.1   | 1.7 | 0.204  |
| W523 | 2.188 | 0.12  | 3.9 | 8.5332  | WD178 | 0.05  | 0.8   | 1.7 | 0.085  |
| W524 | 2.188 | 0.12  | 3.9 | 8.5332  | WD179 | 0.05  | 0.8   | 1.7 | 0.085  |
| W525 | 4.323 | 0.12  | 3.9 | 16.8597 | WD180 | 0.12  | 1     | 1.7 | 0.204  |
| W526 | 0.52  | 0.12  | 3.9 | 2.028   | WD181 | 0.12  | 0.9   | 1.7 | 0.204  |
| W527 | 0.724 | 0.12  | 3.9 | 2.8236  | WD182 | 0.12  | 0.9   | 1.7 | 0.204  |
| W528 | 0.4   | 0.12  | 3.9 | 1.56    | WD183 | 0.12  | 1.03  | 1.7 | 0.204  |
| W529 | 0.069 | 0.12  | 3.9 | 0.2691  | WD184 | 0.12  | 0.9   | 1.7 | 0.204  |
| W530 | 0.049 | 0.12  | 3.9 | 0.1911  | WD185 | 0.123 | 1.5   | 1.7 | 0.2091 |
| W531 | 0.12  | 0.08  | 3.9 | 0.468   | WD186 | 0.12  | 1.3   | 1.7 | 0.204  |
| W532 | 0.039 | 0.136 | 3.9 | 0.1521  | WD187 | 0.12  | 1.501 | 1.7 | 0.204  |
| W533 | 0.05  | 0.12  | 3.9 | 0.195   | WD188 | 0.12  | 1.102 | 1.7 | 0.204  |
| W534 | 0.12  | 0.104 | 3.9 | 0.468   | WD189 | 0.12  | 1.102 | 1.7 | 0.204  |
| W535 | 0.05  | 0.12  | 3.9 | 0.195   | WD190 | 0.12  | 1.5   | 1.7 | 0.204  |
| W536 | 0.12  | 0.104 | 3.9 | 0.468   | WD191 | 0.12  | 1.1   | 1.7 | 0.204  |
| W537 | 0.085 | 0.12  | 3.9 | 0.3315  | WD192 | 0.12  | 1.3   | 1.7 | 0.204  |
| W538 | 0.05  | 0.12  | 3.9 | 0.195   | WD193 | 0.12  | 1.3   | 1.7 | 0.204  |
| W539 | 0.05  | 0.12  | 3.9 | 0.195   | WD194 | 0.12  | 1.3   | 1.7 | 0.204  |
| W540 | 0.071 | 0.12  | 3.9 | 0.2769  | WD195 | 0.12  | 1.3   | 1.7 | 0.204  |
| W541 | 0.05  | 0.12  | 3.9 | 0.195   | WD196 | 0.12  | 0.9   | 1.7 | 0.204  |
| W542 | 0.12  | 0.104 | 3.9 | 0.468   | WD197 | 0.12  | 1     | 1.7 | 0.204  |
| W543 | 0.05  | 0.12  | 3.9 | 0.195   | WD198 | 0.12  | 1.7   | 1.7 | 0.204  |
| W544 | 0.12  | 0.104 | 3.9 | 0.468   | WD199 | 0.12  | 0.9   | 1.7 | 0.204  |
| W545 | 0.085 | 0.12  | 3.9 | 0.3315  | WD200 | 0.12  | 0.9   | 1.7 | 0.204  |
| W546 | 0.05  | 0.12  | 3.9 | 0.195   | WD201 | 0.12  | 0.9   | 1.7 | 0.204  |

|      |       |      |     |         |       |       |       |     |        |
|------|-------|------|-----|---------|-------|-------|-------|-----|--------|
| W547 | 0.05  | 0.12 | 3.9 | 0.195   | WD202 | 0.12  | 1.5   | 1.7 | 0.204  |
| W548 | 0.071 | 0.12 | 3.9 | 0.2769  | WD203 | 0.12  | 1     | 1.7 | 0.204  |
| W549 | 3.129 | 0.12 | 3.9 | 12.2031 | WD204 | 0.12  | 1.7   | 1.7 | 0.204  |
| W550 | 2.817 | 0.12 | 3.9 | 10.9863 | WD205 | 0.12  | 0.9   | 1.7 | 0.204  |
| W551 | 0.38  | 0.12 | 3.9 | 1.482   | WD206 | 0.12  | 1     | 1.7 | 0.204  |
| W552 | 0.379 | 0.12 | 3.9 | 1.4781  | WD207 | 0.12  | 0.9   | 1.7 | 0.204  |
| W553 | 3.043 | 0.12 | 3.9 | 11.8677 | WD208 | 0.12  | 0.9   | 1.7 | 0.204  |
| W554 | 4.553 | 0.12 | 3.9 | 17.7567 | WD209 | 0.12  | 0.9   | 1.7 | 0.204  |
| W555 | 7.25  | 0.12 | 3.9 | 28.275  | WD210 | 0.12  | 1     | 1.7 | 0.204  |
| W556 | 0.41  | 0.12 | 3.9 | 1.599   | WD211 | 0.12  | 0.9   | 1.7 | 0.204  |
| W557 | 1.894 | 0.12 | 3.9 | 7.3866  | WD212 | 0.12  | 0.9   | 1.7 | 0.204  |
| W558 | 4.244 | 0.12 | 3.9 | 16.5516 | WD213 | 0.12  | 1.5   | 1.7 | 0.204  |
| W559 | 4.162 | 0.12 | 3.9 | 16.2318 | WD214 | 0.12  | 0.9   | 1.7 | 0.204  |
| W560 | 2.188 | 0.12 | 3.9 | 8.5332  | WD215 | 0.12  | 1     | 1.7 | 0.204  |
| W561 | 0.198 | 0.12 | 3.9 | 0.7722  | WD216 | 0.12  | 0.9   | 1.7 | 0.204  |
| W562 | 0.162 | 0.12 | 3.9 | 0.6318  | WD217 | 0.12  | 0.9   | 1.7 | 0.204  |
| W563 | 0.52  | 0.12 | 3.9 | 2.028   | WD218 | 0.12  | 0.9   | 1.7 | 0.204  |
| W564 | 0.724 | 0.12 | 3.9 | 2.8236  | WD219 | 0.11  | 0.9   | 1.7 | 0.187  |
| W565 | 0.4   | 0.12 | 3.9 | 1.56    | WD220 | 0.12  | 0.9   | 1.7 | 0.204  |
| W566 | 2.48  | 0.12 | 3.9 | 9.672   | WD221 | 0.12  | 0.9   | 1.7 | 0.204  |
| W567 | 2.188 | 0.12 | 3.9 | 8.5332  | WD222 | 0.12  | 0.9   | 1.7 | 0.204  |
| W568 | 0.201 | 0.12 | 3.9 | 0.7839  | WD223 | 0.12  | 1.7   | 1.7 | 0.204  |
| W569 | 0.159 | 0.12 | 3.9 | 0.6201  | WD224 | 0.12  | 1.3   | 1.7 | 0.204  |
| W570 | 2.296 | 0.12 | 3.9 | 8.9544  | WD225 | 0.12  | 1.3   | 1.7 | 0.204  |
| W571 | 3.624 | 0.64 | 3.9 | 14.1336 | WD226 | 0.12  | 1.3   | 1.7 | 0.204  |
| W572 | 2.332 | 0.12 | 3.9 | 9.0948  | WD227 | 0.12  | 1.302 | 1.7 | 0.204  |
| W573 | 2.332 | 0.12 | 3.9 | 9.0948  | WD228 | 0.12  | 1.102 | 1.7 | 0.204  |
| W574 | 5.02  | 0.12 | 3.9 | 19.578  | WD229 | 0.12  | 1.102 | 1.7 | 0.204  |
| W575 | 4.87  | 0.12 | 3.9 | 18.993  | WD230 | 0.12  | 1.5   | 1.7 | 0.204  |
| W576 | 0.13  | 0.12 | 3.9 | 0.507   | WD231 | 0.12  | 1.5   | 1.7 | 0.204  |
| W577 | 5.299 | 0.12 | 3.9 | 20.6661 | WD232 | 0.12  | 1.102 | 1.7 | 0.204  |
| W578 | 2.689 | 0.12 | 3.9 | 10.4871 | WD233 | 0.12  | 1.3   | 1.7 | 0.204  |
| W579 | 0.724 | 0.12 | 3.9 | 2.8236  | WD234 | 0.25  | 1.746 | 1.7 | 0.425  |
| W580 | 0.52  | 0.12 | 3.9 | 2.028   | WD235 | 0.25  | 1.701 | 1.7 | 0.425  |
| W581 | 0.604 | 0.12 | 3.9 | 2.3556  | WD236 | 0.25  | 1.802 | 1.7 | 0.425  |
| W582 | 2.28  | 0.12 | 3.9 | 8.892   | WD237 | 0.25  | 1.751 | 1.7 | 0.425  |
| W583 | 2.182 | 0.12 | 3.9 | 8.5098  | WD238 | 0.251 | 1.802 | 1.7 | 0.4267 |
| W584 | 0.08  | 0.12 | 3.9 | 0.312   | WD239 | 0.251 | 1.751 | 1.7 | 0.4267 |
| W585 | 0.08  | 0.09 | 3.9 | 0.312   | WD240 | 0.25  | 4.276 | 1.7 | 0.425  |
| W586 | 4.56  | 0.12 | 3.9 | 17.784  | WD241 | 0.25  | 4.225 | 1.7 | 0.425  |
| W587 | 2.189 | 0.12 | 3.9 | 8.5371  | WD242 | 0.25  | 4.522 | 1.7 | 0.425  |
| W588 | 0.08  | 0.12 | 3.9 | 0.312   | WW1   | 0.12  | 1.45  | 2.5 | 0.3    |
| W589 | 0.34  | 0.12 | 3.9 | 1.326   | WW2   | 0.12  | 1.45  | 2.5 | 0.3    |

|      |       |       |     |         |      |       |      |     |        |
|------|-------|-------|-----|---------|------|-------|------|-----|--------|
| W590 | 4.56  | 0.12  | 3.9 | 17.784  | WW3  | 0.12  | 1.45 | 2.5 | 0.3    |
| W591 | 2.184 | 0.12  | 3.9 | 8.5176  | WW4  | 0.12  | 1.45 | 2.5 | 0.3    |
| W592 | 0.12  | 0.08  | 3.9 | 0.468   | WW5  | 0.12  | 1.45 | 2.5 | 0.3    |
| W593 | 0.08  | 0.12  | 3.9 | 0.312   | WW6  | 0.12  | 1.45 | 2.5 | 0.3    |
| W594 | 2.48  | 0.12  | 3.9 | 9.672   | WW7  | 0.12  | 1.46 | 2.5 | 0.3    |
| W595 | 0.844 | 0.12  | 3.9 | 3.2916  | WW8  | 0.12  | 1.45 | 2.5 | 0.3    |
| W596 | 0.399 | 0.12  | 3.9 | 1.5561  | WW9  | 0.12  | 1.45 | 2.5 | 0.3    |
| W597 | 0.4   | 0.12  | 3.9 | 1.56    | WW10 | 0.12  | 1.45 | 2.5 | 0.3    |
| W598 | 2.184 | 0.12  | 3.9 | 8.5176  | WW11 | 0.12  | 1.45 | 2.5 | 0.3    |
| W599 | 0.08  | 0.12  | 3.9 | 0.312   | WW12 | 0.12  | 1.45 | 2.5 | 0.3    |
| W600 | 0.34  | 0.12  | 3.9 | 1.326   | WW13 | 0.12  | 1.45 | 2.5 | 0.3    |
| W601 | 2.689 | 0.12  | 3.9 | 10.4871 | WW14 | 0.12  | 1.45 | 2.5 | 0.3    |
| W602 | 5.324 | 0.12  | 3.9 | 20.7636 | WW15 | 0.12  | 1.45 | 2.5 | 0.3    |
| W603 | 0.52  | 0.12  | 3.9 | 2.028   | WW16 | 0.12  | 1.45 | 2.5 | 0.3    |
| W604 | 0.4   | 0.12  | 3.9 | 1.56    | WW17 | 0.12  | 1.45 | 2.5 | 0.3    |
| W605 | 4.556 | 0.12  | 3.9 | 17.7684 | WW18 | 0.12  | 1.45 | 2.5 | 0.3    |
| W606 | 4.992 | 0.12  | 3.9 | 19.4688 | WW19 | 0.12  | 1.45 | 2.5 | 0.3    |
| W607 | 0.05  | 0.136 | 3.9 | 0.195   | WW20 | 0.12  | 1.45 | 2.5 | 0.3    |
| W608 | 0.134 | 0.12  | 3.9 | 0.5226  | WW21 | 0.12  | 1.45 | 2.5 | 0.3    |
| W609 | 5.898 | 0.12  | 3.9 | 23.0022 | WW22 | 0.12  | 1.7  | 2.5 | 0.3    |
| W610 | 2.296 | 0.12  | 3.9 | 8.9544  | WW23 | 0.12  | 1.7  | 2.5 | 0.3    |
| W611 | 2.48  | 0.12  | 3.9 | 9.672   | WW24 | 0.12  | 1.45 | 2.5 | 0.3    |
| W612 | 2.188 | 0.12  | 3.9 | 8.5332  | WW25 | 0.12  | 1.7  | 2.5 | 0.3    |
| W613 | 0.224 | 0.12  | 3.9 | 0.8736  | WW26 | 0.12  | 1.7  | 2.5 | 0.3    |
| W614 | 0.136 | 0.12  | 3.9 | 0.5304  | WW27 | 0.12  | 1.7  | 2.5 | 0.3    |
| W615 | 4.16  | 0.12  | 3.9 | 16.224  | WW28 | 0.12  | 1.45 | 2.5 | 0.3    |
| W616 | 0.844 | 0.12  | 3.9 | 3.2916  | WW29 | 0.12  | 1.7  | 2.5 | 0.3    |
| W617 | 0.4   | 0.12  | 3.9 | 1.56    | WW30 | 0.121 | 1.45 | 2.5 | 0.3025 |
| W618 | 0.4   | 0.12  | 3.9 | 1.56    | WW31 | 0.12  | 1.5  | 2.5 | 0.3    |
| W619 | 2.188 | 0.12  | 3.9 | 8.5332  | WW32 | 0.12  | 1.45 | 2.5 | 0.3    |
| W620 | 0.085 | 0.12  | 3.9 | 0.3315  |      |       |      |     |        |



# Chapter (10)

## Project Resources & Crew Formation

### 10.1 Project resources:

#### 10.1.1 Labor resource identification:

Tabel 13 Labor Recourses

| Code | Description                    | Rate/day   | Basic Rate |
|------|--------------------------------|------------|------------|
| L1   | Commanda                       | 564.3L.E   | 513.0L.E   |
| L2   | assistant worker               | 480.7L.E   | 437.0L.E   |
| L3   | Formal                         | 385.0L.E   | 350.0L.E   |
| L4   | Driver Heavy Equipment         | 550.0L.E   | 500.0L.E   |
| L5   | Carpenter                      | 605.0L.E   | 550.0L.E   |
| L6   | A builder                      | 775.5L.E   | 705.0L.E   |
| L7   | Mortar preparation worker      | 495.0L.E   | 450.0L.E   |
| L8   | Brick laying worker            | 550.0L.E   | 500.0L.E   |
| L9   | Technical worker               | 660.0L.E   | 600.0L.E   |
| L10  | Plasterer                      | 775.5L.E   | 705.0L.E   |
| L11  | Smith                          | 605.0L.E   | 550.0L.E   |
| L12  | Carpenter's assistant          | 385.0L.E   | 350.0L.E   |
| L13  | Blacksmith's assistant         | 385.0L.E   | 350.0L.E   |
| L14  | Vibrator                       | 275.0L.E   | 250.0L.E   |
| L15  | Insulation worker              | 627.0L.E   | 570.0L.E   |
| L16  | Insulation's assistant         | 480.7L.E   | 437.0L.E   |
| L17  | Ceramic worker                 | 836.0L.E   | 760.0L.E   |
| L18  | Ceramic assistant              | 480.7L.E   | 437.0L.E   |
| L19  | Brick laying assistant         | 275.0L.E   | 250.0L.E   |
| L20  | Plasterer assistant            | 352.0L.E   | 320.0L.E   |
| L21  | Shuttering Worker for Cladding | 1,760.0L.E | 1,600.0L.E |
| L22  | Glass Worker For Cladding      | 1,760.0L.E | 1,600.0L.E |
| L23  | Aluminum Worker for Cladding   | 1,760.0L.E | 1,600.0L.E |

### 10.2 Equipment resource identification:

Tabel 14 Equipment Resources

| Code | Description               | Rate/day   | Basic Rate |
|------|---------------------------|------------|------------|
| E1   | Excavator                 | 3,300.0L.E | 3,000.0L.E |
| E2   | Loader                    | 2,508.0L.E | 2,280.0L.E |
| E3   | bulldozer                 | 2,750.0L.E | 2,500.0L.E |
| E4   | mash                      | 3,553.0L.E | 3,230.0L.E |
| E5   | Tractor                   | 4,807.0L.E | 4,370.0L.E |
| E6   | Dumpers                   | 2,200.0L.E | 2,000.0L.E |
| E7   | winch                     | 7,733.0L.E | 7,030.0L.E |
| E8   | concrete transport trucks | 2,200.0L.E | 2,000.0L.E |
| E9   | Mechanical vibrator       | 1,100.0L.E | 1,000.0L.E |
| E10  | Bump                      | 2,200.0L.E | 2,000.0L.E |



## 10.3 Project resources (Labor & material):

Tabel 15 Project Resources

| Tanta General Hospital-Final                                                              |                                             | Current Project's Resources |             |                     | 11/6/2024 00:40 |  |
|-------------------------------------------------------------------------------------------|---------------------------------------------|-----------------------------|-------------|---------------------|-----------------|--|
| Resource ID                                                                               | Resource Name                               | Resource Type               | Unit of Me: | Standard Rate       | Max             |  |
|  R-207   | Aluminum Works                              | Labor                       |             | 295,735.93 EGP/d    | 1d/d            |  |
|  R-158   | Workers                                     | Labor                       |             | 480.70 EGP/d        | 1d/d            |  |
|  R-159   | Forger                                      | Labor                       |             | 385.00 EGP/d        | 1d/d            |  |
|  R-160   | Insulation Worker                           | Labor                       |             | 627.00 EGP/d        | 1d/d            |  |
|  R-161   | Marble Installer                            | Labor                       |             | 836.00 EGP/d        | 1d/d            |  |
|  R-162   | plasterer                                   | Labor                       |             | 775.50 EGP/d        | 1d/d            |  |
|  R-173   | Ceramic Installer                           | Labor                       |             | 836.00 EGP/d        | 1d/d            |  |
|  R-176   | Bricklayer                                  | Labor                       |             | 550.00 EGP/d        | 1d/d            |  |
|  R-177   | Steel Fixer                                 | Labor                       |             | 605.00 EGP/d        | 1d/d            |  |
|  R-180   | Carpenter                                   | Labor                       |             | 605.00 EGP/d        | 1d/d            |  |
|  R-182   | Worker                                      | Labor                       |             | 2,508.00 EGP/d      | 1d/d            |  |
|  R-183   | Steel FixerAssistant                        | Labor                       |             | 385.00 EGP/d        | 1d/d            |  |
|  R-184   | CarpenterAssistant                          | Labor                       |             | 385.00 EGP/d        | 1d/d            |  |
|  R-185   | BricklayerAssistant                         | Labor                       |             | 275.00 EGP/d        | 1d/d            |  |
|  R-186  | plastererAssistant                          | Labor                       |             | 352.00 EGP/d        | 1d/d            |  |
|  R-187 | Marble InstallerAssistant                   | Labor                       |             | 480.70 EGP/d        | 1d/d            |  |
|  R-188 | Ceramic InstallerAssistant                  | Labor                       |             | 480.70 EGP/d        | 1d/d            |  |
|  R-189 | InsulationAssistant                         | Labor                       |             | 480.70 EGP/d        | 1d/d            |  |
|  R-190 | Preliminary Sanitary                        | Labor                       |             | 27,635.12 EGP/d     | 1d/d            |  |
|  R-191 | Preliminary carbntry                        | Labor                       |             | 294,150.79 EGP/d    | 1d/d            |  |
|  R-193 | Preliminary Electrical                      | Labor                       |             | 2,761,210.10 EGP/d  | 1d/d            |  |
|  R-194 | Metal Works                                 | Labor                       |             | 114,822.50 EGP/d    | 1d/d            |  |
|  R-195 | Preliminary HVAC                            | Labor                       |             | 2,230,537.14 EGP/d  | 1d/d            |  |
|  R-196 | Preliminary Fire Fighting                   | Labor                       |             | 1,659,428.57 EGP/d  | 1d/d            |  |
|  R-197 | Primary Painting                            | Labor                       |             | 82,500.00 EGP/d     | 1d/d            |  |
|  R-198 | Finishing Carpentry                         | Labor                       |             | 441,226.20 EGP/d    | 1d/d            |  |
|  R-199 | Finishing Electrical                        | Labor                       |             | 1,661,211.09 EGP/d  | 1d/d            |  |
|  R-200 | Finishing Sanitary                          | Labor                       |             | 62,179.85 EGP/d     | 1d/d            |  |
|  R-201 | Finishing HVAC                              | Labor                       |             | 5,550,895.22 EGP/d  | 1d/d            |  |
|  R-202 | Finishing Fire Fighting                     | Labor                       |             | 4,873,390.50 EGP/d  | 1d/d            |  |
|  R-203 | Glass Work                                  | Labor                       |             | 1,117,817.50 EGP/d  | 1d/d            |  |
|  R-204 | Finishing Painting                          | Labor                       |             | 165,000.00 EGP/d    | 1d/d            |  |
|  R-205 | Suspended Ceiling                           | Labor                       |             | 267,229.00 EGP/d    | 1d/d            |  |
|  R-208 | Elevator Works                              | Labor                       |             | 1,833,333.00 EGP/d  | 1d/d            |  |
|  R-209 | Elevator Instaliation                       | Labor                       |             | 78,571.43 EGP/d     | 1d/d            |  |
|  R-210 | Form Work for Cladding                      | Labor                       |             | 21,120.00 EGP/d     | 1d/d            |  |
|  R-211 | Glass Work for Cladding                     | Labor                       |             | 21,120.00 EGP/d     | 1d/d            |  |
|  R-212 | Aluminum Work for Cladding                  | Labor                       |             | 7,040.00 EGP/d      | 1d/d            |  |
|  R-213 | Road Paving Works for General Site          | Labor                       |             | 853,187.50 EGP/d    | 1d/d            |  |
|  R-214 | Installing interlock Tiles for General Site | Labor                       |             | 977,625.00 EGP/d    | 1d/d            |  |
|  R-151 | Sand                                        | Material                    | m3          | 126.50 EGP/m3       | 1m3/d           |  |
|  R-152 | Bitumin                                     | Material                    | Bammel      | 3,630.00 EGP/Bammel | 1Bammel/d       |  |
|  R-155 | water                                       | Material                    | m3          | 55.00 EGP/m3        | 1m3/d           |  |
|  R-157 | polystyrene                                 | Material                    | m2          | 38.50 EGP/m2        | 1m2/d           |  |
|  R-163 | Steel                                       | Material                    | Ton         | 44,000.00 EGP/Ton   | 1Ton/d          |  |
|  R-164 | Ceramic                                     | Material                    | m2          | 137.50 EGP/m2       | 1m2/d           |  |
|  R-166 | Marble                                      | Material                    | m2          | 517.00 EGP/m2       | 1m2/d           |  |
|  R-170 | Deawstring Wire                             | Material                    | kg          | 66.00 EGP/kg        | 1kg/d           |  |
|  R-172 | blocks                                      | Material                    | 1000        | 2,640.00 EGP/Unit   | 1Unit/d         |  |
|  R-174 | cement                                      | Material                    | Ton         | 2,420.00 EGP/Ton    | 1Ton/d          |  |
|  R-175 | brick                                       | Material                    | 1000        | 2,640.00 EGP/Unit   | 1Unit/d         |  |

|                                                                                          |                           |          |      |                |         |
|------------------------------------------------------------------------------------------|---------------------------|----------|------|----------------|---------|
|  R-178  | sika top seal -107        | Material | m2   | 126.50 EGP/m2  | 1m2/d   |
|  R-179  | InsusintN3000             | Material | m2   | 660.00 EGP/m2  | 1m2/d   |
|  R-181  | strings                   | Material | Roll | 13.20 EGP/Roll | 1Roll/d |
|  R-1    | Dewatering truck          | Nonlabor |      | 150.00 EGP/d   | 1d/d    |
|  Lo-1   | loader                    | Nonlabor |      | 2,508.00 EGP/d | 1d/d    |
|  R-153  | Excavator                 | Nonlabor |      | 3,300.00 EGP/d | 1d/d    |
|  mash-2 | mash                      | Nonlabor |      | 3,553.00 EGP/d | 1d/d    |
|  pum-2  | pump                      | Nonlabor |      | 2,200.00 EGP/d | 1d/d    |
|  vib-2  | Vibrator for concrete     | Nonlabor |      | 1,100.00 EGP/d | 1d/d    |
|  R-169  | concrete transport trucks | Nonlabor |      | 2,200.00 EGP/d | 1d/d    |
|  R-206  | tractor                   | Nonlabor |      | 4,807.00 EGP/d | 1d/d    |

## 10.4 Crew formation:

The following is the crew formation according to the work type, consisting of labors and equipment, and the crew total cost per time unit.

Tabel 16 Crew Formation

| Code  | Description                | Rate/d       | NoR1  | Res1 | NoR2   | Res2 | NoR3 | Res3 | NoR4 | Res4 | Prod/day              |
|-------|----------------------------|--------------|-------|------|--------|------|------|------|------|------|-----------------------|
| CR-01 | Excavation Crew            | 31,805L.E    | 2.00  | L2   | 2.00   | E1   | 4.00 | E5   | 2.00 | E2   | 300 m <sup>3</sup>    |
| CR-02 | Backfilling Crew           | 40,964L.E    | 2.00  | E2   | 6.00   | E5   | 2.00 | E4   |      |      | 350 m <sup>3</sup>    |
| CR-03 | Shuttering P.C Crew        | 1,980L.E     | 2.00  | L5   | 2.00   | L12  |      |      |      |      | 330m <sup>3</sup>     |
| CR-04 | Pouring P.C Crew           | 271,370L.E   | 2.00  | L3   | 120.00 | E8   | 2.00 | E9   | 2.00 | E10  | 1000 m <sup>3</sup>   |
| CR-05 | Shuttering Raft Crew       | 4,730L.E     | 4.00  | L5   | 6.00   | L12  |      |      |      |      | 500 m <sup>3</sup>    |
| CR-6  | Steel Fixing Raft          | 17,875L.E    | 20.00 | L11  | 15.00  | L13  |      |      |      |      | 30 Ton                |
| CR-7  | Pouring Raft. Crew         | 1,770,725L.E | 5.00  | L3   | 800.00 | E8   | 2.00 | E10  | 4.00 | E9   | 330 m <sup>3</sup>    |
| CR-8  | Insulation crew            | 4,765L.E     | 3.00  | L15  | 6.00   | L16  |      |      |      |      | 750 m <sup>2</sup>    |
| CR-9  | Shuttering crew For Column | 4,730L.E     | 4.00  | L5   | 6.00   | L12  |      |      |      |      | 50 m <sup>3</sup>     |
| CR-10 | Shuttering crew For Slab   | 5,940L.E     | 6.00  | L5   | 6.00   | L12  |      |      |      |      | 150 m <sup>3</sup> /d |
| CR-11 | Steel Fixing Column        | 7,920L.E     | 8.00  | L11  | 8.00   | L13  |      |      |      |      | 3.5 ton/d             |
| CR-12 | Steel Fixing Slab          | 12,760L.E    | 16.00 | L11  | 8.00   | L13  |      |      |      |      | 10 ton/d              |
| CR-13 | Steel Fixing Stairs        | 3,740L.E     | 3.00  | L11  | 5.00   | L13  |      |      |      |      | 4 ton/d               |
| CR-14 | Building Crew              | 8,250L.E     | 10.00 | L8   | 10.00  | L19  |      |      |      |      | 400 m <sup>2</sup> /d |
| CR-15 | Plastering crew            | 11,275L.E    | 10.00 | L10  | 10.00  | L20  |      |      |      |      | 150 m <sup>2</sup> /d |
| CR-16 | Ceramic Crew               | 13,167L.E    | 10.00 | L17  | 10.00  | L18  |      |      |      |      | 350 m <sup>2</sup> /d |
| CR-17 | Insulation Foundation      | 5,392L.E     | 4.00  | L15  | 6.00   | L16  |      |      |      |      | 500 m <sup>2</sup> /d |
| CR-18 | Pouring Columns            | 84,370L.E    | 2.00  | L3   | 34.00  | E8   | 2.00 | E10  | 4.00 | E9   | 25 m <sup>2</sup> /d  |
| CR-19 | Pouring Slab               | 365,255L.E   | 3.00  | L3   | 160.00 | E8   | 3.00 | E10  | 5.00 | E9   | 160 m <sup>2</sup> /d |

|       |                                       |           |      |     |      |     |      |    |      |     |          |
|-------|---------------------------------------|-----------|------|-----|------|-----|------|----|------|-----|----------|
| CR-20 | Shuttering for Stairs of Ground floor | 1,375L.E  | 1.00 | L5  | 2.00 | L12 |      |    |      |     | 160 m³/d |
| CR-21 | Shuttering Formwork for Cladding      | 10,560L.E | 6.00 | L21 |      |     |      |    |      |     | 100 m²/d |
| CR-22 | Glass Work for Cladding               | 10,560L.E | 6.00 | L22 |      |     |      |    |      |     | 36 m²/d  |
| CR-23 | Aluminum Work For Cladding            | 3,520L.E  | 2.00 | L23 |      |     |      |    |      |     | 900 m/d  |
| CR-24 | Preliminary Plastering                | 2,255L.E  | 2.00 | L20 | 2.00 | L10 |      |    |      |     | 150 m²/d |
| CR-25 | Pouring for Stairs                    | 13,970L.E | 2.00 | L3  | 3.00 | E8  | 2.00 | E9 | 2.00 | E10 | 31m²     |

Resources of material:

Tabel 17 Material

| Code | Description        | Cost/Unit   | Basic (LE/Unit) | Unit    |
|------|--------------------|-------------|-----------------|---------|
| M1   | Cement             | 2,420.0L.E  | 2,200.000 L.E   | Ton     |
| M2   | Sand               | 126.5L.E    | 115.000 L.E     | M3      |
| M3   | Steel              | 44,000.0L.E | 40,000.000 L.E  | Ton     |
| M4   | Crushed stone      | 192.5L.E    | 175.000 L.E     | M2      |
| M5   | Bitumen            | 3,630.0L.E  | 3,300.000 L.E   | Barrel  |
| M6   | Water              | 55.0L.E     | 50.000 L.E      | M3      |
| M7   | bricks             | 2,640.0L.E  | 2,400.000 L.E   | 1000.00 |
| M8   | Deawstring wire    | 66.0L.E     | 60.000 L.E      | Kg      |
| M9   | Ceramic            | 137.5L.E    | 125.000 L.E     | M2      |
| M10  | Grout              | 16.5L.E     | 15.000 L.E      | Kg      |
| M11  | Marble             | 517.0L.E    | 470.000 L.E     | M2      |
| M12  | Cladding           | 1,045.0L.E  | 950.000 L.E     | M2      |
| M13  | Thermal insulation | 2,942.5L.E  | 2,675.000 L.E   | M2      |
| M14  | Paints             | 165.0L.E    | 150.000 L.E     | M2      |
| M15  | Insusint N3000     | 660.0L.E    | 600.000 L.E     | M2      |
| M16  | Sika top Seal -107 | 126.5L.E    | 115.000 L.E     | M2      |
| M17  | polystyrene        | 38.5L.E     | 35.000 L.E      | M2      |
| M18  | strings            | 13.2L.E     | 12.000 L.E      | Roll    |

## 10.5 Resources Histogram:




Figure 35 Carpenter Assistant Crews



Figure 36 Steel Fixer Crews





Figure 37 Carpenter crews



Figure 38 Vibrator for concrete Crews



Figure 39 Pump crews



# **Chapter (11)**

## Project Planning & Project Schedule

### 11.1 What is Project Planning:

Project planning refers to the phase in project management in which you determine the actual steps to complete a project. This includes laying out timelines, establishing the budget, setting milestones, assessing risks, and solidifying tasks and assigning them to team members.

### 11.2 Components of a project plan

During the planning phase of the project management lifecycle, you'll determine the steps to achieve your project goals. This is the "how" of completing the project.

The components of project planning are: tasks, milestones, people, documentation, and time. This step involves outlining your project scope, objectives, and timeline to make sure all stakeholders are on the same page.

**Tasks:** Tasks are activities that need to be accomplished within a set period of time. These are assigned to different members of the team according to their role and skill set.

**Milestones:** To go along with tasks, milestones are important points within the schedule that indicate progress. They tend to signify the completion of a deliverable or phase of the project.

**People:** A project plan also includes the people working on your team and their roles. It's important that each team member understands their role and the tasks they're responsible for completing. Ensuring that everyone is clear on their assigned tasks frees you up to focus on managing the project, ultimately creating a sense of personal responsibility for team members.

**Documentation:** During the project planning phase, it is a good idea to draft a project plan that links to relevant documentation. Besides your project plan, you can include documents like a RACI chart (Responsibility Assignment Matrix), which defines roles and responsibilities for individuals on your team. Another document is your charter which defines the project and outlines the details needed to reach your goals. You can include a budget and risk management plan, if relevant.

**Time:** Project plans should include the estimated duration of the project. How much time will be spent on each part? The schedule will be the anchor of your project plan. It includes dates for starting and completing tasks, and dates (deadlines) for reaching specific milestones. Indicating the project's start and end dates will help situate this project among competing priorities, and helps

determine resources (including people) needed and when you'll need them.

### **11.3 What Is a Project Schedule?**

A project schedule is a timetable that organizes tasks, resources and due dates in an ideal sequence so that a project can be completed on time. A project schedule is created during the planning phase and includes the following:

- A project timeline with start dates, end dates and milestones.
- The work necessary to complete the project deliverables.
- The costs, resources and dependencies associated with each task.
- The team members that are responsible for each task.

### **11.4 What's Included in a Project Schedule?**

Project schedules are created during the project planning phase and are crucial to the creation of a project plan, where the schedule plan, schedule baseline, deliverables and requirements are identified. The project schedule is designed to guide the project team throughout the execution phase of the project.


Then, during the execution phase, the schedule baseline is compared against the actual project progress. The following are included in the creation of a project schedule:

- 1) Deliverables
- 2) Tasks
- 3) Task start and end dates
- 4) Task dependencies
- 5) Project calendar
- 6) Work packages
- 7) Task duration and project timeline
- 8) Budgets
- 9) Resource availability
- 10) Schedule risk analysis





## 11.5 Construction Sequence:

Figure 40 Gant Chart






















[illegible]



## Chapter (12)

## Cost management

### 12.1 Defining The Cost estimating

Cost estimating is a well-formulated prediction of the probable construction cost of a specific building project. A cost estimate can be an important management tool for library planners during the design phases of a project providing information about the facility and the project budget.

All projects begin with an idea and end by filling a need. Most projects at conceptual design requires changes to present an acceptable workable solution. The conceptual cost estimate is becoming more important to owners, architects, and builders. It is a tool for determining required funding and gauging the needs of a project. This tool continues to be refined during the design stages of the project.

The cost estimate accounts for all items that will generally be included in the general contractor's bid. The cost estimate is prepared by breaking down the items of work using a standard format and determining the cost of each item from experience and a database of current construction cost information. A cost estimate should not be confused with a project budget. A project budget will include the total cost estimate, and will also include what is known as overhead. This overhead will specifically be excluded from the cost estimate and will typically include land acquisition, architectural and design fees, movable furniture and equipment, building permits and fees, fire, and all risk insurance. The project budget will also include non-construction related costs such as fundraising and moving costs.

### 12.2 Types of Cost Estimates:

Cost estimates fall into two groups: conceptual estimates and detailed estimates. Each can be broadly defined as follows:

*Conceptual Estimate:* Conceptual estimating or parametric estimating is the process of establishing a project's cost, often before any graphical representation of a facility has been developed, it depends on historical data. To make a conceptual cost estimate we can use one of these techniques.

- 1) linear regression
- 2) multiple regression
- 3) analogous estimation
- 4) top-down & bottom-up estimation
- 5) factors & ratios

Figure 41 S- Curve




Table 17 list Of Activity in Excel with Budget Total Cost

| Code | Description                                    | Duration | Cost           | Units | NoCrew/<br>Sub | Crew  |
|------|------------------------------------------------|----------|----------------|-------|----------------|-------|
| 1    | Excavation                                     | 5        | 477,081 L.E    | m3    | 3              | CR-01 |
| 2    | Soil replacement                               | 4        | 594,211 L.E    | m3    | 2              | CR-01 |
| 3    | Back filling                                   | 2        | 784,010 L.E    | m3    | 2              | CR-02 |
| 4    | Shultering PC                                  | 1        | 5,940 L.E      | m2    | 3              | CR-03 |
| 5    | Pouring PC                                     | 1        | 814,110 L.E    | m3    | 3              | CR-04 |
| 6    | De shuttering PC                               | 1        | 5,940 L.E      | m2    | 3              | CR-03 |
| 7    | Shuttering RC Raft                             | 2        | 28,380 L.E     | m3    | 3              | CR-05 |
| 8    | Steel Fixing RC Raft                           | 5        | 48,233,185 L.E | Ton   | 3              | CR-6  |
| 9    | Pouring RC Raft                                | 3        | 15,936,525 L.E | m3    | 3              | CR-7  |
| 10   | De shuttering RC Raft                          | 1        | 14,190 L.E     | m2    | 3              | CR-05 |
| 11   | Pouring of slab on grade                       | 1        | 814,110 L.E    | m3    | 3              | CR-04 |
| 12   | Insulation for RC Foundation                   | 1        | 148,862 L.E    | m2    | 2              | CR-17 |
| 13   | Block under slab on grade                      | 3        | 547,089 L.E    | m2    | 3              | CR-14 |
| 14   | Shuttering for columns of Ground floor         | 4        | 56,760 L.E     | m3    | 3              | CR-9  |
| 15   | Steel Fixed for column of ground floor         | 8        | 3,603,490 L.E  | Ton   | 3              | CR-11 |
| 16   | Pouring for Columns of Ground floor            | 4        | 674,960 L.E    | m3    | 2              | CR-18 |
| 17   | De shuttering for Columns of Ground floor      | 1        | 9,460 L.E      | m3    | 2              | CR-9  |
| 18   | Shuttering for Slab of Ground floor            | 6        | 71,280 L.E     | m3    | 2              | CR-10 |
| 19   | Steel Fixed for Slab of ground floor           | 11       | 9,944,660 L.E  | Ton   | 2              | CR-12 |
| 20   | Pouring for Slab of Ground floor               | 3        | 2,191,530 L.E  | m3    | 2              | CR-19 |
| 21   | De shuttering for Slab of Ground floor         | 1        | 11,880 L.E     | m3    | 2              | CR-10 |
| 22   | Shuttering for Stairs of Ground floor          | 1        | 2,750 L.E      | m2    | 2              | CR-20 |
| 23   | Steel Fixed for Stairs of Ground floor         | 1        | 245,089 L.E    | ton   | 2              | CR-13 |
| 24   | Pouring for Stairs of Ground floor             | 1        | 13,970 L.E     | M3    | 1              | CR-25 |
| 25   | De shuttering for Stairs of Ground floor       | 1        | 2,750 L.E      | M3    | 2              | CR-20 |
| 26   | Brick Works of Ground floor                    | 6        | 1,685,456 L.E  | m2    | 3              | CR-14 |
| 27   | Primary Carpentry Works of Ground floor        | 10       | 2,941,508 L.E  | unit  | 2              |       |
| 28   | Primary Electrical Works of Ground floor       | 10       | 27,612,101 L.E | unit  | 2              |       |
| 29   | Primary Sanitary Works of Ground floor         | 30       | 829,054 L.E    | unit  | 2              |       |
| 30   | Aluminum Works of Ground floor                 | 4        | 1,182,944 L.E  | unit  | 2              |       |
| 31   | Metal Works of Ground floor                    | 4        | 459,290 L.E    | unit  | 2              |       |
| 32   | Primary HVAC System of Ground floor            | 10       | 22,305,371 L.E | unit  | 2              |       |
| 33   | Plastering of Ground floor                     | 8        | 3,156,378 L.E  | m2    | 3              | CR-15 |
| 34   | Primary Painting of Ground floor               | 8        | 660,000 L.E    | unit  | 2              |       |
| 35   | Flooring of Ground Floor                       | 17       | 1,988,414 L.E  | m2    | 2              | CR-16 |
| 36   | Finishing Carpentry of Ground floor            | 10       | 4,412,262 L.E  | unit  | 1              |       |
| 37   | Finishing Electrical of Ground floor           | 20       | 33,224,222 L.E | unit  | 1              |       |
| 38   | Finishing Sanitary of Ground floor             | 20       | 1,243,597 L.E  | unit  | 1              |       |
| 39   | Finishing HVAC System of Ground floor          | 9        | 49,958,057 L.E | unit  | 1              |       |
| 40   | Finishing Fire Fighting System of Ground floor | 2        | 9,746,781 L.E  | unit  | 1              |       |
| 41   | Glass Work for Ground floor                    | 2        | 2,235,635 L.E  | unit  | 1              |       |
| 42   | Finishing Painting of Ground floor             | 8        | 1,320,000 L.E  | unit  | 2              |       |
| 43   | Moisture Insulation of Ground Floor            | 1        | 4,537,411 L.E  | m2    | 2              | CR-8  |
| 44   | Thermal Insulation of Ground Floor             | 1        | 231,791 L.E    | m2    | 2              | CR-8  |
| 45   | Suspended Ceiling for Ground Floor             | 10       | 2,672,290 L.E  | m2    | 1              |       |

|    |                                               |    |                |      |   |       |
|----|-----------------------------------------------|----|----------------|------|---|-------|
| 46 | Install Covering of Stairs for Ground floor   | 2  | 116,385 L.E    | m2   | 3 | CR-16 |
| 47 | Moisture Insulation Roof                      | 3  | 4,554,760 L.E  | m2   | 1 | CR-8  |
| 48 | Thermal Insulation of Roof                    | 3  | 236,556 L.E    | m2   | 1 | CR-8  |
| 49 | Install Floor Cover for Roof                  | 11 | 817,452 L.E    | m2   | 2 | CR-16 |
| 50 | Elevator Works                                | 15 | 27,500,000 L.E | unit | 1 |       |
| 51 | Elevator Instaliation                         | 7  | 550,000 L.E    | unit | 1 |       |
| 52 | Form Work for Cladding                        | 1  | 21,120 L.E     | m2   | 2 | CR-21 |
| 53 | Glass Work for Cladding                       | 1  | 21,120 L.E     | m2   | 2 | CR-22 |
| 54 | Aluminum Work for Cladding                    | 1  | 7,040 L.E      | m2   | 2 | CR-23 |
| 55 | Road Paving Works for General Site            | 4  | 3,412,750 L.E  | unit | 1 |       |
| 56 | Installing interlock Tiles for General Site   | 4  | 3,910,500 L.E  | unit | 1 |       |
| 57 | Shuttering for columns of First floor         | 4  | 56,760 L.E     | m3   | 3 | CR-9  |
| 58 | Steel Fixed for coloumn of First floor        | 8  | 3,603,490 L.E  | Ton  | 3 | CR-11 |
| 59 | Pouring for Columns of First floor            | 4  | 674,960 L.E    | m3   | 2 | CR-18 |
| 60 | De shuttering for Columns of First floor      | 1  | 9,460 L.E      | m3   | 2 | CR-9  |
| 61 | Shuttering for Slab of First floor            | 6  | 71,280 L.E     | m3   | 2 | CR-10 |
| 62 | Steel Fixed for Slab of First floor           | 11 | 9,944,660 L.E  | Ton  | 2 | CR-12 |
| 63 | Pouring for Slab of First floor               | 3  | 2,191,530 L.E  | m3   | 2 | CR-19 |
| 64 | De shuttering for Slab of First floor         | 1  | 11,880 L.E     | m3   | 2 | CR-10 |
| 65 | Shuttering for Staris of First floor          | 1  | 2,750 L.E      | m2   | 2 | CR-20 |
| 66 | Steel Fixed for Stairs of First floor         | 1  | 245,089 L.E    | ton  | 2 | CR-13 |
| 67 | Pouring for Stairs of First floor             | 1  | 13,970 L.E     | M3   | 1 | CR-25 |
| 68 | De shuttering for Stairs of First floor       | 1  | 2,750 L.E      | M3   | 2 | CR-20 |
| 69 | Brick Works of First floor                    | 6  | 1,564,650 L.E  | m2   | 3 | CR-14 |
| 70 | Preliminary Carpentry Works of First floor    | 10 | 2,941,508 L.E  | unit | 2 |       |
| 71 | Preliminary Electrical Works of First floor   | 10 | 33,224,222 L.E | unit | 2 |       |
| 72 | Preliminary Sanitary Works of First floor     | 30 | 829,054 L.E    | unit | 2 |       |
| 73 | Aluminum Works of First floor                 | 4  | 1,182,944 L.E  | unit | 2 |       |
| 74 | Metal Works of First floor                    | 4  | 459,290 L.E    | unit | 2 |       |
| 75 | Preliminary HVAC System of First floor        | 10 | 22,305,371 L.E | unit | 2 |       |
| 76 | Plastering of First floor                     | 13 | 3,268,698 L.E  | m2   | 2 | CR-15 |
| 77 | Primary Painting of First floor               | 8  | 660,000 L.E    | unit | 2 |       |
| 78 | Flooring of First Floor                       | 11 | 1,711,996 L.E  | m2   | 2 | CR-16 |
| 79 | Finishing Carpentry of First floor            | 10 | 4,412,262 L.E  | unit | 1 |       |
| 80 | Finishing Electrical of First floor           | 20 | 33,224,222 L.E | unit | 1 |       |
| 81 | Finishing Sanitary of First floor             | 20 | 1,243,597 L.E  | unit | 1 |       |
| 82 | Finishing HVAC System of First floor          | 9  | 49,958,057 L.E | unit | 1 |       |
| 83 | Finishing Fire Fighting System of First floor | 2  | 9,746,781 L.E  | unit | 1 |       |
| 84 | Glass Work for First floor                    | 2  | 2,235,635 L.E  | unit | 1 |       |
| 85 | Finishing Painting of First floor             | 8  | 1,320,000 L.E  | unit | 2 |       |
| 86 | Moisture Insulation of First Floor            | 1  | 4,537,411 L.E  | m2   | 2 | CR-8  |
| 87 | Thermal Insulation of First Floor             | 1  | 231,791 L.E    | m2   | 2 | CR-8  |
| 88 | Suspended Ceiling for First Floor             | 10 | 2,672,290 L.E  | m2   | 1 |       |
| 89 | Install Covering of Stars for First floor     | 2  | 116,385 L.E    | m2   | 3 | CR-16 |
| 90 | Shuttering for columns of second floor        | 4  | 56,760 L.E     | m3   | 3 | CR-9  |
| 91 | Steel Fixed for coloumn of second floor       | 8  | 3,603,490 L.E  | Ton  | 3 | CR-11 |
| 92 | Pouring for Columns of second floor           | 4  | 674,960 L.E    | m3   | 2 | CR-18 |
| 93 | De shuttering for Columns of second floor     | 1  | 9,460 L.E      | m3   | 2 | CR-9  |

|     |                                                |    |                |      |   |       |
|-----|------------------------------------------------|----|----------------|------|---|-------|
| 94  | Shuttering for Slab of second floor            | 6  | 71,280 L.E     | m3   | 2 | CR-10 |
| 95  | Steel Fixed for Slab of second floor           | 11 | 9,944,660 L.E  | Ton  | 2 | CR-12 |
| 96  | Pouring for Slab of second floor               | 3  | 2,191,530 L.E  | m3   | 2 | CR-19 |
| 97  | De shuttering for Slab of second floor         | 1  | 11,880 L.E     | m3   | 2 | CR-10 |
| 98  | Shuttering for Stairs of second floor          | 1  | 2,750 L.E      | m2   | 2 | CR-20 |
| 99  | Steel Fixed for Stairs of second floor         | 1  | 245,089 L.E    | ton  | 2 | CR-13 |
| 100 | Pouring for Stairs of second floor             | 1  | 13,970 L.E     | M3   | 1 | CR-25 |
| 101 | De shuttering for Stairs of second floor       | 1  | 2,750 L.E      | M3   | 2 | CR-20 |
| 102 | Brick Works of second floor                    | 5  | 1,361,722 L.E  | m2   | 3 | CR-14 |
| 103 | Preliminary Carpentry Works of second floor    | 10 | 2,941,508 L.E  | unit | 2 |       |
| 104 | Preliminary Electrical Works of second floor   | 10 | 33,224,222 L.E | unit | 2 |       |
| 105 | Preliminary Sanitary Works of second floor     | 30 | 829,054 L.E    | unit | 2 |       |
| 106 | Aluminum Works of second floor                 | 4  | 1,182,944 L.E  | unit | 2 |       |
| 107 | Metal Works of second floor                    | 4  | 459,290 L.E    | unit | 2 |       |
| 108 | Preliminary HVAC System of second floor        | 10 | 22,305,371 L.E | unit | 2 |       |
| 109 | Plastering of second floor                     | 10 | 2,622,032 L.E  | m2   | 2 | CR-15 |
| 110 | Primary Painting of second floor               | 8  | 660,000 L.E    | unit | 2 |       |
| 111 | Flooring of second Floor                       | 12 | 1,752,735 L.E  | m2   | 2 | CR-16 |
| 112 | Finishing Carpentry of second floor            | 10 | 4,412,262 L.E  | unit | 1 |       |
| 113 | Finishing Electrical of second floor           | 20 | 33,224,222 L.E | unit | 1 |       |
| 114 | Finishing Sanitary of second floor             | 20 | 1,243,597 L.E  | unit | 1 |       |
| 115 | Finishing HVAC System of second floor          | 9  | 49,958,057 L.E | unit | 1 |       |
| 116 | Finishing Fire Fighting System of second floor | 2  | 9,746,781 L.E  | unit | 1 |       |
| 117 | Glass Work for second floor                    | 2  | 2,235,635 L.E  | unit | 1 |       |
| 118 | Finishing Painting of second floor             | 8  | 1,320,000 L.E  | unit | 2 |       |
| 119 | Moisture Insulation of second Floor            | 1  | 4,537,411 L.E  | m2   | 2 | CR-8  |
| 120 | Thermal Insulation of second Floor             | 1  | 231,791 L.E    | m2   | 2 | CR-8  |
| 121 | Suspended Ceiling for second Floor             | 10 | 2,672,290 L.E  | m2   | 1 |       |
| 122 | Install Covering of Stars for second floor     | 2  | 116,385 L.E    | m2   | 3 | CR-16 |
| 123 | Shuttering for columns of third floor          | 4  | 56,760 L.E     | m3   | 3 | CR-9  |
| 124 | Steel Fixed for coloumn of third floor         | 8  | 3,603,490 L.E  | Ton  | 3 | CR-11 |
| 125 | Pouring for Columns of third floor             | 4  | 674,960 L.E    | m3   | 2 | CR-18 |
| 126 | De shuttering for Columns of third floor       | 1  | 9,460 L.E      | m3   | 2 | CR-9  |
| 127 | Shuttering for Slab of third floor             | 6  | 71,280 L.E     | m3   | 2 | CR-10 |
| 128 | Steel Fixed for Slab of third floor            | 11 | 9,944,660 L.E  | Ton  | 2 | CR-12 |
| 129 | Pouring for Slab of third floor                | 3  | 2,191,530 L.E  | m3   | 2 | CR-19 |
| 130 | De shuttering for Slab of third floor          | 1  | 11,880 L.E     | m3   | 2 | CR-10 |
| 131 | Shuttering for Stars of third floor            | 1  | 2,750 L.E      | m2   | 2 | CR-20 |
| 132 | Steel Fixed for Stairs of third floor          | 1  | 245,089 L.E    | ton  | 2 | CR-13 |
| 133 | Pouring for Stairs of third floor              | 1  | 13,970 L.E     | M3   | 1 | CR-25 |
| 134 | De shuttering for Stairs of third floor        | 1  | 2,750 L.E      | M3   | 2 | CR-20 |
| 135 | Brick Works of third floor                     | 5  | 1,304,506 L.E  | m2   | 3 | CR-14 |
| 136 | Preliminary Carpentry Works of third floor     | 10 | 2,941,508 L.E  | unit | 2 |       |
| 137 | Preliminary Electrical Works of third floor    | 10 | 33,224,222 L.E | unit | 2 |       |
| 138 | Preliminary Sanitary Works of third floor      | 30 | 829,054 L.E    | unit | 2 |       |
| 139 | Aluminum Works of third floor                  | 4  | 1,182,944 L.E  | unit | 2 |       |

|     |                                                |    |                |      |   |       |
|-----|------------------------------------------------|----|----------------|------|---|-------|
| 140 | Metal Works of third floor                     | 4  | 459,290 L.E    | unit | 2 |       |
| 141 | Preliminary HVAC System of third floor         | 10 | 22,305,371 L.E | unit | 2 |       |
| 142 | Plastering of third floor                      | 11 | 2,709,461 L.E  | m2   | 2 | CR-15 |
| 143 | Primary Painting of third floor                | 8  | 660,000 L.E    | unit | 2 |       |
| 144 | Flooring of third Floor                        | 12 | 1,755,823 L.E  | m2   | 2 | CR-16 |
| 145 | Finishing Carpentry of third floor             | 10 | 4,412,262 L.E  | unit | 1 |       |
| 146 | Finishing Electrical of third floor            | 20 | 33,224,222 L.E | unit | 1 |       |
| 147 | Finishing Sanitary of third floor              | 20 | 1,243,597 L.E  | unit | 1 |       |
| 148 | Finishing HVAC System of third floor           | 9  | 49,958,057 L.E | unit | 1 |       |
| 149 | Finishing Fire Fighting System of third floor  | 2  | 9,746,781 L.E  | unit | 1 |       |
| 150 | Glass Work for third floor                     | 2  | 2,235,635 L.E  | unit | 1 |       |
| 151 | Finishing Painting of third floor              | 8  | 1,320,000 L.E  | unit | 2 |       |
| 152 | Moisture Insulation of third Floor             | 1  | 4,537,411 L.E  | m2   | 2 | CR-8  |
| 153 | Thermal Insulation of third Floor              | 1  | 231,791 L.E    | m2   | 2 | CR-8  |
| 154 | Suspended Ceiling for third Floor              | 10 | 2,672,290 L.E  | m2   | 1 |       |
| 155 | Install Covering of Stars for third floor      | 2  | 116,385 L.E    | m2   | 3 | CR-16 |
| 156 | Shuttering for columns of fourth floor         | 4  | 56,760 L.E     | m3   | 3 | CR-9  |
| 157 | Steel Fixed for coloumn of fourth floor        | 8  | 3,603,490 L.E  | Ton  | 3 | CR-11 |
| 158 | Pouring for Columns of fourth floor            | 4  | 674,960 L.E    | m3   | 2 | CR-18 |
| 159 | De shuttering for Columns of fourth floor      | 1  | 9,460 L.E      | m3   | 2 | CR-9  |
| 160 | Shuttering for Slab of fourth floor            | 6  | 71,280 L.E     | m3   | 2 | CR-10 |
| 161 | Steel Fixed for Slab of fourth floor           | 11 | 9,944,660 L.E  | Ton  | 2 | CR-12 |
| 162 | Pouring for Slab of fourth floor               | 3  | 2,191,530 L.E  | m3   | 2 | CR-19 |
| 163 | De shuttering for Slab of fourth floor         | 1  | 11,880 L.E     | m3   | 2 | CR-10 |
| 164 | Shuttering for Stars of fourth floor           | 1  | 2,750 L.E      | m2   | 2 | CR-20 |
| 165 | Steel Fixed for Stairs of fourth floor         | 1  | 245,089 L.E    | ton  | 2 | CR-13 |
| 166 | Pouring for Stairs of fourth floor             | 1  | 13,970 L.E     | M3   | 1 | CR-25 |
| 167 | De shuttering for Stairs of fourth floor       | 1  | 2,750 L.E      | M3   | 2 | CR-20 |
| 168 | Brick Works of fourth floor                    | 5  | 1,432,169 L.E  | m2   | 3 | CR-14 |
| 169 | Preliminary Carpentry Works of fourth floor    | 10 | 2,941,508 L.E  | unit | 2 |       |
| 170 | Preliminary Electrical Works of fourth floor   | 10 | 33,224,222 L.E | unit | 2 |       |
| 171 | Preliminary Sanitary Works of fourth floor     | 30 | 829,054 L.E    | unit | 2 |       |
| 172 | Aluminum Works of fourth floor                 | 4  | 1,182,944 L.E  | unit | 2 |       |
| 173 | Metal Works of fourth floor                    | 4  | 459,290 L.E    | unit | 2 |       |
| 174 | Preliminary HVAC System of fourth floor        | 10 | 22,305,371 L.E | unit | 2 |       |
| 175 | Plastering of fourth floor                     | 14 | 3,552,805 L.E  | m2   | 2 | CR-15 |
| 176 | Primary Painting of fourth floor               | 8  | 660,000 L.E    | unit | 2 |       |
| 177 | Flooring of fourth Floor                       | 13 | 1,801,522 L.E  | m2   | 2 | CR-16 |
| 178 | Finishing Carpentry of fourth floor            | 10 | 4,412,262 L.E  | unit | 1 |       |
| 179 | Finishing Electrical of fourth floor           | 20 | 33,224,222 L.E | unit | 1 |       |
| 180 | Finishing Sanitary of fourth floor             | 20 | 1,243,597 L.E  | unit | 1 |       |
| 181 | Finishing HVAC System of fourth floor          | 9  | 49,958,057 L.E | unit | 1 |       |
| 182 | Finishing Fire Fighting System of fourth floor | 2  | 9,746,781 L.E  | unit | 1 |       |
| 183 | Glass Work for fourth floor                    | 2  | 2,235,635 L.E  | unit | 1 |       |
| 184 | Finishing Painting of fourth floor             | 8  | 1,320,000 L.E  | unit | 2 |       |
| 185 | Moisture Insulation of fourth Floor            | 1  | 4,537,411 L.E  | m2   | 2 | CR-8  |
| 186 | Thermal Insulation of fourth Floor             | 1  | 231,791 L.E    | m2   | 2 | CR-8  |



|     |                                                 |    |                |      |   |       |
|-----|-------------------------------------------------|----|----------------|------|---|-------|
| 187 | Suspended Ceiling for fourth Floor              | 10 | 2,672,290 L.E  | m2   | 1 |       |
| 188 | Install Covering of Stars for fourth floor      | 2  | 116,385 L.E    | m2   | 3 | CR-16 |
| 189 | Preliminary Plastering Ground floor             | 2  | 20,030 L.E     | M2   | 2 | CR-24 |
| 190 | Preliminary Plastering First floor              | 2  | 20,030 L.E     | M2   | 2 | CR-24 |
| 191 | Preliminary Plastering Second floor             | 2  | 20,030 L.E     | M2   | 2 | CR-24 |
| 192 | Preliminary Plastering Third floor              | 2  | 20,030 L.E     | M2   | 2 | CR-24 |
| 193 | Preliminary Plastering fourth floor             | 2  | 20,030 L.E     | M2   | 2 | CR-24 |
| 194 | Preliminary Plastering of Roof                  | 2  | 10,702 L.E     | M2   | 2 | CR-24 |
| 195 | Brick Works of Roof                             | 1  | 346,222 L.E    | M2   | 3 | CR-14 |
| 196 | Plastering of Roof                              | 1  | 12,863 L.E     | M2   | 1 | CR-15 |
| 197 | Preliminary Fire Fighting Works of Ground floor | 7  | 11,616,000 L.E | unit | 1 |       |
| 198 | Preliminary Fire Fighting Works of First floor  | 7  | 11,616,000 L.E | unit | 1 |       |
| 199 | Preliminary Fire Fighting Works of Second floor | 7  | 11,616,000 L.E | unit | 1 |       |
| 200 | Preliminary Fire Fighting Works of third floor  | 7  | 11,616,000 L.E | unit | 1 |       |
| 201 | Preliminary Fire Fighting Works of Fourth floor | 7  | 11,616,000 L.E | unit | 1 |       |

| Code | Sub | Quantity | RegPr/d | MatQ/Unit | Material1 | MatQ/Unit | Material2 | MatQ/Unit | Material3 | MatQ/Unit | Material4 |
|------|-----|----------|---------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| 1    |     | 13104    | 900.0   |           |           |           |           |           |           |           |           |
| 2    |     | 1872     | 300.0   | 1.00      | M2        | 1.00      | M6        |           |           |           |           |
| 3    |     | 2663     | 700.0   | 1.41      | M2        | 1.00      | M6        |           |           |           |           |
| 4    |     | 986      | 986.0   |           |           |           |           |           |           |           |           |
| 5    |     | 1248     | 1000.0  |           |           |           |           |           |           |           |           |
| 6    |     | 986      | 986.0   |           |           |           |           |           |           |           |           |
| 7    |     | 8325     | 1500.0  |           |           |           |           |           |           |           |           |
| 8    |     | 1082     | 90.0    | 1.00      | M3        | 5.00      | M8        |           |           |           |           |
| 9    |     | 8325     | 1000.0  |           |           |           |           |           |           |           |           |
| 10   |     | 8325     | 3000.0  |           |           |           |           |           |           |           |           |
| 11   |     | 1248     | 1000.0  |           |           |           |           |           |           |           |           |
| 12   |     | 2660     | 1500.0  | 0.01      | M5        |           |           |           |           |           |           |
| 13   |     | 2662     | 300.0   | 0.06      | M7        | 0.01      | M1        | 0.34      | M2        | 0.15      | M6        |
| 14   |     | 448      | 40.0    |           |           |           |           |           |           |           |           |
| 15   |     | 77       | 3.5     | 1.00      | M3        | 5.00      | M8        |           |           |           |           |
| 16   |     | 342      | 50.0    |           |           |           |           |           |           |           |           |
| 17   |     | 448      | 300.0   |           |           |           |           |           |           |           |           |
| 18   |     | 1674     | 150.0   |           |           |           |           |           |           |           |           |
| 19   |     | 218      | 10.0    | 1.00      | M3        | 5.00      | M8        |           |           |           |           |
| 20   |     | 1674     | 320.0   |           |           |           |           |           |           |           |           |
| 21   |     | 1674     | 1500.0  |           |           |           |           |           |           |           |           |
| 22   |     | 168      | 168.0   |           |           |           |           |           |           |           |           |
| 23   |     | 4        | 4.0     | 1.34      | M3        | 6.70      | M8        |           |           |           |           |
| 24   |     | 31       | 31.0    |           |           |           |           |           |           |           |           |
| 25   |     | 31       | 31.0    |           |           |           |           |           |           |           |           |
| 26   |     | 8652     | 500.0   | 0.06      | M7        | 0.01      | M1        | 0.67      | M2        | 0.29      | M6        |

|    |     |       |        |      |     |      |     |       |    |      |     |
|----|-----|-------|--------|------|-----|------|-----|-------|----|------|-----|
| 27 | S9  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 28 | S12 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 29 | S13 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 30 | S10 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 31 | S11 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 32 | S5  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 33 |     | 14125 | 600.0  | 0.08 | M1  | 0.03 | M2  | 0.12  | M6 |      |     |
| 34 | S26 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 35 |     | 11322 | 350.0  | 0.01 | M1  | 0.12 | M2  | 25.00 | M9 | 0.07 | M6  |
| 36 | S15 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 37 | S16 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 38 | S17 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 39 | S18 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 40 | S19 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 41 | S20 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 42 | S27 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 43 |     | 5757  | 3000.0 | 1.00 | M15 | 1.00 | M16 |       |    |      |     |
| 44 |     | 5773  | 3000.0 | 1.00 | M17 |      |     |       |    |      |     |
| 45 | S21 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 46 |     | 168   | 30.0   | 0.00 | M1  | 0.01 | M2  | 0.01  | M6 | 2.35 | M11 |
| 47 |     | 5773  | 2700.0 | 1.00 | M15 | 1.00 | M16 |       |    |      |     |
| 48 |     | 5773  | 2700.0 | 1.00 | M17 |      |     |       |    |      |     |
| 49 |     | 3114  | 150.0  | 0.01 | M1  | 1.08 | M9  | 0.03  | M6 | 1.16 | M2  |
| 50 | S7  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 51 | S29 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 52 |     | 1000  | 500.0  |      |     |      |     |       |    |      |     |
| 53 |     | 1000  | 500.0  |      |     |      |     |       |    |      |     |
| 54 |     | 100   | 50.0   |      |     |      |     |       |    |      |     |
| 55 | S22 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 56 | S23 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 57 |     | 448   | 40.0   |      |     |      |     |       |    |      |     |
| 58 |     | 77    | 3.5    | 1.00 | M3  | 5.00 | M8  |       |    |      |     |
| 59 |     | 342   | 50.0   |      |     |      |     |       |    |      |     |
| 60 |     | 448   | 300.0  |      |     |      |     |       |    |      |     |
| 61 |     | 1674  | 150.0  |      |     |      |     |       |    |      |     |
| 62 |     | 218   | 10.0   | 1.00 | M3  | 5.00 | M8  |       |    |      |     |
| 63 |     | 1674  | 320.0  |      |     |      |     |       |    |      |     |
| 64 |     | 1674  | 1500.0 |      |     |      |     |       |    |      |     |
| 65 |     | 168   | 168.0  |      |     |      |     |       |    |      |     |
| 66 |     | 4     | 4.0    | 1.34 | M3  | 6.70 | M8  |       |    |      |     |
| 67 |     | 31    | 31.0   |      |     |      |     |       |    |      |     |
| 68 |     | 31    | 31.0   |      |     |      |     |       |    |      |     |
| 69 |     | 7949  | 500.0  | 0.06 | M7  | 0.01 | M1  | 0.67  | M2 | 0.29 | M6  |
| 70 | S9  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 71 | S16 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 72 | S13 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 73 | S10 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 74 | S11 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 75 | S5  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 76 |     | 14565 | 600.0  | 0.08 | M1  | 0.03 | M2  | 0.12  | M6 |      |     |
| 77 | S26 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 78 |     | 7335  | 350.0  | 0.01 | M1  | 0.12 | M2  | 25.00 | M9 | 0.07 | M6  |
| 79 | S15 | 1     | 1.0    |      |     |      |     |       |    |      |     |

|     |     |       |        |      |     |      |     |       |    |      |     |
|-----|-----|-------|--------|------|-----|------|-----|-------|----|------|-----|
| 80  | S16 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 81  | S17 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 82  | S18 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 83  | S19 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 84  | S20 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 85  | S27 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 86  |     | 5757  | 3000.0 | 1.00 | M15 | 1.00 | M16 |       |    |      |     |
| 87  |     | 5773  | 3000.0 | 1.00 | M17 |      |     |       |    |      |     |
| 88  | S21 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 89  |     | 168   | 30.0   | 0.00 | M1  | 0.01 | M2  | 0.01  | M6 | 2.35 | M11 |
| 90  |     | 448   | 40.0   |      |     |      |     |       |    |      |     |
| 91  |     | 77    | 3.5    | 1.00 | M3  | 5.00 | M8  |       |    |      |     |
| 92  |     | 342   | 50.0   |      |     |      |     |       |    |      |     |
| 93  |     | 448   | 300.0  |      |     |      |     |       |    |      |     |
| 94  |     | 1674  | 150.0  |      |     |      |     |       |    |      |     |
| 95  |     | 218   | 10.0   | 1.00 | M3  | 5.00 | M8  |       |    |      |     |
| 96  |     | 1674  | 320.0  |      |     |      |     |       |    |      |     |
| 97  |     | 1674  | 1500.0 |      |     |      |     |       |    |      |     |
| 98  |     | 168   | 168.0  |      |     |      |     |       |    |      |     |
| 99  |     | 4     | 4.0    | 1.34 | M3  | 6.70 | M8  |       |    |      |     |
| 100 |     | 31    | 31.0   |      |     |      |     |       |    |      |     |
| 101 |     | 31    | 31.0   |      |     |      |     |       |    |      |     |
| 102 |     | 6912  | 500.0  | 0.06 | M7  | 0.01 | M1  | 0.67  | M2 | 0.29 | M6  |
| 103 | S9  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 104 | S16 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 105 | S13 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 106 | S10 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 107 | S11 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 108 | S5  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 109 |     | 11727 | 600.0  | 0.08 | M1  | 0.03 | M2  | 0.12  | M6 |      |     |
| 110 | S26 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 111 |     | 7820  | 350.0  | 0.01 | M1  | 0.12 | M2  | 25.00 | M9 | 0.07 | M6  |
| 112 | S15 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 113 | S16 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 114 | S17 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 115 | S18 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 116 | S19 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 117 | S20 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 118 | S27 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 119 |     | 5757  | 3000.0 | 1.00 | M15 | 1.00 | M16 |       |    |      |     |
| 120 |     | 5773  | 3000.0 | 1.00 | M17 |      |     |       |    |      |     |
| 121 | S21 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 122 |     | 168   | 30.0   | 0.00 | M1  | 0.01 | M2  | 0.01  | M6 | 2.35 | M11 |
| 123 |     | 448   | 40.0   |      |     |      |     |       |    |      |     |
| 124 |     | 77    | 3.5    | 1.00 | M3  | 5.00 | M8  |       |    |      |     |
| 125 |     | 342   | 50.0   |      |     |      |     |       |    |      |     |
| 126 |     | 448   | 300.0  |      |     |      |     |       |    |      |     |
| 127 |     | 1674  | 150.0  |      |     |      |     |       |    |      |     |
| 128 |     | 218   | 10.0   | 1.00 | M3  | 5.00 | M8  |       |    |      |     |
| 129 |     | 1674  | 320.0  |      |     |      |     |       |    |      |     |
| 130 |     | 1674  | 1500.0 |      |     |      |     |       |    |      |     |
| 131 |     | 168   | 168.0  |      |     |      |     |       |    |      |     |
| 132 |     | 4     | 4.0    | 1.34 | M3  | 6.70 | M8  |       |    |      |     |

|     |     |       |        |      |     |      |     |       |    |      |     |
|-----|-----|-------|--------|------|-----|------|-----|-------|----|------|-----|
| 133 |     | 31    | 31.0   |      |     |      |     |       |    |      |     |
| 134 |     | 31    | 31.0   |      |     |      |     |       |    |      |     |
| 135 |     | 6579  | 500.0  | 0.06 | M7  | 0.01 | M1  | 0.67  | M2 | 0.29 | M6  |
| 136 | S9  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 137 | S16 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 138 | S13 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 139 | S10 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 140 | S11 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 141 | S5  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 142 |     | 12045 | 600.0  | 0.08 | M1  | 0.03 | M2  | 0.12  | M6 |      |     |
| 143 | S26 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 144 |     | 7924  | 350.0  | 0.01 | M1  | 0.12 | M2  | 25.00 | M9 | 0.07 | M6  |
| 145 | S15 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 146 | S16 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 147 | S17 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 148 | S18 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 149 | S19 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 150 | S20 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 151 | S27 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 152 |     | 5757  | 3000.0 | 1.00 | M15 | 1.00 | M16 |       |    |      |     |
| 153 |     | 5773  | 3000.0 | 1.00 | M17 |      |     |       |    |      |     |
| 154 | S21 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 155 |     | 168   | 30.0   | 0.00 | M1  | 0.01 | M2  | 0.01  | M6 | 2.35 | M11 |
| 156 |     | 448   | 40.0   |      |     |      |     |       |    |      |     |
| 157 |     | 77    | 3.5    | 1.00 | M3  | 5.00 | M8  |       |    |      |     |
| 158 |     | 342   | 50.0   |      |     |      |     |       |    |      |     |
| 159 |     | 448   | 300.0  |      |     |      |     |       |    |      |     |
| 160 |     | 1674  | 150.0  |      |     |      |     |       |    |      |     |
| 161 |     | 218   | 10.0   | 1.00 | M3  | 5.00 | M8  |       |    |      |     |
| 162 |     | 1674  | 320.0  |      |     |      |     |       |    |      |     |
| 163 |     | 1674  | 1500.0 |      |     |      |     |       |    |      |     |
| 164 |     | 168   | 168.0  |      |     |      |     |       |    |      |     |
| 165 |     | 4     | 4.0    | 1.34 | M3  | 6.70 | M8  |       |    |      |     |
| 166 |     | 31    | 31.0   |      |     |      |     |       |    |      |     |
| 167 |     | 31    | 31.0   |      |     |      |     |       |    |      |     |
| 168 |     | 7322  | 500.0  | 0.06 | M7  | 0.01 | M1  | 0.67  | M2 | 0.29 | M6  |
| 169 | S9  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 170 | S16 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 171 | S13 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 172 | S10 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 173 | S11 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 174 | S5  | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 175 |     | 15847 | 600.0  | 0.08 | M1  | 0.03 | M2  | 0.12  | M6 |      |     |
| 176 | S26 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 177 |     | 8576  | 350.0  | 0.01 | M1  | 0.12 | M2  | 25.00 | M9 | 0.07 | M6  |
| 178 | S15 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 179 | S16 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 180 | S17 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 181 | S18 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 182 | S19 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 183 | S20 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 184 | S27 | 1     | 1.0    |      |     |      |     |       |    |      |     |
| 185 |     | 5757  | 3000.0 | 1.00 | M15 | 1.00 | M16 |       |    |      |     |

|     |     |      |        |      |     |      |    |      |    |      |     |
|-----|-----|------|--------|------|-----|------|----|------|----|------|-----|
| 186 |     | 5773 | 3000.0 | 1.00 | M17 |      |    |      |    |      |     |
| 187 | S21 | 1    | 1.0    |      |     |      |    |      |    |      |     |
| 188 |     | 168  | 30.0   | 0.00 | M1  | 0.01 | M2 | 0.01 | M6 | 2.35 | M11 |
| 189 |     | 120  | 40.0   | 0.00 | M1  | 0.01 | M2 | 4.04 | M6 | 2.50 | M18 |
| 190 |     | 120  | 40.0   | 0.00 | M1  | 0.01 | M2 | 4.04 | M6 | 2.50 | M18 |
| 191 |     | 120  | 40.0   | 0.00 | M1  | 0.01 | M2 | 4.04 | M6 | 2.50 | M18 |
| 192 |     | 120  | 40.0   | 0.00 | M1  | 0.01 | M2 | 4.04 | M6 | 2.50 | M18 |
| 193 |     | 120  | 40.0   | 0.00 | M1  | 0.01 | M2 | 4.04 | M6 | 2.50 | M18 |
| 194 |     | 120  | 40.0   | 0.00 | M1  | 0.01 | M2 | 0.16 | M6 | 1.00 | M18 |
| 195 |     | 420  | 200.0  | 0.01 | M1  | 0.04 | M2 | 0.18 | M6 | 0.58 | M7  |

| Code | Mat1Cost      | Mat2Cost   | Mat3Cost     | Mat4Cost | Sub Cost      | Crew Cost    |
|------|---------------|------------|--------------|----------|---------------|--------------|
| 1    |               |            |              |          |               | 95,416.20    |
| 2    | 236,808.00    | 102,960.00 |              |          |               | 63,610.80    |
| 3    | 473,677.34    | 146,477.01 |              |          |               | 81,928.00    |
| 4    |               |            |              |          |               | 5,940.00     |
| 5    |               |            |              |          |               | 814,110.00   |
| 6    |               |            |              |          |               | 5,940.00     |
| 7    |               |            |              |          |               | 14,190.00    |
| 8    | 47,608,000.00 | 357,060.00 |              |          |               | 53,625.00    |
| 9    |               |            |              |          |               | 5,312,175.00 |
| 10   |               |            |              |          |               | 14,190.00    |
| 11   |               |            |              |          |               | 814,110.00   |
| 12   | 138,077.94    |            |              |          |               | 10,784.40    |
| 13   | 386,522.40    | 70,862.44  | 12,978.90    | 2,475.00 |               | 24,750.00    |
| 14   |               |            |              |          |               | 14,190.00    |
| 15   | 3,388,000.00  | 25,410.00  |              |          |               | 23,760.00    |
| 16   |               |            |              |          |               | 168,740.00   |
| 17   |               |            |              |          |               | 9,460.00     |
| 18   |               |            |              |          |               | 11,880.00    |
| 19   | 9,592,000.00  | 71,940.00  |              |          |               | 25,520.00    |
| 20   |               |            |              |          |               | 730,510.00   |
| 21   |               |            |              |          |               | 11,880.00    |
| 22   |               |            |              |          |               | 2,750.00     |
| 23   | 235,840.00    | 1,768.80   |              |          |               | 7,480.00     |
| 24   |               |            |              |          |               | 13,970.00    |
| 25   |               |            |              |          |               | 2,750.00     |
| 26   | 1,256,284.63  | 230,318.85 | 42,377.50    | 7,975.00 |               | 24,750.00    |
| 27   |               |            |              |          | 2,941,507.88  |              |
| 28   |               |            |              |          | 27,612,101.00 |              |
| 29   |               |            |              |          | 829,053.50    |              |
| 30   |               |            |              |          | 1,182,943.67  |              |
| 31   |               |            |              |          | 459,290.33    |              |
| 32   |               |            |              |          | 22,305,371.36 |              |
| 33   | 2,837,147.50  | 44,670.31  | 3,960.00     |          |               | 33,825.00    |
| 34   |               |            |              |          | 660,000.00    |              |
| 35   | 164,395.44    | 171,867.96 | 1,203,125.00 | 1,347.50 |               | 26,334.00    |
| 36   |               |            |              |          | 4,412,261.82  |              |
| 37   |               |            |              |          | 33,224,221.80 |              |
| 38   |               |            |              |          | 1,243,596.75  |              |
| 39   |               |            |              |          | 49,958,057.05 |              |
| 40   |               |            |              |          | 9,746,781.00  |              |

|    |              |            |              |           |               |            |
|----|--------------|------------|--------------|-----------|---------------|------------|
| 41 |              |            |              |           | 2,235,635.49  |            |
| 42 |              |            |              |           | 1,320,000.00  |            |
| 43 | 3,799,620.00 | 728,260.50 |              |           |               | 9,530.40   |
| 44 | 222,260.50   |            |              |           |               | 9,530.40   |
| 45 |              |            |              |           | 2,672,289.58  |            |
| 46 | 731.81       | 191.27     | 11.55        | 36,448.50 |               | 39,501.00  |
| 47 | 3,810,180.00 | 730,284.50 |              |           |               | 4,765.20   |
| 48 | 222,260.50   |            |              |           |               | 4,765.20   |
| 49 | 45,215.28    | 460,288.13 | 264.00       | 22,011.00 |               | 26,334.00  |
| 50 |              |            |              |           | 27,500,000.00 |            |
| 51 |              |            |              |           | 550,000.00    |            |
| 52 |              |            |              |           |               | 21,120.00  |
| 53 |              |            |              |           |               | 21,120.00  |
| 54 |              |            |              |           |               | 7,040.00   |
| 55 |              |            |              |           | 3,412,750.00  |            |
| 56 |              |            |              |           | 3,910,500.00  |            |
| 57 |              |            |              |           |               | 14,190.00  |
| 58 | 3,388,000.00 | 25,410.00  |              |           |               | 23,760.00  |
| 59 |              |            |              |           |               | 168,740.00 |
| 60 |              |            |              |           |               | 9,460.00   |
| 61 |              |            |              |           |               | 11,880.00  |
| 62 | 9,592,000.00 | 71,940.00  |              |           |               | 25,520.00  |
| 63 |              |            |              |           |               | 730,510.00 |
| 64 |              |            |              |           |               | 11,880.00  |
| 65 |              |            |              |           |               | 2,750.00   |
| 66 | 235,840.00   | 1,768.80   |              |           |               | 7,480.00   |
| 67 |              |            |              |           |               | 13,970.00  |
| 68 |              |            |              |           |               | 2,750.00   |
| 69 | 1,154,194.80 | 211,602.38 | 42,377.50    | 7,975.00  |               | 24,750.00  |
| 70 |              |            |              |           | 2,941,507.88  |            |
| 71 |              |            |              |           | 33,224,221.80 |            |
| 72 |              |            |              |           | 829,053.50    |            |
| 73 |              |            |              |           | 1,182,943.67  |            |
| 74 |              |            |              |           | 459,290.33    |            |
| 75 |              |            |              |           | 22,305,371.36 |            |
| 76 | 2,925,525.90 | 46,061.81  | 3,960.00     |           |               | 22,550.00  |
| 77 |              |            |              |           | 660,000.00    |            |
| 78 | 106,504.20   | 111,345.30 | 1,203,125.00 | 1,347.50  |               | 26,334.00  |
| 79 |              |            |              |           | 4,412,261.82  |            |
| 80 |              |            |              |           | 33,224,221.80 |            |
| 81 |              |            |              |           | 1,243,596.75  |            |
| 82 |              |            |              |           | 49,958,057.05 |            |
| 83 |              |            |              |           | 9,746,781.00  |            |
| 84 |              |            |              |           | 2,235,635.49  |            |
| 85 |              |            |              |           | 1,320,000.00  |            |
| 86 | 3,799,620.00 | 728,260.50 |              |           |               | 9,530.40   |
| 87 | 222,260.50   |            |              |           |               | 9,530.40   |
| 88 |              |            |              |           | 2,672,289.58  |            |
| 89 | 731.81       | 191.27     | 11.55        | 36,448.50 |               | 39,501.00  |
| 90 |              |            |              |           |               | 14,190.00  |
| 91 | 3,388,000.00 | 25,410.00  |              |           |               | 23,760.00  |
| 92 |              |            |              |           |               | 168,740.00 |
| 93 |              |            |              |           |               | 9,460.00   |

|     |              |            |              |           |               |            |
|-----|--------------|------------|--------------|-----------|---------------|------------|
| 94  |              |            |              |           |               | 11,880.00  |
| 95  | 9,592,000.00 | 71,940.00  |              |           |               | 25,520.00  |
| 96  |              |            |              |           |               | 730,510.00 |
| 97  |              |            |              |           |               | 11,880.00  |
| 98  |              |            |              |           |               | 2,750.00   |
| 99  | 235,840.00   | 1,768.80   |              |           |               | 7,480.00   |
| 100 |              |            |              |           |               | 13,970.00  |
| 101 |              |            |              |           |               | 2,750.00   |
| 102 | 1,003,622.40 | 183,997.44 | 42,377.50    | 7,975.00  |               | 24,750.00  |
| 103 |              |            |              |           | 2,941,507.88  |            |
| 104 |              |            |              |           | 33,224,221.80 |            |
| 105 |              |            |              |           | 829,053.50    |            |
| 106 |              |            |              |           | 1,182,943.67  |            |
| 107 |              |            |              |           | 459,290.33    |            |
| 108 |              |            |              |           | 22,305,371.36 |            |
| 109 | 2,355,485.22 | 37,086.64  | 3,960.00     |           |               | 22,550.00  |
| 110 |              |            |              |           | 660,000.00    |            |
| 111 | 113,546.40   | 118,707.60 | 1,203,125.00 | 1,347.50  |               | 26,334.00  |
| 112 |              |            |              |           | 4,412,261.82  |            |
| 113 |              |            |              |           | 33,224,221.80 |            |
| 114 |              |            |              |           | 1,243,596.75  |            |
| 115 |              |            |              |           | 49,958,057.05 |            |
| 116 |              |            |              |           | 9,746,781.00  |            |
| 117 |              |            |              |           | 2,235,635.49  |            |
| 118 |              |            |              |           | 1,320,000.00  |            |
| 119 | 3,799,620.00 | 728,260.50 |              |           |               | 9,530.40   |
| 120 | 222,260.50   |            |              |           |               | 9,530.40   |
| 121 |              |            |              |           | 2,672,289.58  |            |
| 122 | 731.81       | 191.27     | 11.55        | 36,448.50 |               | 39,501.00  |
| 123 |              |            |              |           |               | 14,190.00  |
| 124 | 3,388,000.00 | 25,410.00  |              |           |               | 23,760.00  |
| 125 |              |            |              |           |               | 168,740.00 |
| 126 |              |            |              |           |               | 9,460.00   |
| 127 |              |            |              |           |               | 11,880.00  |
| 128 | 9,592,000.00 | 71,940.00  |              |           |               | 25,520.00  |
| 129 |              |            |              |           |               | 730,510.00 |
| 130 |              |            |              |           |               | 11,880.00  |
| 131 |              |            |              |           |               | 2,750.00   |
| 132 | 235,840.00   | 1,768.80   |              |           |               | 7,480.00   |
| 133 |              |            |              |           |               | 13,970.00  |
| 134 |              |            |              |           |               | 2,750.00   |
| 135 | 955,270.80   | 175,132.98 | 42,377.50    | 7,975.00  |               | 24,750.00  |
| 136 |              |            |              |           | 2,941,507.88  |            |
| 137 |              |            |              |           | 33,224,221.80 |            |
| 138 |              |            |              |           | 829,053.50    |            |
| 139 |              |            |              |           | 1,182,943.67  |            |
| 140 |              |            |              |           | 459,290.33    |            |
| 141 |              |            |              |           | 22,305,371.36 |            |
| 142 | 2,419,358.70 | 38,092.31  | 3,960.00     |           |               | 22,550.00  |
| 143 |              |            |              |           | 660,000.00    |            |
| 144 | 115,056.48   | 120,286.32 | 1,203,125.00 | 1,347.50  |               | 26,334.00  |
| 145 |              |            |              |           | 4,412,261.82  |            |
| 146 |              |            |              |           | 33,224,221.80 |            |

|     |              |            |              |            |               |            |
|-----|--------------|------------|--------------|------------|---------------|------------|
| 147 |              |            |              |            | 1,243,596.75  |            |
| 148 |              |            |              |            | 49,958,057.05 |            |
| 149 |              |            |              |            | 9,746,781.00  |            |
| 150 |              |            |              |            | 2,235,635.49  |            |
| 151 |              |            |              |            | 1,320,000.00  |            |
| 152 | 3,799,620.00 | 728,260.50 |              |            |               | 9,530.40   |
| 153 | 222,260.50   |            |              |            |               | 9,530.40   |
| 154 |              |            |              |            | 2,672,289.58  |            |
| 155 | 731.81       | 191.27     | 11.55        | 36,448.50  |               | 39,501.00  |
| 156 |              |            |              |            |               | 14,190.00  |
| 157 | 3,388,000.00 | 25,410.00  |              |            |               | 23,760.00  |
| 158 |              |            |              |            |               | 168,740.00 |
| 159 |              |            |              |            |               | 9,460.00   |
| 160 |              |            |              |            |               | 11,880.00  |
| 161 | 9,592,000.00 | 71,940.00  |              |            |               | 25,520.00  |
| 162 |              |            |              |            |               | 730,510.00 |
| 163 |              |            |              |            |               | 11,880.00  |
| 164 |              |            |              |            |               | 2,750.00   |
| 165 | 235,840.00   | 1,768.80   |              |            |               | 7,480.00   |
| 166 |              |            |              |            |               | 13,970.00  |
| 167 |              |            |              |            |               | 2,750.00   |
| 168 | 1,063,154.40 | 194,911.64 | 42,377.50    | 7,975.00   |               | 24,750.00  |
| 169 |              |            |              |            | 2,941,507.88  |            |
| 170 |              |            |              |            | 33,224,221.80 |            |
| 171 |              |            |              |            | 829,053.50    |            |
| 172 |              |            |              |            | 1,182,943.67  |            |
| 173 |              |            |              |            | 459,290.33    |            |
| 174 |              |            |              |            | 22,305,371.36 |            |
| 175 | 3,183,028.42 | 50,116.14  | 3,960.00     |            |               | 22,550.00  |
| 176 |              |            |              |            | 660,000.00    |            |
| 177 | 124,523.52   | 130,183.68 | 1,203,125.00 | 1,347.50   |               | 26,334.00  |
| 178 |              |            |              |            | 4,412,261.82  |            |
| 179 |              |            |              |            | 33,224,221.80 |            |
| 180 |              |            |              |            | 1,243,596.75  |            |
| 181 |              |            |              |            | 49,958,057.05 |            |
| 182 |              |            |              |            | 9,746,781.00  |            |
| 183 |              |            |              |            | 2,235,635.49  |            |
| 184 |              |            |              |            | 1,320,000.00  |            |
| 185 | 3,799,620.00 | 728,260.50 |              |            |               | 9,530.40   |
| 186 | 222,260.50   |            |              |            |               | 9,530.40   |
| 187 |              |            |              |            | 2,672,289.58  |            |
| 188 | 731.81       | 191.27     | 11.55        | 36,448.50  |               | 39,501.00  |
| 189 | 726.00       | 75.90      | 8,888.00     | 1,320.00   |               | 4,510.00   |
| 190 | 726.00       | 75.90      | 8,888.00     | 1,320.00   |               | 4,510.00   |
| 191 | 726.00       | 75.90      | 8,888.00     | 1,320.00   |               | 4,510.00   |
| 192 | 726.00       | 75.90      | 8,888.00     | 1,320.00   |               | 4,510.00   |
| 193 | 726.00       | 75.90      | 8,888.00     | 1,320.00   |               | 4,510.00   |
| 194 | 726.00       | 75.90      | 352.00       | 528.00     |               | 4,510.00   |
| 195 | 11,180.40    | 2,072.07   | 1,980.00     | 306,240.00 |               | 24,750.00  |
| 196 | 907.50       | 158.13     | 522.50       |            |               | 11,275.00  |



**Table 18 List of Subs**

| <b>Code</b> | <b>Description</b>                          | <b>Cost/Unit</b> | <b>Sub-Contractor</b> | <b>SubCost/Unit</b> | <b>Unit</b> |
|-------------|---------------------------------------------|------------------|-----------------------|---------------------|-------------|
| S1          | Site Investigation                          | 55,000.0L.E      | Lump sum              | 50,000.0L.E         | Lump sum    |
| S2          | Site Cleaning                               | 33,000.0L.E      | Lump sum              | 30,000.0L.E         | Lump sum    |
| S3          | Temporary Facilities                        | 220,000.0L.E     | Lump sum              | 200,000.0L.E        | Lump sum    |
| S4          | Surveying Works                             | 33,000.0L.E      | Lump sum              | 30,000.0L.E         | Lump sum    |
| S5          | Primary HVAC System                         | 22,305,371.4L.E  | Lump sum              | 20,277,610.3L.E     | Lump sum    |
| S6          | Glass Work                                  | 11,178,172.5L.E  | Lump sum              | 10,161,975.0L.E     | Lump sum    |
| S7          | Elevators works                             | 27,500,000.0L.E  | Lump sum              | 25,000,000.0L.E     | Lump sum    |
| S8          | Primary Fire Fighting System                | 19,162,790.9L.E  | Lump sum              | 17,420,719.0L.E     | Lump sum    |
| S9          | Primary Carpentry                           | 2,941,507.9L.E   | Lump sum              | 2,674,098.1L.E      | Lump sum    |
| S10         | Aluminum works                              | 1,182,943.7L.E   | Lump sum              | 1,075,403.3L.E      | Lump sum    |
| S11         | Metal work                                  | 459,290.3L.E     | Lump sum              | 417,536.7L.E        | Lump sum    |
| S12         | Primary Electrical                          | 27,612,101.0L.E  | Lump sum              | 25,101,910.0L.E     | Lump sum    |
| S13         | Primary Sanitary                            | 829,053.5L.E     | Lump sum              | 753,685.0L.E        | Lump sum    |
| S14         | Kitchen and washroom                        | 19,210,422.0L.E  | Lump sum              | 17,464,020.0L.E     | Lump sum    |
| S15         | Finishing Carpentry                         | 4,412,261.8L.E   | Lump sum              | 4,011,147.1L.E      | Lump sum    |
| S16         | Finishing Electrical                        | 33,224,221.8L.E  | Lump sum              | 30,203,838.0L.E     | Lump sum    |
| S17         | Finishing Sanitary                          | 1,243,596.8L.E   | Lump sum              | 1,130,542.5L.E      | Lump sum    |
| S18         | Finishing HVAC System                       | 49,958,057.1L.E  | Lump sum              | 45,416,415.5L.E     | Lump sum    |
| S19         | Finishing Fire Fighting System              | 9,746,781.0L.E   | Lump sum              | 8,860,710.0L.E      | Lump sum    |
| S20         | Glass Work                                  | 2,235,635.5L.E   | Lump sum              | 2,032,395.9L.E      | Lump sum    |
| S21         | Suspended Ceiling Work                      | 2,672,289.6L.E   | Lump sum              | 2,429,354.2L.E      | Lump sum    |
| S22         | Road Paving Works for general site          | 3,412,750.0L.E   | Lump sum              | 3,102,500.0L.E      | Lump sum    |
| S23         | Installing interlock tiles for general site | 3,910,500.0L.E   | Lump sum              | 3,555,000.0L.E      | Lump sum    |
| S24         | Agriculture Work for general site           | 1,566,963.8L.E   | Lump sum              | 1,424,512.5L.E      | Lump sum    |
| S24         | Agriculture Work for general site           | 1,566,964.9L.E   | Lump sum              | 1,424,513.5L.E      | Lump sum    |
| S26         | Primary Painting                            | 660,000.0L.E     | Lump sum              | 600,000.0L.E        | Lump sum    |
| S27         | Finishing Painting                          | 1,320,000.0L.E   | Lump sum              | 1,200,000.0L.E      | Lump sum    |
| S28         | Parapet concrete casting                    | 110,000.0L.E     | Lump sum              | 100,000.0L.E        | Lump sum    |
| S29         | Elevator Instaliation                       | 550,000.0L.E     | Lump sum              | 500,000.0L.E        | Lump sum    |
| S30         | Parapet Shutter                             | 110,000.0L.E     | Lump sum              | 100,000.0L.E        | Lump sum    |
| S31         | Parapet steel                               | 110,000.0L.E     | Lump sum              | 100,000.0L.E        | Lump sum    |
| S32         | Parapet Deshutter                           | 11,000.0L.E      | Lump sum              | 10,000.0L.E         | Lump sum    |
| S33         | tank of oxygen                              | 4,400,000.0L.E   | Lump sum              | 4,000,000.0L.E      | Lump sum    |
| S34         | Preliminary Fire Fighting                   | 11,616,000.0L.E  | Lump sum              | 10,560,000.0L.E     | Lump sum    |

## 12.3 List of Activities:

The activity list is essentially an itemized documentation of all of the schedule activities that are part of a particular project. These lists are typically (and ideally should be) very detailed and comprehensive, providing as many details as possible to make it as easy and quick as possible for a user to attain general, broad sheet information. Some specific categories of information that should be included within the activity list can include the title or brief description of the activity, the detailed description of the activity, the unique activity identifier, a list of project team members who may be assigned to that particular activity. A detailed description of each activity is essential in providing all project team members with a big picture perspective of what is taking place, what work needs to be performed, and what their role will be within that activity. The activity list should be compiled as early in the process as possible to assure that all team members have a chance to review it.

Table 20 list Of Activity in Primavera With Budget Total Cost

| Activity ID                  | Activity Name              | Original Duration | Start      | Finish    | Budgeted Total Cost  |
|------------------------------|----------------------------|-------------------|------------|-----------|----------------------|
| Tanta General Hospital-Final |                            | 512d              | 1/10/2023  | 11/6/2025 | 1,114,504,793.49 EGP |
| Milestones                   |                            | 512d              | 1/10/2023  | 11/6/2025 | 0.00 EGP             |
| Key dates                    |                            | 512d              | 1/10/2023  | 11/6/2025 | 0.00 EGP             |
| A2                           | Project Finish             | 0d                |            | 11/6/2025 | 0.00 EGP             |
| A1                           | Project Start              | 0d                | 1/10/2023* |           | 0.00 EGP             |
| Contractual                  |                            | 0d                | 1/10/2023  | 1/10/2023 | 0.00 EGP             |
| A1020                        | Site Handover from client  | 0d                |            | 1/10/2023 | 0.00 EGP             |
| A1010                        | Advanced Payment           | 0d                |            | 1/10/2023 | 0.00 EGP             |
| A1000                        | Contract Agreement         | 0d                |            | 1/10/2023 | 0.00 EGP             |
| Controls                     |                            | 265d              | 4/8/2024   | 11/6/2025 | 0.00 EGP             |
| A4130                        | Roof Floor Finish Date     | 0d                |            | 11/6/2025 | 0.00 EGP             |
| A4120                        | 4th Floor Finish Date      | 0d                |            | 1/5/2025  | 0.00 EGP             |
| A4110                        | 3rd Floor Finish Date      | 0d                |            | 3/4/2025  | 0.00 EGP             |
| A4100                        | 2nd Floor Finish Date      | 0d                |            | 4/3/2025  | 0.00 EGP             |
| A4090                        | 1st Floor Finish Date      | 0d                |            | 4/3/2025  | 0.00 EGP             |
| A4080                        | GF Finish Date             | 0d                |            | 27/1/2025 | 0.00 EGP             |
| A1030                        | Concrete works Finish Date | 0d                |            | 4/8/2024  | 0.00 EGP             |
| Mobilization works           |                            | 6d                | 1/10/2023  | 8/10/2023 | 0.00 EGP             |
| Fence                        |                            | 2d                | 1/10/2023  | 2/10/2023 | 0.00 EGP             |

| A1050                      | Fixing the fence            | 1d                | 2/10/2023  | 2/10/2023  | 0.00 EGP             |
|----------------------------|-----------------------------|-------------------|------------|------------|----------------------|
| A1040                      | Cleaning & Settlement Works | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| <b>Carvans</b>             |                             | 1d                | 4/10/2023  | 4/10/2023  | 0.00 EGP             |
| A1060                      | Install Cravans and Offices | 1d                | 4/10/2023  | 4/10/2023  | 0.00 EGP             |
| <b>Lighting</b>            |                             | 1d                | 4/10/2023  | 4/10/2023  | 0.00 EGP             |
| A1070                      | Site Lighting               | 1d                | 4/10/2023  | 4/10/2023  | 0.00 EGP             |
| <b>Surveying</b>           |                             | 3d                | 4/10/2023  | 8/10/2023  | 0.00 EGP             |
| A108                       | Surveying Works             | 3d                | 4/10/2023  | 8/10/2023  | 0.00 EGP             |
| <b>Engineering</b>         |                             | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| A1110                      | Shop Drawings Package       | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| A1100                      | MEP design Drawings         | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| A1090                      | Arch design Drawings        | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| A1080                      | Structural design drawings  | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| <b>Procurement</b>         |                             | 2d                | 1/10/2023  | 2/10/2023  | 0.00 EGP             |
| <b>Arch Material</b>       |                             | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| A1130                      | Arch Material Approval      | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| Activity ID                | Activity Name               | Original Duration | Start      | Finish     | Budgeted Total Cost  |
| A1120                      | Arch Material Submittal     | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| <b>Civil Material</b>      |                             | 2d                | 1/10/2023  | 2/10/2023  | 0.00 EGP             |
| A1150                      | Civil Material Approval     | 1d                | 2/10/2023  | 2/10/2023  | 0.00 EGP             |
| A1140                      | Civil Material Submittal    | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| <b>MEP Material</b>        |                             | 2d                | 1/10/2023  | 2/10/2023  | 0.00 EGP             |
| A1170                      | MEP Material Approval       | 1d                | 2/10/2023  | 2/10/2023  | 0.00 EGP             |
| A1160                      | MEP Material Submittal      | 1d                | 1/10/2023  | 1/10/2023  | 0.00 EGP             |
| <b>Construction</b>        |                             | 506d              | 9/10/2023  | 11/6/2025  | 1,114,504,793.49 EGP |
| <b>Sup Structure Works</b> |                             | 67d               | 9/10/2023  | 25/12/2023 | 68,693,543.69 EGP    |
| <b>Soil Works</b>          |                             | 63d               | 9/10/2023  | 20/12/2023 | 1,996,045.35 EGP     |
| 140                        | Back filling                | 2d                | 19/12/2023 | 20/12/2023 | 763,948.35 EGP       |
| 130                        | Soil replacement            | 4d                | 16/10/2023 | 19/10/2023 | 630,696.00 EGP       |
| 120                        | Dewatering                  | 4d                | 11/10/2023 | 15/10/2023 | 124,320.00 EGP       |
| 110                        | Excavation                  | 5d                | 9/10/2023  | 14/10/2023 | 477,081.00 EGP       |
| <b>Concrete Works</b>      |                             | 57d               | 21/10/2023 | 25/12/2023 | 65,852,380.00 EGP    |

| Foundation Works             |                                        | 57d               | 21/10/2023  | 25/12/2023 | 65,852,380.00 EGP    |
|------------------------------|----------------------------------------|-------------------|-------------|------------|----------------------|
| PC for Foundation Works      |                                        | 4d                | 21/10/2023  | 24/10/2023 | 825,990.00 EGP       |
| A1250                        | De shuttering P.C Raft                 | 1d                | 24/10/2023  | 24/10/2023 | 5,940.00 EGP         |
| A1190                        | Pouring P.C Raft                       | 1d                | 22/10/2023  | 22/10/2023 | 814,110.00 EGP       |
| A1180                        | Shuttering PC Raft                     | 1d                | 21/10/2023  | 21/10/2023 | 5,940.00 EGP         |
| RC for Foundation Works      |                                        | 53d               | 25/10/2023  | 25/12/2023 | 65,026,390.00 EGP    |
| A1270                        | Pouring of Slab on grade               | 1d                | 25/12/2023  | 25/12/2023 | 814,110.00 EGP       |
| A1260                        | De shuttering R.C Raft                 | 1d                | 11/11/2023  | 11/11/2023 | 14,190.00 EGP        |
| A1230                        | Pouring R.C Raft                       | 3d                | 5/11/2023*  | 7/11/2023  | 15,936,525.00 EGP    |
| A1220                        | Steel Fixing RC Raft                   | 5d                | 28/10/2023* | 1/11/2023  | 48,233,185.00 EGP    |
| A1210                        | Shuttering RC Raft                     | 2d                | 25/10/2023  | 26/10/2023 | 28,380.00 EGP        |
| Arch Works                   |                                        | 6d                | 18/12/2023  | 24/12/2023 | 845,118.34 EGP       |
| A1300                        | Blocks under slab on grade             | 3d                | 21/12/2023  | 24/12/2023 | 547,088.74 EGP       |
| A1290                        | Insulation for RC Raft                 | 1d                | 18/12/2023  | 18/12/2023 | 149,014.80 EGP       |
| A1280                        | Insulation for PC Raft                 | 1d                | 18/12/2023  | 18/12/2023 | 149,014.80 EGP       |
| Super structure Works        |                                        | 477d              | 12/11/2023  | 11/6/2025  | 1,045,811,249.80 EGP |
| Ground Floor Works           |                                        | 361d              | 12/11/2023  | 27/1/2025  | 201,410,410.98 EGP   |
| Concrete Works for Ground fl |                                        | 60d               | 12/11/2023  | 21/1/2024  | 17,256,492.00 EGP    |
| Columns for Ground floor     |                                        | 31d               | 12/11/2023  | 17/12/2023 | 4,344,670.00 EGP     |
| A1370                        | De shuttering for Columns of Ground    | 1d                | 17/12/2023  | 17/12/2023 | 9,460.00 EGP         |
| Activity ID                  | Activity Name                          | Original Duration | Start       | Finish     | Budgeted Total Cost  |
| A1340                        | Pouring for Columns of Ground floor    | 4d                | 11/12/2023  | 14/12/2023 | 674,960.00 EGP       |
| A1330                        | Steel Fixing for Columns of Ground flo | 8d                | 2/12/2023*  | 10/12/2023 | 3,603,490.00 EGP     |
| A1320                        | Shuttering for Columns of Ground floo  | 4d                | 12/11/2023  | 15/11/2023 | 56,760.00 EGP        |
| Slab for Ground floor        |                                        | 22d               | 26/12/2023  | 21/1/2024  | 12,219,350.00 EGP    |
| A1420                        | De shuttering for Slab of Ground floor | 1d                | 21/1/2024   | 21/1/2024  | 11,880.00 EGP        |
| A1400                        | Pouring for Slab of Ground floor       | 3d                | 9/1/2024    | 11/1/2024  | 2,191,530.00 EGP     |
| A1390                        | Steel Fixing for Slab of Ground floor  | 11d               | 26/12/2023  | 8/1/2024   | 9,944,660.00 EGP     |
| A1380                        | Shuttering for Slab of Ground floor    | 6d                | 26/12/2023  | 1/1/2024   | 71,280.00 EGP        |
| Marginal Beam for Ground flo |                                        | 22d               | 26/12/2023  | 21/1/2024  | 427,020.00 EGP       |
| A3910                        | De shuttering for marginal beam        | 1d                | 21/1/2024   | 21/1/2024  | 2,750.00 EGP         |
| A3900                        | Pouring for marginal beam              | 3d                | 9/1/2024    | 11/1/2024  | 60,720.00 EGP        |
| A3890                        | Steel Fixing for marginal beam         | 2d                | 26/12/2023  | 27/12/2023 | 360,800.00 EGP       |

| A3880                                    | Shuttering for marginal beam             | 2d                | 26/12/2023 | 27/12/2023 | 2,750.00 EGP        |
|------------------------------------------|------------------------------------------|-------------------|------------|------------|---------------------|
| <b>Stairs for Ground Floor</b>           |                                          | 22d               | 26/12/2023 | 21/1/2024  | 265,452.00 EGP      |
| A3070                                    | De shuttering for Stairs of Ground floo  | 1d                | 21/1/2024  | 21/1/2024  | 2,750.00 EGP        |
| A3050                                    | Pouring for Stairs of Ground floor       | 1d                | 9/1/2024   | 9/1/2024   | 13,970.00 EGP       |
| A3040                                    | Steel Fixing for Stairs of Ground floor  | 1d                | 26/12/2023 | 26/12/2023 | 245,982.00 EGP      |
| A3030                                    | Shuttering for Stairs of Ground floor    | 1d                | 26/12/2023 | 26/12/2023 | 2,750.00 EGP        |
| <b>Finishing Works for Ground Flooor</b> |                                          | 142d              | 13/8/2024  | 27/1/2025  | 184,153,918.98 EGP  |
| A3280                                    | Install Covering of Stairs for Ground fl | 2d                | 26/1/2025  | 27/1/2025  | 116,377.80 EGP      |
| A1580                                    | Finishing Sanitary of Ground floor       | 20d               | 2/1/2025   | 25/1/2025  | 1,243,597.00 EGP    |
| A1600                                    | Finishing Fire Fighting System of Grou   | 2d                | 10/12/2024 | 11/12/2024 | 9,746,781.00 EGP    |
| A1590                                    | Finishing HVAC System of Ground flo      | 9d                | 10/12/2024 | 19/12/2024 | 49,958,056.98 EGP   |
| A1550                                    | Finishing Electrical of Ground floor     | 20d               | 10/12/2024 | 1/1/2025   | 33,224,221.80 EGP   |
| A1540                                    | Finishing Carpentry of Ground floor      | 10d               | 10/12/2024 | 21/12/2024 | 4,412,262.00 EGP    |
| A1620                                    | Finisishing Painting of Ground floor     | 8d                | 1/12/2024  | 9/12/2024  | 1,320,000.00 EGP    |
| A1660                                    | Suspended Ceiling for Ground Floor       | 10d               | 19/11/2024 | 30/11/2024 | 2,672,290.00 EGP    |
| A1640                                    | Thermal Insulation of Ground Floor       | 1d                | 18/11/2024 | 18/11/2024 | 231,790.90 EGP      |
| A1630                                    | Moisture Insulation of Ground Floor      | 1d                | 18/11/2024 | 18/11/2024 | 4,537,410.90 EGP    |
| A1610                                    | Glass Work for Ground floor              | 2d                | 13/11/2024 | 14/11/2024 | 2,235,635.00 EGP    |
| A1520                                    | Primary Painting of Ground floor         | 8d                | 9/11/2024  | 17/11/2024 | 660,000.00 EGP      |
| A1480                                    | Metal Works of Ground floor              | 4d                | 9/11/2024  | 12/11/2024 | 459,290.00 EGP      |
| A1470                                    | Aluminum Works of Ground floor           | 4d                | 9/11/2024  | 12/11/2024 | 1,182,943.70 EGP    |
| A1500                                    | Preliminary Fire Fighting Works of Gro   | 7d                | 31/10/2024 | 7/11/2024  | 11,616,000.00 EGP   |
| A1530                                    | Flooring of Ground Floor                 | 17d               | 20/10/2024 | 7/11/2024  | 1,988,283.00 EGP    |
| A1490                                    | Preliminary HVAC System of Ground        | 10d               | 20/10/2024 | 30/10/2024 | 22,305,371.40 EGP   |
| A1510                                    | Plastering of Ground floor               | 8d                | 10/10/2024 | 19/10/2024 | 3,155,454.50 EGP    |
| A1440                                    | Preliminary Carpentry Works of Grou      | 10d               | 28/9/2024  | 9/10/2024  | 2,941,507.90 EGP    |
| A1460                                    | Preliminary Sanitary Works of Ground     | 30d               | 22/8/2024  | 26/9/2024  | 829,053.50 EGP      |
| Activity ID                              | Activity Name                            | Original Duration | Start      | Finish     | Budgeted Total Cost |
| A1450                                    | Preliminary Electrical Works of Groun    | 10d               | 22/8/2024  | 2/9/2024   | 27,612,101.00 EGP   |
| A5780                                    | Preliminary Plastering of Ground floor   | 2d                | 20/8/2024  | 21/8/2024  | 20,029.90 EGP       |
| A1430                                    | Brick Works of Ground floor              | 6d                | 13/8/2024* | 19/8/2024  | 1,685,460.70 EGP    |
| <b>First Floor Works</b>                 |                                          | 332d              | 22/1/2024  | 4/3/2025   | 201,085,689.44 EGP  |
| <b>Concrete Works for First floor</b>    |                                          | 37d               | 22/1/2024  | 5/3/2024   | 17,214,912.00 EGP   |
| <b>Columns for First floor</b>           |                                          | 14d               | 22/1/2024  | 7/2/2024   | 4,300,340.00 EGP    |
| A4170                                    | De shuttering for Columns of First floo  | 1d                | 7/2/2024   | 7/2/2024   | 9,460.00 EGP        |
| A4160                                    | Pouring for Columns of First floor       | 4d                | 1/2/2024*  | 5/2/2024   | 674,960.00 EGP      |
| A4150                                    | Steel Fixing for Columns of First floor  | 8d                | 22/1/2024  | 31/1/2024  | 3,559,160.00 EGP    |

| A4140                                  | Shuttering for Columns of First floor      | 4d                | 22/1/2024  | 27/1/2024  | 56,760.00 EGP       |
|----------------------------------------|--------------------------------------------|-------------------|------------|------------|---------------------|
| <b>Slab for First floor</b>            |                                            | 22d               | 8/2/2024   | 4/3/2024   | 12,219,350.00 EGP   |
| A4210                                  | De shuttering for Slab of First floor      | 1d                | 4/3/2024   | 4/3/2024   | 11,880.00 EGP       |
| A4200                                  | Pouring for Slab of First floor            | 3d                | 21/2/2024* | 24/2/2024  | 2,191,530.00 EGP    |
| A4190                                  | Steel Fixing for Slab of First floor       | 11d               | 8/2/2024   | 20/2/2024  | 9,944,660.00 EGP    |
| A4180                                  | Shuttering for Slab of First floor         | 6d                | 8/2/2024   | 14/2/2024  | 71,280.00 EGP       |
| <b>Marginal Beam for First floor</b>   |                                            | 23d               | 8/2/2024   | 5/3/2024   | 429,770.00 EGP      |
| A4540                                  | De shuttering for marginal beam            | 2d                | 4/3/2024   | 5/3/2024   | 5,500.00 EGP        |
| A4530                                  | Pouring for marginal beam                  | 3d                | 21/2/2024  | 24/2/2024  | 60,720.00 EGP       |
| A4520                                  | Steel Fixing for marginal beam             | 2d                | 8/2/2024   | 10/2/2024  | 360,800.00 EGP      |
| A4510                                  | Shuttering for marginal beam               | 2d                | 8/2/2024   | 10/2/2024  | 2,750.00 EGP        |
| <b>Stairs for First Floor</b>          |                                            | 22d               | 8/2/2024   | 4/3/2024   | 265,452.00 EGP      |
| A4450                                  | De shuttering for Stairs of First floor    | 1d                | 4/3/2024   | 4/3/2024   | 2,750.00 EGP        |
| A4440                                  | Pouring for Stairs of First floor          | 1d                | 21/2/2024  | 21/2/2024  | 13,970.00 EGP       |
| A4430                                  | Steel Fixing for Stairs of First floor     | 1d                | 8/2/2024   | 8/2/2024   | 245,982.00 EGP      |
| A4420                                  | Shuttering for Stairs of First floor       | 1d                | 8/2/2024   | 8/2/2024   | 2,750.00 EGP        |
| <b>Finishing Works for First Floor</b> |                                            | 167d              | 20/8/2024  | 4/3/2025   | 183,870,777.44 EGP  |
| A4460                                  | Install Covering of Stairs for First floor | 2d                | 3/3/2025   | 4/3/2025   | 116,377.80 EGP      |
| A4330                                  | Finishing Sanitary of First floor          | 20d               | 8/2/2025   | 2/3/2025   | 1,243,597.00 EGP    |
| A4340                                  | Finishing HVAC System of First floor       | 9d                | 25/1/2025* | 3/2/2025   | 49,958,056.98 EGP   |
| A4320                                  | Finishing Electrical of First floor        | 20d               | 15/1/2025* | 6/2/2025   | 33,224,221.80 EGP   |
| A4350                                  | Finishing Fire Fighting System of First    | 2d                | 23/12/2024 | 24/12/2024 | 9,746,781.00 EGP    |
| A4310                                  | Finishing Carpentry of First floor         | 10d               | 23/12/2024 | 2/1/2025   | 4,412,262.00 EGP    |
| A4370                                  | Finishing Painting of First floor          | 8d                | 14/12/2024 | 22/12/2024 | 1,320,000.00 EGP    |
| A4410                                  | Suspended Ceiling for First Floor          | 10d               | 2/12/2024  | 12/12/2024 | 2,672,290.00 EGP    |
| A4390                                  | Thermal Insulation of First Floor          | 1d                | 1/12/2024  | 1/12/2024  | 231,790.90 EGP      |
| A4380                                  | Moisture Insulation of First Floor         | 1d                | 1/12/2024  | 1/12/2024  | 4,537,410.90 EGP    |
| A4290                                  | Primary Painting of First floor            | 8d                | 21/11/2024 | 30/11/2024 | 660,000.00 EGP      |
| A4360                                  | Glass Work for First floor                 | 2d                | 19/11/2024 | 20/11/2024 | 2,235,635.00 EGP    |
| Activity ID                            | Activity Name                              | Original Duration | Start      | Finish     | Budgeted Total Cost |
| A4260                                  | Metal Works of First floor                 | 4d                | 14/11/2024 | 18/11/2024 | 459,290.00 EGP      |
| A4250                                  | Aluminum Works of First floor              | 4d                | 14/11/2024 | 18/11/2024 | 1,182,943.70 EGP    |
| A4490                                  | Preliminary Fire Fighting Works of First   | 7d                | 13/11/2024 | 20/11/2024 | 11,616,000.00 EGP   |
| A4300                                  | Flooring of First Floor                    | 11d               | 2/11/2024  | 13/11/2024 | 1,711,996.00 EGP    |
| A4270                                  | Preliminary HVAC System of First floor     | 10d               | 2/11/2024  | 12/11/2024 | 22,305,371.40 EGP   |
| A4280                                  | Plastering of First floor                  | 13d               | 17/10/2024 | 31/10/2024 | 3,268,684.98 EGP    |
| A4220                                  | Preliminary Carpentry Works of First f     | 10d               | 5/10/2024  | 16/10/2024 | 2,941,507.90 EGP    |

|       |                                           |     |           |           |                   |
|-------|-------------------------------------------|-----|-----------|-----------|-------------------|
| A4240 | Preliminary Sanitary Works of First flo   | 30d | 29/8/2024 | 3/10/2024 | 829,053.50 EGP    |
| A4230 | Preliminary Electrical Works of First flo | 10d | 29/8/2024 | 9/9/2024  | 27,612,101.00 EGP |
| A4470 | Preliminary Plastering of First floor     | 2d  | 27/8/2024 | 28/8/2024 | 20,755.90 EGP     |
| A4500 | Brick Works of First floor                | 6d  | 20/8/2024 | 26/8/2024 | 1,564,649.68 EGP  |

|                           |      |          |          |                    |
|---------------------------|------|----------|----------|--------------------|
| <b>Second Floor Works</b> | 295d | 6/3/2024 | 4/3/2025 | 200,277,146.87 EGP |
|---------------------------|------|----------|----------|--------------------|

|                                        |     |          |           |                   |
|----------------------------------------|-----|----------|-----------|-------------------|
| <b>Concrete Works for Second floor</b> | 37d | 6/3/2024 | 23/4/2024 | 17,214,912.00 EGP |
|----------------------------------------|-----|----------|-----------|-------------------|

|                                 |     |          |           |                  |
|---------------------------------|-----|----------|-----------|------------------|
| <b>Columns for Second floor</b> | 14d | 6/3/2024 | 23/3/2024 | 4,300,340.00 EGP |
|---------------------------------|-----|----------|-----------|------------------|

|       |                                        |    |           |           |                  |
|-------|----------------------------------------|----|-----------|-----------|------------------|
| A4990 | De shuttering for Columns of second    | 1d | 23/3/2024 | 23/3/2024 | 9,460.00 EGP     |
| A4980 | Pouring for Columns of second floor    | 4d | 16/3/2024 | 20/3/2024 | 674,960.00 EGP   |
| A4970 | Steel Fixing for Columns of second flo | 8d | 6/3/2024  | 14/3/2024 | 3,559,160.00 EGP |
| A4960 | Shuttering for Columns of second floo  | 4d | 6/3/2024  | 10/3/2024 | 56,760.00 EGP    |

|                              |     |           |           |                   |
|------------------------------|-----|-----------|-----------|-------------------|
| <b>Slab for Second floor</b> | 22d | 24/3/2024 | 22/4/2024 | 12,219,350.00 EGP |
|------------------------------|-----|-----------|-----------|-------------------|

|       |                                        |     |           |           |                  |
|-------|----------------------------------------|-----|-----------|-----------|------------------|
| A5030 | De shuttering for Slab of second floor | 1d  | 22/4/2024 | 22/4/2024 | 11,880.00 EGP    |
| A5020 | Pouring for Slab of second floor       | 3d  | 6/4/2024  | 8/4/2024  | 2,191,530.00 EGP |
| A5010 | Steel Fixing for Slab of second floor  | 11d | 24/3/2024 | 4/4/2024  | 9,944,660.00 EGP |
| A5000 | Shuttering for Slab of second floor    | 6d  | 24/3/2024 | 30/3/2024 | 71,280.00 EGP    |

|                                       |     |           |           |                |
|---------------------------------------|-----|-----------|-----------|----------------|
| <b>Marginal Beam for Second floor</b> | 23d | 24/3/2024 | 23/4/2024 | 429,770.00 EGP |
|---------------------------------------|-----|-----------|-----------|----------------|

|       |                                 |    |           |           |                |
|-------|---------------------------------|----|-----------|-----------|----------------|
| A5360 | De shuttering for marginal beam | 2d | 22/4/2024 | 23/4/2024 | 5,500.00 EGP   |
| A5350 | Pouring for marginal beam       | 3d | 6/4/2024  | 8/4/2024  | 60,720.00 EGP  |
| A5340 | Steel Fixing for marginal beam  | 2d | 24/3/2024 | 25/3/2024 | 360,800.00 EGP |
| A5330 | Shuttering for marginal beam    | 2d | 24/3/2024 | 25/3/2024 | 2,750.00 EGP   |

|                                |     |           |           |                |
|--------------------------------|-----|-----------|-----------|----------------|
| <b>Stairs for Second Floor</b> | 22d | 24/3/2024 | 22/4/2024 | 265,452.00 EGP |
|--------------------------------|-----|-----------|-----------|----------------|

|       |                                         |    |           |           |                |
|-------|-----------------------------------------|----|-----------|-----------|----------------|
| A5270 | De shuttering for Stairs of second floo | 1d | 22/4/2024 | 22/4/2024 | 2,750.00 EGP   |
| A5260 | Pouring for Stairs of second floor      | 1d | 6/4/2024  | 6/4/2024  | 13,970.00 EGP  |
| A5250 | Steel Fixing for Stairs of second floor | 1d | 24/3/2024 | 24/3/2024 | 245,982.00 EGP |
| A5240 | Shuttering for Stairs of second floor   | 1d | 24/3/2024 | 24/3/2024 | 2,750.00 EGP   |

|                                         |      |           |          |                    |
|-----------------------------------------|------|-----------|----------|--------------------|
| <b>Finishing Works for Second Floor</b> | 161d | 27/8/2024 | 4/3/2025 | 183,062,234.87 EGP |
|-----------------------------------------|------|-----------|----------|--------------------|

|       |                                             |     |            |          |                   |
|-------|---------------------------------------------|-----|------------|----------|-------------------|
| A5280 | Install Covering of Stairs for second floor | 2d  | 3/3/2025   | 4/3/2025 | 116,377.80 EGP    |
| A5150 | Finishing Sanitary of second floor          | 20d | 8/2/2025   | 2/3/2025 | 1,243,597.00 EGP  |
| A5160 | Finishing HVAC System of second floor       | 9d  | 25/1/2025* | 3/2/2025 | 49,958,056.98 EGP |
| A5140 | Finishing Electrical of second floor        | 20d | 15/1/2025* | 6/2/2025 | 33,224,221.80 EGP |

| Activity ID | Activity Name                          | Original Duration | Start      | Finish     | Budgeted Total Cost |
|-------------|----------------------------------------|-------------------|------------|------------|---------------------|
| A5170       | Finishing Fire Fighting System of seco | 2d                | 25/12/2024 | 26/12/2024 | 9,746,781.00 EGP    |
| A5130       | Finishing Carpentry of second floor    | 10d               | 25/12/2024 | 5/1/2025   | 4,412,262.00 EGP    |
| A5190       | Finishing Painting of second floor     | 8d                | 16/12/2024 | 24/12/2024 | 1,320,000.00 EGP    |
| A5230       | Suspended Ceiling for second Floor     | 10d               | 4/12/2024  | 15/12/2024 | 2,672,290.00 EGP    |




| A5210                                 | Thermal Insulation of second Floor      | 1d                | 3/12/2024        | 3/12/2024        | 231,790.90 EGP            |
|---------------------------------------|-----------------------------------------|-------------------|------------------|------------------|---------------------------|
| A5200                                 | Moisture Insulation of second Floor     | 1d                | 3/12/2024        | 3/12/2024        | 4,537,410.90 EGP          |
| A5110                                 | Primary Painting of second floor        | 8d                | 24/11/2024       | 2/12/2024        | 660,000.00 EGP            |
| A5180                                 | Glass Work for second floor             | 2d                | 23/11/2024       | 24/11/2024       | 2,235,635.00 EGP          |
| A5080                                 | Metal Works of second floor             | 4d                | 18/11/2024       | 21/11/2024       | 459,290.00 EGP            |
| A5070                                 | Aluminum Works of second floor          | 4d                | 18/11/2024       | 21/11/2024       | 1,182,943.70 EGP          |
| A5310                                 | Preliminary Fire Fighting Works of sec  | 7d                | 16/11/2024       | 23/11/2024       | 11,616,000.00 EGP         |
| A5120                                 | Flooring of second Floor                | 12d               | 4/11/2024        | 17/11/2024       | 1,752,734.50 EGP          |
| A5090                                 | Preliminary HVAC System of second       | 10d               | 4/11/2024        | 14/11/2024       | 22,305,371.40 EGP         |
| A5100                                 | Plastering of second floor              | 10d               | 23/10/2024       | 3/11/2024        | 2,622,028.81 EGP          |
| A5040                                 | Preliminary Carpentry Works of secon    | 10d               | 12/10/2024       | 22/10/2024       | 2,941,507.90 EGP          |
| A5060                                 | Preliminary Sanitary Works of second    | 30d               | 4/9/2024         | 10/10/2024       | 829,053.50 EGP            |
| A5050                                 | Preliminary Electrical Works of second  | 10d               | 4/9/2024         | 15/9/2024        | 27,612,101.00 EGP         |
| A5290                                 | Preliminary Plastering of second floor  | 2d                | 2/9/2024         | 3/9/2024         | 20,029.90 EGP             |
| A5320                                 | Brick Works of second floor             | 5d                | 27/8/2024        | 1/9/2024         | 1,362,750.78 EGP          |
| <b>Third Floor Works</b>              |                                         | <b>284d</b>       | <b>24/4/2024</b> | <b>3/4/2025</b>  | <b>200,310,054.86 EGP</b> |
| <b>Concrete Works for Third floor</b> |                                         | <b>42d</b>        | <b>24/4/2024</b> | <b>15/6/2024</b> | <b>17,214,912.00 EGP</b>  |
| <b>Columns for Third floor</b>        |                                         | <b>19d</b>        | <b>24/4/2024</b> | <b>19/5/2024</b> | <b>4,300,340.00 EGP</b>   |
| A5400                                 | De shuttering for Columns of Third flo  | 1d                | 19/5/2024        | 19/5/2024        | 9,460.00 EGP              |
| A5390                                 | Pouring for Columns of Third floor      | 4d                | 13/5/2024        | 16/5/2024        | 674,960.00 EGP            |
| A5380                                 | Steel Fixing for Columns of Third floor | 8d                | 2/5/2024*        | 12/5/2024        | 3,559,160.00 EGP          |
| A5370                                 | Shuttering for Columns of Third floor   | 4d                | 24/4/2024        | 29/4/2024        | 56,760.00 EGP             |
| <b>Slab for Third floor</b>           |                                         | <b>22d</b>        | <b>20/5/2024</b> | <b>13/6/2024</b> | <b>12,219,350.00 EGP</b>  |
| A5440                                 | De shuttering for Slab of Third floor   | 1d                | 13/6/2024        | 13/6/2024        | 11,880.00 EGP             |
| A5430                                 | Pouring for Slab of Third floor         | 3d                | 2/6/2024         | 4/6/2024         | 2,191,530.00 EGP          |
| A5420                                 | Steel Fixing for Slab of Third floor    | 11d               | 20/5/2024        | 1/6/2024         | 9,944,660.00 EGP          |
| A5410                                 | Shuttering for Slab of Third floor      | 6d                | 20/5/2024        | 26/5/2024        | 71,280.00 EGP             |
| <b>Marginal Beam for Third floor</b>  |                                         | <b>23d</b>        | <b>20/5/2024</b> | <b>15/6/2024</b> | <b>429,770.00 EGP</b>     |
| A5770                                 | De shuttering for marginal beam         | 2d                | 13/6/2024        | 15/6/2024        | 5,500.00 EGP              |
| A5760                                 | Pouring for marginal beam               | 3d                | 2/6/2024         | 4/6/2024         | 60,720.00 EGP             |
| A5750                                 | Steel Fixing for marginal beam          | 2d                | 20/5/2024        | 21/5/2024        | 360,800.00 EGP            |
| A5740                                 | Shuttering for marginal beam            | 2d                | 20/5/2024        | 21/5/2024        | 2,750.00 EGP              |
| <b>Stairs for Third Floor</b>         |                                         | <b>22d</b>        | <b>20/5/2024</b> | <b>13/6/2024</b> | <b>265,452.00 EGP</b>     |
| A5680                                 | De shuttering for Stairs of Third floor | 1d                | 13/6/2024        | 13/6/2024        | 2,750.00 EGP              |
| A5670                                 | Pouring for Stairs of Third floor       | 1d                | 2/6/2024         | 2/6/2024         | 13,970.00 EGP             |
| A5660                                 | Steel Fixing for Stairs of Third floor  | 1d                | 20/5/2024        | 20/5/2024        | 245,982.00 EGP            |
| Activity ID                           | Activity Name                           | Original Duration | Start            | Finish           | Budgeted Total Cost       |



|                                        |                                            |      |            |            |                    |
|----------------------------------------|--------------------------------------------|------|------------|------------|--------------------|
| A5650                                  | Shuttering for Stairs of Third floor       | 1d   | 20/5/2024  | 20/5/2024  | 2,750.00 EGP       |
| <b>Finishing Works for Third Floor</b> |                                            | 182d | 2/9/2024   | 3/4/2025   | 183,095,142.86 EGP |
| A5690                                  | Install Covering of Stairs for Third floor | 2d   | 2/4/2025   | 3/4/2025   | 116,377.80 EGP     |
| A5560                                  | Finishing Sanitary of Third floor          | 20d  | 10/3/2025  | 1/4/2025   | 1,243,597.00 EGP   |
| A5570                                  | Finishing HVAC System of Third floor       | 9d   | 25/2/2025* | 6/3/2025   | 49,958,056.98 EGP  |
| A5550                                  | Finishing Electrical of Third floor        | 20d  | 15/2/2025* | 9/3/2025   | 33,224,221.80 EGP  |
| A5580                                  | Finishing Fire Fighting System of Third    | 2d   | 30/12/2024 | 31/12/2024 | 9,746,781.00 EGP   |
| A5540                                  | Finishing Carpentry of Third floor         | 10d  | 30/12/2024 | 9/1/2025   | 4,412,262.00 EGP   |
| A5600                                  | Finishing Painting of Third floor          | 8d   | 21/12/2024 | 29/12/2024 | 1,320,000.00 EGP   |
| A5640                                  | Suspended Ceiling for Third Floor          | 10d  | 9/12/2024  | 19/12/2024 | 2,672,290.00 EGP   |
| A5620                                  | Thermal Insulation of Third Floor          | 1d   | 8/12/2024  | 8/12/2024  | 231,790.90 EGP     |
| A5610                                  | Moisture Insulation of Third Floor         | 1d   | 8/12/2024  | 8/12/2024  | 4,537,410.90 EGP   |
| A5520                                  | Primary Painting of Third floor            | 8d   | 28/11/2024 | 7/12/2024  | 660,000.00 EGP     |
| A5590                                  | Glass Work for Third floor                 | 2d   | 27/11/2024 | 28/11/2024 | 2,235,635.00 EGP   |
| A5490                                  | Metal Works of Third floor                 | 4d   | 23/11/2024 | 26/11/2024 | 459,290.00 EGP     |
| A5480                                  | Aluminum Works of Third floor              | 4d   | 23/11/2024 | 26/11/2024 | 1,182,943.70 EGP   |
| A5720                                  | Preliminary Fire Fighting Works of Thir    | 7d   | 20/11/2024 | 27/11/2024 | 11,616,000.00 EGP  |
| A5530                                  | Flooring of Third Floor                    | 12d  | 9/11/2024  | 21/11/2024 | 1,755,813.62 EGP   |
| A5500                                  | Preliminary HVAC System of Third floo      | 10d  | 9/11/2024  | 19/11/2024 | 22,305,371.40 EGP  |
| A5510                                  | Plastering of Third floor                  | 11d  | 27/10/2024 | 7/11/2024  | 2,710,102.19 EGP   |
| A5450                                  | Preliminary Carpentry Works of Third       | 10d  | 15/10/2024 | 26/10/2024 | 2,941,507.90 EGP   |
| A5460                                  | Preliminary Electrical Works of Third fl   | 10d  | 8/10/2024* | 19/10/2024 | 27,612,101.00 EGP  |
| A5700                                  | Preliminary Plastering of Third floor      | 2d   | 8/9/2024   | 9/9/2024   | 20,029.90 EGP      |
| A5470                                  | Preliminary Sanitary Works of Third flo    | 30d  | 8/9/2024   | 14/10/2024 | 829,053.50 EGP     |
| A5730                                  | Brick Works of Third floor                 | 5d   | 2/9/2024   | 7/9/2024   | 1,304,506.28 EGP   |
| <b>Fourth Floor Works</b>              |                                            | 266d | 16/6/2024  | 1/5/2025   | 201,326,876.23 EGP |
| <b>Concrete Works for Fourth floor</b> |                                            | 37d  | 16/6/2024  | 5/8/2024   | 17,214,912.00 EGP  |
| <b>Columns for Fourth floor</b>        |                                            | 14d  | 16/6/2024  | 7/7/2024   | 4,300,340.00 EGP   |
| A4580                                  | De shuttering for Columns of Fourth fl     | 1d   | 7/7/2024   | 7/7/2024   | 9,460.00 EGP       |
| A4570                                  | Pouring for Columns of Fourth floor        | 4d   | 1/7/2024   | 4/7/2024   | 674,960.00 EGP     |
| A4560                                  | Steel Fixing for Columns of Fourth floo    | 8d   | 16/6/2024  | 29/6/2024  | 3,559,160.00 EGP   |
| A4550                                  | Shuttering for Columns of Fourth floor     | 4d   | 16/6/2024  | 24/6/2024  | 56,760.00 EGP      |
| <b>Slab for Fourth floor</b>           |                                            | 22d  | 9/7/2024   | 4/8/2024   | 12,219,350.00 EGP  |
| A4620                                  | De shuttering for Slab of Fourth floor     | 1d   | 4/8/2024   | 4/8/2024   | 11,880.00 EGP      |
| A4610                                  | Pouring for Slab of Fourth floor           | 3d   | 22/7/2024  | 25/7/2024  | 2,191,530.00 EGP   |
| A4600                                  | Steel Fixing for Slab of Fourth floor      | 11d  | 9/7/2024   | 21/7/2024  | 9,944,660.00 EGP   |
| A4590                                  | Shuttering for Slab of Fourth floor        | 6d   | 9/7/2024   | 15/7/2024  | 71,280.00 EGP      |

| <b>Marginal Beam for Fourth floor</b>   |                                           | 23d               | 9/7/2024    | 5/8/2024   | 429,770.00 EGP      |
|-----------------------------------------|-------------------------------------------|-------------------|-------------|------------|---------------------|
| Activity ID                             | Activity Name                             | Original Duration | Start       | Finish     | Budgeted Total Cost |
| A4950                                   | De shuttering for marginal beam           | 2d                | 4/8/2024    | 5/8/2024   | 5,500.00 EGP        |
| A4940                                   | Pouring for marginal beam                 | 3d                | 22/7/2024   | 25/7/2024  | 60,720.00 EGP       |
| A4930                                   | Steel Fixing for marginal beam            | 2d                | 9/7/2024    | 10/7/2024  | 360,800.00 EGP      |
| A4920                                   | Shuttering for marginal beam              | 2d                | 9/7/2024    | 10/7/2024  | 2,750.00 EGP        |
| <b>Stairs for Fourth Floor</b>          |                                           | 22d               | 9/7/2024    | 4/8/2024   | 265,452.00 EGP      |
| A4860                                   | De shuttering for Stairs of Fourth floor  | 1d                | 4/8/2024    | 4/8/2024   | 2,750.00 EGP        |
| A4850                                   | Pouring for Stairs of Fourth floor        | 1d                | 22/7/2024   | 22/7/2024  | 13,970.00 EGP       |
| A4840                                   | Steel Fixing for Stairs of Fourth floor   | 1d                | 9/7/2024    | 9/7/2024   | 245,982.00 EGP      |
| A4830                                   | Shuttering for Stairs of Fourth floor     | 1d                | 9/7/2024    | 9/7/2024   | 2,750.00 EGP        |
| <b>Finishing Works for Fourth Floor</b> |                                           | 201d              | 8/9/2024    | 1/5/2025   | 184,111,964.23 EGP  |
| A4870                                   | Install Covering of Stairs for Fourth flo | 2d                | 30/4/2025   | 1/5/2025   | 116,377.80 EGP      |
| A4740                                   | Finishing Sanitary of Fourth floor        | 20d               | 7/4/2025    | 29/4/2025  | 1,243,597.00 EGP    |
| A4750                                   | Finishing HVAC System of Fourth floo      | 9d                | 5/4/2025*   | 14/4/2025  | 49,958,056.98 EGP   |
| A4730                                   | Finishing Electrical of Fourth floor      | 20d               | 15/3/2025*  | 6/4/2025   | 33,224,221.80 EGP   |
| A4760                                   | Finishing Fire Fighting System of Four    | 2d                | 13/1/2025   | 14/1/2025  | 9,746,781.00 EGP    |
| A4720                                   | Finishing Carpentry of Fourth floor       | 10d               | 13/1/2025   | 23/1/2025  | 4,412,262.00 EGP    |
| A4780                                   | Finishing Painting of Fourth floor        | 8d                | 4/1/2025    | 12/1/2025  | 1,320,000.00 EGP    |
| A4820                                   | Suspended Ceiling for Fourth Floor        | 10d               | 23/12/2024  | 2/1/2025   | 2,672,290.00 EGP    |
| A4800                                   | Thermal Insulation of Fourth Floor        | 1d                | 22/12/2024  | 22/12/2024 | 231,790.90 EGP      |
| A4790                                   | Moisture Insulation of Fourth Floor       | 1d                | 22/12/2024  | 22/12/2024 | 4,537,410.90 EGP    |
| A4700                                   | Primary Painting of Fourth floor          | 8d                | 12/12/2024  | 21/12/2024 | 660,000.00 EGP      |
| A4900                                   | Preliminary Fire Fighting Works of Fou    | 7d                | 4/12/2024   | 11/12/2024 | 11,616,000.00 EGP   |
| A4770                                   | Glass Work for Fourth floor               | 2d                | 26/11/2024  | 27/11/2024 | 2,235,635.00 EGP    |
| A4680                                   | Preliminary HVAC System of Fourth fl      | 10d               | 23/11/2024  | 3/12/2024  | 22,305,371.40 EGP   |
| A4670                                   | Metal Works of Fourth floor               | 4d                | 21/11/2024  | 25/11/2024 | 459,290.00 EGP      |
| A4660                                   | Aluminum Works of Fourth floor            | 4d                | 21/11/2024  | 25/11/2024 | 1,182,943.70 EGP    |
| A4710                                   | Flooring of Fourth Floor                  | 13d               | 6/11/2024   | 20/11/2024 | 1,801,507.18 EGP    |
| A4690                                   | Plastering of Fourth floor                | 14d               | 6/11/2024   | 21/11/2024 | 3,552,802.14 EGP    |
| A4640                                   | Preliminary Electrical Works of Fourth    | 10d               | 26/10/2024* | 5/11/2024  | 27,612,101.00 EGP   |
| A4630                                   | Preliminary Carpentry Works of Fourt      | 10d               | 23/10/2024  | 3/11/2024  | 2,941,507.90 EGP    |
| A4650                                   | Preliminary Sanitary Works of Fourth      | 30d               | 17/9/2024   | 22/10/2024 | 829,053.50 EGP      |
| A4880                                   | Preliminary Plastering of Fourth floor    | 2d                | 14/9/2024   | 15/9/2024  | 20,029.90 EGP       |
| A4910                                   | Brick Works of Fourth floor               | 5d                | 8/9/2024    | 12/9/2024  | 1,432,934.14 EGP    |
| <b>Roof works</b>                       |                                           | 209d              | 14/9/2024   | 17/5/2025  | 5,978,546.42 EGP    |
| <b>Finishing Works for Roof</b>         |                                           | 209d              | 14/9/2024   | 17/5/2025  | 5,978,546.42 EGP    |
| A3710                                   | Install Floor Cover for Roof              | 11d               | 5/5/2025    | 17/5/2025  | 817,442.73 EGP      |

| A3700                        | Thermal Insulation of Roof        | 3d                   | 1/5/2025   | 4/5/2025   | 236,556.10 EGP      |
|------------------------------|-----------------------------------|----------------------|------------|------------|---------------------|
| A3690                        | Moisture Insulation Roof          | 3d                   | 1/5/2025   | 4/5/2025   | 4,554,760.10 EGP    |
| A3790                        | Sanitary Works of Roof            | 0d                   | 30/4/2025  | 30/4/2025  | 0.00 EGP            |
| Tanta General Hospital-Final |                                   | 0-MENA BL Creat-Cost |            |            | 13/6/2024 12:22     |
| Activity ID                  | Activity Name                     | Original Duration    | Start      | Finish     | Budgeted Total Cost |
| A3770                        | Plastering of Roof                | 1d                   | 30/4/2025  | 30/4/2025  | 12,863.13 EGP       |
| A3780                        | Electrical Works of Roof          | 0d                   | 7/4/2025   | 7/4/2025   | 0.00 EGP            |
| A3760                        | Preliminary Plastering of Roof    | 2d                   | 23/11/2024 | 24/11/2024 | 10,701.90 EGP       |
| A3680                        | Brick Works of Roof               | 1d                   | 14/9/2024  | 14/9/2024  | 346,222.47 EGP      |
| <b>Elevators</b>             |                                   | 22d                  | 18/5/2025  | 11/6/2025  | 28,049,995.00 EGP   |
| A3370                        | Elevator Instaliation             | 7d                   | 4/6/2025   | 11/6/2025  | 550,000.00 EGP      |
| A3360                        | Elevator Works                    | 15d                  | 18/5/2025  | 3/6/2025   | 27,499,995.00 EGP   |
| <b>Parapets</b>              |                                   | 6d                   | 28/5/2025  | 3/6/2025   | 0.00 EGP            |
| A3750                        | Parapet Deshutter                 | 2d                   | 2/6/2025   | 3/6/2025   | 0.00 EGP            |
| A3740                        | Parapet Concrete Casting          | 1d                   | 29/5/2025  | 29/5/2025  | 0.00 EGP            |
| A3730                        | Parapet steel                     | 1d                   | 28/5/2025  | 28/5/2025  | 0.00 EGP            |
| A3720                        | Parapet Shutter                   | 2d                   | 28/5/2025  | 29/5/2025  | 0.00 EGP            |
| <b>Cladding Works</b>        |                                   | 5d                   | 18/5/2025  | 22/5/2025  | 49,280.00 EGP       |
| A3390                        | Glass Work for Cladding           | 1d                   | 22/5/2025  | 22/5/2025  | 21,120.00 EGP       |
| A3400                        | Aluminum Work for Cladding        | 1d                   | 21/5/2025  | 21/5/2025  | 7,040.00 EGP        |
| A3410                        | Artifical Stone Work for Cladding | 1d                   | 20/5/2025  | 20/5/2025  | 0.00 EGP            |
| A3380                        | Form Work for Cladding            | 1d                   | 19/5/2025  | 19/5/2025  | 21,120.00 EGP       |
| A3420                        | Release Form Work for Cladding    | 1d                   | 18/5/2025  | 18/5/2025  | 0.00 EGP            |
| <b>General Site</b>          |                                   | 15d                  | 24/5/2025  | 9/6/2025   | 7,323,250.00 EGP    |
| A3450                        | Agriculture Work for General Site | 1d                   | 9/6/2025   | 9/6/2025   | 0.00 EGP            |



## Chapter (13)

## Cash flow

### 13.1 Cash flow

measures how much cash a company takes in versus how much it expends. More cash coming in than going out means the cash flow is positive. If the opposite is true, the cash flow is negative.

A business is considered healthy when its cash flow is positive for a prolonged period of time. Even profitable businesses, however, can experience short periods of negative cash flow.

When a business has a negative cash flow for an extended period of time, it typically becomes insolvent and may need to declare bankruptcy.

Banks look at cash flow to help decide how much money they are willing to lend a company. They calculate EBITDA (earnings before deducting interest, taxes, depreciation and amortization) to measure cash coming in, and then deduct all contractual debt payments of principal and interest (cash expended) to determine the net cash flow.

Table . Cash Flow Analysis Calculations

|                  | 0           | 1              | 2              | 3              | 4              | 5              | 6              | 7              | 8              | 9              | 10             | 11             |
|------------------|-------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|
|                  | beginning   | March          | April          | May            | June           | July           | August         | September      | October        | November       | December       | January        |
| DC               | 0           | 40,673,015     | 25,654,112     | 11,903,069     | 11,335,760     | 13,578,862     | 11,332,452     | 5,959,350      | 13,967,742     | 6,806,330      | 13,578,862     | 32,289,679     |
| IC               | 0           | 5,287,492      | 3,335,035      | 1,547,399      | 1,473,649      | 1,765,252      | 1,473,219      | 774,716        | 1,815,806      | 884,823        | 1,765,252      | 4,197,658      |
| Total Cost       | 0           | 45,960,507     | 28,989,147     | 13,450,468     | 12,809,409     | 15,344,114     | 12,805,671     | 6,734,066      | 15,783,548     | 7,691,153      | 15,344,114     | 36,487,337     |
| Cum. Cost        | 0           | 45,960,507     | 74,949,654     | 88,400,121     | 101,209,530    | 116,553,644    | 129,359,315    | 136,093,380    | 151,876,929    | 159,568,082    | 174,912,196    | 211,399,533    |
| Cum. Expenses    | 0           | 45,960,507     | 74,949,654     | 88,400,121     | 101,209,530    | 116,553,644    | 129,359,315    | 136,093,380    | 151,876,929    | 159,568,082    | 174,912,196    | 211,399,533    |
| Revenue          |             | 50,556,557.65  | 31,888,061.22  | 14,795,514.38  | 14,090,349.68  | 16,878,525.47  | 14,086,237.84  | 7,407,472.05   | 17,361,903.31  | 8,460,268.19   | 16,878,525.47  | 40,136,070.96  |
| Retention        |             |                |                |                |                |                |                |                |                |                |                |                |
| advanced payment | 138,532,946 |                |                |                |                |                |                |                |                |                |                |                |
| Adjusted Revenue | 138,532,946 | 42,973,074.00  | 27,104,852.03  | 12,576,187.22  | 11,976,797.23  | 14,346,746.65  | 11,973,302.16  | 6,296,351.24   | 14,757,617.81  | 7,191,227.96   | 14,346,746.65  | 34,115,660.32  |
| Cum. Revenue     | 138,532,946 | 181,506,019.83 | 208,610,871.86 | 221,187,059.09 | 233,163,856.32 | 247,510,602.96 | 259,483,905.12 | 265,780,256.36 | 280,537,874.17 | 287,729,102.14 | 302,075,848.78 | 336,191,509.10 |
| Cum. Income      | 138,532,946 | 138,532,945.83 | 181,506,019.83 | 208,610,871.86 | 221,187,059.09 | 233,163,856.32 | 247,510,602.96 | 259,483,905.12 | 265,780,256.36 | 280,537,874.17 | 287,729,102.14 | 302,075,848.78 |
| Cash Before      | 138,532,946 | 92,572,438.88  | 63,583,292.32  | 93,105,898.70  | 107,401,341.93 | 104,633,415.10 | 103,804,541.57 | 111,417,222.71 | 107,606,976.41 | 106,212,174.75 | 105,625,678.50 | 76,329,569.23  |
| Cash After       |             |                | 106,556,366.32 | 120,210,750.73 | 119,977,529.16 | 116,610,212.33 | 118,151,288.21 | 123,390,524.87 | 113,903,327.65 | 120,969,792.56 | 112,816,906.47 | 90,676,315.88  |

|                  | 12             | 13             | 14              | 15              | 16               | 17               | 18               | 19               | 20               | 21               | 22               |
|------------------|----------------|----------------|-----------------|-----------------|------------------|------------------|------------------|------------------|------------------|------------------|------------------|
|                  | February       | March          | April           | May             | June             | July             | August           | September        | October          | November         | December         |
| DC               | 62,286,469     | 93,526,515     | 181,068,368     | 186,119,194     | 138,336,507      | 92,065,598       | 73,176,119       | 59,757,319       | 31,626,724       | 9,462,749        |                  |
| IC               | 8,097,241      | 12,158,447     | 23,538,888      | 24,195,495      | 17,983,746       | 11,968,528       | 9,512,895        | 7,768,451        | 4,111,474        | 1,230,157        |                  |
| Total Cost       | 70,383,710     | 105,684,962    | 204,607,256     | 210,314,689     | 156,320,253      | 104,034,125      | 82,689,014       | 67,525,771       | 35,738,198       | 10,692,906       |                  |
| Cum. Cost        | 281,783,243    | 387,468,205    | 592,075,461     | 802,390,150     | 958,710,402      | 1,062,744,528    | 1,145,433,542    | 1,212,959,312    | 1,248,697,510    | 1,259,390,417    | 1,259,390,417    |
| Cum. Expenses    | 281,783,243    | 387,468,205    | 592,075,461     | 802,390,150     | 958,710,402      | 1,062,744,528    | 1,145,433,542    | 1,212,959,312    | 1,248,697,510    | 1,259,390,417    | 1,259,390,417    |
| Revenue          | 77,422,080.69  | 116,253,458.15 | 225,067,982.01  | 231,346,157.53  | 171,952,278.01   | 114,437,537.99   | 90,957,915.35    | 74,278,347.65    | 39,312,017.72    | 11,762,197.01    |                  |
| Retention        |                |                |                 |                 |                  |                  |                  |                  |                  | 69,266,472.92    |                  |
| advanced payment |                |                |                 |                 |                  |                  |                  |                  |                  |                  |                  |
| Adjusted Revenue | 65,808,768.59  | 98,815,439.42  | 191,307,784.71  | 196,644,233.90  | 146,159,436.31   | 97,271,907.29    | 77,314,228.04    | 63,136,595.51    | 33,415,215.06    | 9,997,867.46     |                  |
| Cum. Revenue     | 402,000,277.69 | 500,815,717.11 | 692,123,501.82  | 888,767,735.72  | 1,034,927,172.03 | 1,132,199,079.33 | 1,209,513,307.37 | 1,272,649,902.87 | 1,306,065,117.94 | 1,316,062,985.39 | 1,316,062,985.39 |
| Cum. Income      | 336,191,509.10 | 402,000,277.69 | 500,815,717.11  | 692,123,501.82  | 888,767,735.72   | 1,034,927,172.03 | 1,132,199,079.33 | 1,209,513,307.37 | 1,272,649,902.87 | 1,306,065,117.94 | 1,316,062,985.39 |
| Cash Before      | 20,292,606.15  | -51,276,695.48 | -190,075,183.26 | -301,574,432.50 | -266,586,900.54  | -173,976,792.08  | -110,506,369.72  | -80,760,233.02   | -39,184,202.91   | 13,259,486.23    | 46,674,701.29    |
| Cash After       | 54,408,266.47  | 14,532,073.11  | -91,259,743.84  | -110,266,647.80 | -69,942,666.63   | -27,817,355.77   | -13,234,462.43   | -3,446,004.98    | 23,952,392.60    | 46,674,701.29    | 56,672,568.75    |




Figure . Cash Flow Curves (Cumulative Income & Expenses Curves)





Figure . Net Cash Flow Curve





## Chapter (14)

## **Project & Contract Pricing**

Because of the unique nature of constructed facilities, it is almost imperative to have a separate price for each facility. The construction contract price includes the direct project cost including field supervision expenses plus the markup imposed by contractors for general overhead expenses and profit. The factors influencing a facility price will vary by type of facility and location as well. Within each of the major categories of construction such as residential housing, commercial buildings, industrial complexes and infrastructure, there are smaller segments which have very different environments with regard to price setting. However, all pricing arrangements have some common features in the form of the legal documents binding the owner and the supplier(s) of the facility. Without addressing special issues in various industry segments, the most common types of pricing arrangements can be described broadly to illustrate the basic principles.

## Pricing

Table 22 Pricing

| Name of items    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Measuring unit | Cost of unit | Quantity | PRICE  |
|------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|--------------|----------|--------|
| Excavation       | In cubic metres, excavate the necessary foundations to any depth in all types of soil in accordance with the consultant's instructions and the soil research report. The category includes the removal of surface and groundwater, if any, and everything necessary to complete the work in accordance with the conditions and specifications and according to the principles of industry and engineering measurement according to the design drawings. The method of measurement has been clarified in the technical specifications for excavation and earthworks.                                                                                                                                                                                       | m3             | 45           | 13104    | 589680 |
| Soil replacement | In cubic metres, supply and implementation of a replacement layer of sand and sand At a ratio of 1:2, taking into account that the prescribed proportions are mixed well before backfilling the replacement soil and it is formed The layers are at a height of 25 cm, and the layers are compacted well with mash weighing no less than 10 tons In layers with a thickness of 25 cm for each layer after adding the necessary percentage of water to it (off-site) To reach the maximum dry density based on the modified Proctor experiment and not less than 95% of its value and in accordance with the instructions of the supervising engineer and everything necessary for this work according to Technical specifications and industry standards. | m3             | 400          | 1872     | 748800 |

|                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |    |      |      |          |
|--------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|------|----------|
| Back filling             | <p>In cubic metres, backfill around foundations and buildings using clean sand in layers<br/> Its height is more than 25 cm, with good compaction using mechanical compactors and good spraying<br/> With water to reach a relative blood level of no less than 95% of that sample according to the test<br/> Modified Proctor and these layers are made until the levels specified in the drawings are reached<br/> The category includes everything necessary to complete the work in accordance with the conditions and specifications and according to the rules<br/> Industry and engineering measurement.</p> | m3 | 37   | 2662 | 98494    |
| PC                       | <p>In cubic metres, supplying and pouring ordinary concrete for foundations<br/> Change it in the project with a cement content of no less than 250 kg/m3 so that the resistance does not decrease<br/> Pressure for its standard cubes must be no less than 200 kg/cm2 after 28 days of casting.<br/> This category includes weighing and leveling the bottom and surface of the concrete at the required level and compacting it well<br/> Spraying it with water after finishing it according to industry standards and technical specifications.</p>                                                            | m3 | 815  | 1248 | 1017120  |
| RC                       | <p>In cubic metres, supplying and pouring any new foundations needed for the project, including rooms on site<br/> General or any other foundations (0.8 oz., 0.4 m3 sand, 400+ kg Seawater cement<br/> (This category includes reinforcing steel of different diameters, and its standard cubes can withstand stress of no less than About 300 kg/cm2 after 28 days according to drawings and specifications, all of which are in cubic metres.</p>                                                                                                                                                                | m3 | 9487 | 8325 | 78979275 |
| Pouring of slab on grade | <p>By square metre, supply and pour a regular concrete pile for the building floors with a thickness of 10 cm<br/> The item includes everything necessary to complete the business in accordance with industry principles<br/> Technical specifications and instructions of the supervising engineer.</p>                                                                                                                                                                                                                                                                                                           | m2 | 803  | 1248 | 1002144  |

|                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |    |       |        |            |
|------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|-------|--------|------------|
| Insulation for RC Foundation | Per square metre, supply and paint hot bitumen in three faces for all structural elements<br>Adhering to the soil. According to specifications and industry principles, all in square metres.                                                                                                                                                                                                                                                                                                                                                                                  | m2 | 67    | 2660   | 178220     |
| Block under slab on grade    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | m3 | 253   | 2662   | 673486     |
| Columns                      | In cubic metres, supplying and pouring reinforced concrete for any new columns required for the works (0.8 m3 0.4 gravel + m3 sand + 400 kg ordinary Portland cement (the category includes rebar<br>Of different diameters, its standard cubes can withstand a stress of no less than 350 kg/cm2.<br>After 28 days according to the specifications, all in cubic metres.                                                                                                                                                                                                      | m3 | 12376 | 2159   | 26719784   |
| Slab & Stairs                | In cubic metres, supplying and pouring reinforced concrete for any slabs or slab beams<br>Solid slabs, which is necessary for any new rooms or any new concrete elements on the site<br>General (0.8 m3 gravel + 0.4 m3 sand + 350 kg ordinary Portland cement) and the category includes<br>Reinforcing steel of different diameters, its standard cubes can withstand a stress of no less than 350 kg/cm2 according to specifications, all of which are in cubic metres.                                                                                                     | m3 | 8387  | 9154.5 | 76778791.5 |
| Brick Works                  | In cubic metres, supplying and making brick buildings<br>25 x 12 x 6 cm (in bathrooms, the walls are up to a meter high The floor is made of solid cement bricks at the same price and the rest of the price<br>Clay bricks, 25 cm thick, according to the sample approved for supply and construction<br>With cement and sand mortar and finishing work, the item is charged with plastering<br>Of galvanized iron in the connection places between buildings, columns and everything else<br>The work must be completed in accordance with industry principles and technical | m3 | 252   | 41755  | 10522260   |

|                              |                                                                                                                                                                                       |         |  |   |            |
|------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|--|---|------------|
|                              | specifications<br>And the instructions of the consulting engineer.                                                                                                                    |         |  |   |            |
| Carpentry Works              | All carpentry works are carried out according to the specifications of the architectural carpentry works according to the Egyptian code.                                              | LUMPSUM |  | 1 | 45225685.5 |
| Electrical Works             | Wires ,Cables ,Feeders and related accessories: multicore copper cables PVC as shown on the drawings and specification including all required works such like manholes , civil works. | LUMPSUM |  | 1 | 374143387  |
| Sanitary Works & HVAC System | Suppling, Installing, connecting and testing of UPVC pipes and fitting above ground and under tiles with 6 bar completed with all accessories as per specification and drawings.      | LUMPSUM |  | 1 | 457166886  |
| Aluminum Works & Metal Works | All aluminum and metal works are carried out According to specifications Aluminum and metal works mentioned in the specifications and in accordance with the Egyptian code.           | LUMPSUM |  | 1 | 2019947.82 |

|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |         |     |          |            |
|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|-----|----------|------------|
| Plastering | <p>By square meter, supplying and making rough plastering for interior walls Interior ceilings are made from a general slab with mortar of 350 kg cement/m3 Sand and backing with a mortar consisting of cement and sand, 350 kg Cement/m3 sand with an average thickness of 2 cm and the category includes covering the seams between The connection of the concrete structure with the bricks with strips of expanded mesh is no less Its width is more than 10 cm, and it is fixed with galvanized nails on both sides according to the welding According to the specifications, the item also includes whitewashing in damaged areas with work The necessary treatment for it if it has cracks and making any necessary additions Of building materials. The item is comprehensive, all of which are measured by flat meters and according to the instructions Consulting engineer. The measurement is geometric.</p> | m2      | 287 | 68307.34 | 19604205.4 |
| Painting   | <p>By square meter, supplying and making plastic paints for walls or ceilings Based on acrylic, such as Cricut, produced by a local company such as: Skip, Jotun, or similar modern building chemicals, according to the sample Approved from three sides other than the preparatory side in the required color In accordance with industry principles and standard specifications. The item is charged It requires preparing the surface with an abrasive material such as Silcoat 101 or something Similar items, and the item includes all of them in square metres, in accordance with the instructions Consulting engineer.</p>                                                                                                                                                                                                                                                                                      | LUMPSUM |     | 1        | 12177000   |

|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |         |     |       |            |
|----------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|-----|-------|------------|
| Flooring             | Supply and installation of ceramic floor tiles produced by Al-Gawhara companies Cleopatra or similar, taking into account the regularity of the floor tiles with The walls and brackets are loaded with watering cans filled with anti-bacteria according to the requirements Excellent industry principles and in accordance with technical specifications and instructions The consultant and the approved sample.                                                                                                                                                                                                                                                       | m2      | 352 | 42967 | 15124384   |
| Fire Fighting System | All Fire Fighting System are carried out According to specifications Fire Fighting System mentioned in the specifications and in accordance with the Egyptian code.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | LUMPSUM |     | 1     | 131381103  |
| Glass Work           | By flat metre, supply and installation of thick securit glass partitions 10 mm and sanded the item in some parts according to the instructions The consultant also includes all necessary accessories For installation according to the consultant's instructions and the item is comprehensive, all of which are per metre Flat and according to the consultant's instructions.                                                                                                                                                                                                                                                                                           | LUMPSUM |     | 1     | 13749155.3 |
| Moisture Insulation  | By square metre, supply and installation of insulation for bathrooms, roof and floor The ground floor consists of a layer of Innocent 3000N coil, 3 mm thick or Bitonil or something similar, which is installed in Bashbouri and according to industry standards. Production of enzymes or something similar. The price includes making a plastered cement plaster The bottom is 3 cm thick, as well as a 3 cm cement plaster on top for protection, as well as Overalls 30cm high and measured according to horizontal projection. According to specifications The clause is comprehensive of all of them, in accordance with the instructions of the consulting mentor. | m2      | 970 | 34558 | 33521260   |



|                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                |     |      |            |
|----------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-----|------|------------|
| Thermal Insulation         | By square metre, supply and installation of a heat insulating layer of polycarbonate panels<br>Styrene manufactured by extrusion method with a thickness of less than 5 cm and the price includes<br>Make a cement plaster over it with a thickness of 3 cm, and the item includes all of them. In metres flat and according to the instructions of the consulting engineer.                                                                                                                                                                                                                                                                                                                                                                                                             | m2             | 223 | 7723 | 1722229    |
| Suspended Ceilling         | By flat metre, supply and installation of artificial ceilings made of gypsum boards GYPSUM BOARD (first class fire resistance), produced by a company Knauf, Lafarge, Saint-Gobain, or similar, complete with suspension system and price<br>It includes making the necessary openings and entries for lighting units and exits Air conditioning, etc., as well as the required inspection doors in coordination with the rest<br>Works and bearing on the item putty and acrylic paints and lining<br>The final color is in the required color until the work is completed according to the rules<br>Industry. According to drawings, specifications, engineering measurement, and the item is comprehensive<br>Of all of it. According to the instructions of the consulting engineer. | LUMPSUM        |     | 1    | 16434583.5 |
| Install Covering of Stairs | By linear metre, supply and installation of granite staircase cladding<br>Gray or colored according to the consultant's instructions, with a thickness of 4 cm and slate<br>2 cm of skirting, the height of the post and the width of the sleeper, and a bearing on it<br>Braking or hammering with a 4cm wide blade according to approved samples and a bearing<br>The item includes runners for the stairs and also made a skirting board with a height of up to 20 cm<br>And finish the work in accordance with industry standards and specifications, in accordance with instructions<br>Consulting engineer.                                                                                                                                                                        | m <sup>2</sup> | 852 | 840  | 715680     |

|                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |         |  |   |                   |
|---------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|--|---|-------------------|
| Elevator Works                              | Supply, Install, testing, commissioning, maintenance and guarantee of the following elevators all in accordance with the tender drawings, specifications (Division 14) and the latest technology provided by one of the following elevators.                                                                                                                                                                                                                                                    | LUMPSUM |  | 1 | 34501500          |
| Cladding                                    | All Cladding works are carried out According to specifications Cladding works mentioned in the specifications and in accordance with the Egyptian code.                                                                                                                                                                                                                                                                                                                                         | LUMPSUM |  | 1 | 60614.4           |
| Road Paving Works for General Site          | Per square meter, supply and installation of interlock tiles for street cars Rectangular and in the colors approved by the consultant and according to the operating drawings With a thickness of not less than 8 cm, the item includes a layer of clean, fine sand Well tamped under the tiles with a thickness of 8 cm according to the specifications and drawings The item includes all of it, and the item includes all of it, in flat meters and accordingly For consultant instructions. | LUMPSUM |  | 1 | 4197682.5         |
| Installing interlock Tiles for General Site | Per square metre, supply and installation of rectangular garden interlocks 10*20 cm With a thickness of not less than 6 cm or according to the consultant's instructions. The item includes a layer Of clean, soft sand, well tamped under the tiles, 8 cm thick For specifications, drawings and the item is comprehensive of all of them.                                                                                                                                                     | LUMPSUM |  | 1 | 4809915           |
|                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |         |  |   | <b>1363863273</b> |

## **References:**

- ✚ Prof .Dr. Amr ElKholy, Construction Project Management Lecture Notes.
- ✚ Prof .Dr. Emad Elbeltagi, Construction Project Management Lecture Notes.
- ✚ Conditions of Contractor Construction (FIDIC99)
- ✚ PMI. (2017). A Guide to the Project Management Body of Knowledge 6. Project Management Institute, USA.
- ✚ Introduction to Health and Safety Management Systems Program Development Guideline - EDITION 1.
- ✚ HSG150 (Third edition, published 2006) - Health and safety in construction
- ✚ Handbook of OSHA Construction Safety and Health Second Edition
- ✚ Communication and Collaboration in Project Management – Introduction – Project Management Hut". Pmhut.com. 17 February 2010
- ✚ <https://www.project-management.pm/portfolio-management/portfolio-communication-management/>
- ✚ <https://www.apm.org.uk/body-of-knowledge/delivery/financial-cost-management/>
- ✚ <https://www.projectmanagement.com/wikis/465221/Project-Cash-Flow->
- ✚ [https://onlinelibrary.wiley.com/doi/10.1002/9781118802342.ch2.](https://onlinelibrary.wiley.com/doi/10.1002/9781118802342.ch2)
- ✚ <https://study.com/academy/lesson/project-quality-management-definition-example.html> .